

# Alabama Department of Environmental Management adem.alabama.gov

1400 Coliseum Blvd. 36110-2400 Post Office Box 301463

APRIL 1, 2021

Montgomery, Alabama 36130-1463 (334) 271-7700 FAX (334) 271-7950

MEREDITH BRUICK SITE LEADER DC ALABAMA, INC. 1940 OHIO FERRO ROAD MOUNT MEIGS AL 36057

RE: REVISED DRAFT PERMIT MODIFICATION NPDES PERMIT NUMBER AL0083763

Dear Ms. Bruick:

Transmitted herein is a revised draft of the referenced permit modification.

We would appreciate your comments on the permit within 30 days of the date of this letter. Please direct any comments of a technical or administrative nature to the undersigned.

By copy of this letter and the draft permit, we are also requesting comments within the same time frame from EPA.

Our records indicate that you are currently utilizing the Department's web-based electronic environmental (E2) reporting system for submittal of discharge monitoring reports (DMRs). Your E2 DMRs will automatically update on the effective date of this permit, if issued.

The Alabama Department of Environmental Management encourages you to voluntarily consider pollution prevention practices and alternatives at your facility. Pollution Prevention may assist you in complying with effluent limitations, and possibly reduce or eliminate monitoring requirements.

If you have questions regarding this permit or monitoring requirements, please contact Scott Jackson by e-mail at scott.jackson@adem.alabama.gov or by phone at (334) 394-4366.

Sincerel

Scott Ramsey, Chief Industrial Section Industrial/Municipal Branch Water Division

Enclosure:

Draft Permit

pc via website:

Montgomery Field Office

EPA Region IV

U.S. Fish & Wildlife Service AL Historical Commission

Advisory Council on Historic Preservation

Department of Conservation and Natural Resources





# NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT

PERMITTEE: DC ALABAMA, INC.

FACILITY LOCATION: DC ALABAMA, INC.

1940 OHIO FERRO ROAD MOUNT MEIGS, AL 36057

PERMIT NUMBER: AL0083763

RECEIVING WATERS: DSN001-DSN003: UNNAMED TRIBUTARY TO MILLER CREEK

**DSN004: TALLAPOOSA RIVER** 

In accordance with and subject to the provisions of the Federal Water Pollution Control Act, as amended, 33 U.S.C. §\$1251-1388 (the 'FWPCA''), the Alabama Water Pollution Control Act, as amended, Code of Alabama 1975, §\$12-22-1 to 22-22-14 (the "AWPCA"), the Alabama Environmental Management Act, as amended, Code of Alabama 1975, §\$12-22A-1 to 22-22A-17, and rules and regulations adopted thereunder, and subject further to the terms and conditions set forth in this permit, the Permittee is hereby authorized to discharge into the above-named receiving waters.

ISSUANCE DATE: NOVEMBER 19, 2018

EFFECTIVE DATE: DECEMBER 1, 2018

EXPIRATION DATE: NOVEMBER 30, 2023

MODIFICATION ISSUED DATE:

MODIFICATION EFFECTIVE DATE:



# INDUSTRIAL SECTION NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) PERMIT

#### TABLE OF CONTENTS

PART I	DISCHARGE LIMITATIONS, CONDITIONS, AND REQUIREMENTS	1
A.	DISCHARGE LIMITATIONS AND MONITORING REQUIREMENTS	1
В.	DISCHARGE MONITORING AND RECORD KEEPING REQUIREMENTS	12
	1. Representative Sampling	12
	2. Test Procedures	12
	Recording of Results      Records Retention and Production	
	5. Monitoring Equipment and Instrumentation.	13
C.	DISCHARGE REPORTING REQUIREMENTS	
	1. Reporting of Monitoring Requirements	
	2. Noncompliance Notification	
D.	OTHER REPORTING AND NOTIFICATION REQUIREMENTS	
	I. Anticipated Noncompliance	15
	Termination of Discharge     Updating Information	15 16
	4. Duty to Provide Information	
	5. Cooling Water and Boiler Water Additives	16
	6. Permit Issued Based On Estimated Characteristics	
E.	SCHEDULE OF COMPLIANCE	
PART II	OTHER REQUIREMENTS, RESPONSIBILITIES, AND DUTIES	
A.	OPERATIONAL AND MANAGEMENT REQUIREMENTS	
	Facilities Operation and Maintenance      Best Management Practices	
	Spill Prevention, Control, and Management	18
В.	OTHER RESPONSIBILITIES	
	1. Duty to Mitigate Adverse Impacts	
	2. Right of Entry and Inspection	18
C.	BYPASS AND UPSET	
	1. Bypass	
_	2. Upset	
D.	DUTY TO COMPLY WITH PERMIT, RULES, AND STATUTES	
	1. Duty to Comply	19 - 19
	3. Loss or Failure of Treatment Facilities	20
	4. Compliance with Statutes and Rules	
E.	PERMIT TRANSFER, MODIFICATION, SUSPENSION, REVOCATION, AND REISSUANCE	
	Duty to Reapply or Notify of Intent to Cease Discharge	20
	Change in Discharge     Transfer of Permit.	21
	4. Permit Modification and Revocation	21
	5. Permit Termination	
	6. Permit Suspension	22
F.	COMPLIANCE WITH TOXIC POLLUTANT STANDARD OR PROHIBITION	
G.	DISCHARGE OF WASTEWATER GENERATED BY OTHERS	22
PART III	OTHER PERMIT CONDITIONS	23
A.	CIVIL AND CRIMINAL LIABILITY	23
B.	OIL AND HAZARDOUS SUBSTANCE LIABILITY	23
C.	PROPERTY AND OTHER RIGHTS	
D.	AVAILABILITY OF REPORTS	
E.	EXPIRATION OF PERMITS FOR NEW OR INCREASED DISCHARGES	
F.	COMPLIANCE WITH WATER QUALITY STANDARDS	
G.	GROUNDWATER	
H.	DEFINITIONS	
I.	SEVERABILITY	
PART IV	ADDITIONAL REQUIREMENTS, CONDITIONS, AND LIMITATIONS	
, <b>A</b> .	BEST MANAGEMENT PRACTICES (BMP) PLAN REQUIREMENTS	
В.	STORMWATER FLOW MEASUREMENT AND SAMPLING REQUIREMENTS	
C.	ACUTE TOXICITY LIMITATIONS AND BIOMONITORING REQUIREMENTS (DSN004)	
D.	CHRONIC TOXICITY LIMITATIONS AND BIOMONITORING REQUIREMENTS (DSN002)	
E.	COOLING WATER INTAKE REQUIREMENTS	35

#### PART I DISCHARGE LIMITATIONS, CONDITIONS, AND REQUIREMENTS

#### A. DISCHARGE LIMITATIONS AND MONITORING REQUIREMENTS

During the period beginning on the effective date of this permit and lasting through the expiration date of this permit, the permittee is authorized to discharge from the following point source(s) outfall(s), described more fully in the permittee's application:

DSN001Q: Uncontaminated groundwater and stormwater run-off associated with silicon metal manufacturing, 3/4/

Such discharge shall be limited and monitored by the permittee as specified below:

Such discharge shart of minted and mor		LIMITATIONS				MONITORING I	REQUIREMENTS 1/	
EFFLUENT CHARACTERISTIC pH	Monthly Average -	<u>Daily</u> <u>Maximum</u> -	<u>Daily</u> <u>Minimum</u> REPORT S.U.	<u>Monthly</u> <u>Average</u> -	<u>Daily</u> <u>Maximum</u> REPORT S.U.	Measurement Frequency 2/ Quarterly	<u>Sample Type</u> Grab	<u>Seasonal</u> -
Solids, Total Suspended	-	-	-	REPORT mg/l	REPORT mg/l	Quarterly	Grab	-
Oil & Grease	•	-	-	-	15.0 mg/i	Quarterly	Grab	-
Arsenic, Total (As As)	-	-	-	-	REPORT mg/l	Quarterly	Grab	-
Chromium, Total (As Cr)	-	-	-	-	REPORT mg/l	Quarterly	Grab	~
Copper, Total (As Cu)	-	-	-	-	REPORT mg/l	Quarterly	Grab	•
Lead, Total (As Pb)	-	-	-	-	REPORT mg/l	Quarterly	Grab	-
Nickel, Total (As Ni)	-	-	-	-	REPORT mg/l	Quarterly	Grab	-

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ See Part IV.A for Best Management Practices (BMP) Plan Requirements.
- 4/ See Part IV.B for Stormwater Measurement and Sampling Requirements.

DSN001Q (continued): Uncontaminated groundwater and stormwater run-off associated with silicon metal manufacturing. 3/4/

Such discharge shall be limited and monitored by the permittee as specified below:

<b></b>	DISCHARGE	LIMITATIONS	3			MONITORING I	REQUIREMENTS 1/	
	Monthly	<u>Daily</u>	<u>Daily</u>	<b>Monthly</b>	<u>Daily</u>	Measurement		
EFFLUENT CHARACTERISTIC	Average	<u>Maximum</u>	<u>Minimum</u>	<u>Average</u>	<u>Maximum</u>	Frequency 2/	Sample Type	<u>Seasonal</u>
Aluminum, Total (As Al)	•	-	-	-	REPORT mg/l	Quarterly	Grab	-
Selenium, Total (As Se)	-	-	-	-	REPORT mg/l	Quarterly	Grab	-
Bis (2-Ethylhexyl) Phthalate 5/	-	-	-	-	REPORT ug/l	Quarterly	Grab	-
Flow, In Conduit or Thru Treatment Plant	REPORT MGD	REPORT MGD	-	-	-	Quarterly	Instantaneous	-
Solids, Total Dissolved	-	-	-	-	REPORT mg/l	Quarterly	Grab	-

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ See Part IV.A for Best Management Practices (BMP) Plan Requirements.
- 4/ See Part IV.B for Stormwater Measurement and Sampling Requirements.
- 5/ The facility should monitor for Bis (2-Ethylhexyl) Phthalate at this outfall once per quarter until there have been 4 consecutive below detection samples. Monitoring for this parameter at this outfall will no longer be required after 4 consecutive quarterly below detection monitoring results, unless otherwise notified by the Department. If monitoring is not applicable during a monitoring period, the parameter should be marked with "\*9" on the discharge monitoring report.

DSN0021: Process wastewater associated with silicon metal manufacturing and treated silica fume slurry discharging to U.T. to Miller Creek.

Such discharge shall be limited and monitored by the permittee as specified below:

2	DISCHARGE	LIMITATIONS	3			<b>MONITORING</b>	REQUIREMENTS 1/	
EFFLUENT CHARACTERISTIC Oxygen, Dissolved (DO)	Monthly Average	<u>Daily</u> <u>Maximum</u> -	<u>Daily</u> <u>Minimum</u> 6.0 mg/l	Monthly Average	<u>Daily</u> <u>Maximum</u> -	Measurement Frequency 2/ Weekly	<u>Sample Type</u> Grab	Seasonal -
рН	-	-	6.0 S.U.	-	8.5 S.U.	Weekly	Grab	-
Solids, Total Suspended	-	-	-	30.0 mg/l	60.0 mg/l	Weekly	Composite	-
Oil & Grease	-	-	-	. <del>-</del>	15.0 mg/l	Weekly	Grab	-
Nitrogen, Ammonia Total (As N)	•	-	-	0.4 mg/l	0,6 mg/l	Weekly	Composite	~
Selenium, Total Recoverable 3/	-	-	-	0,005 mg/1	0.020 mg/l	Weekly	Composite	-
Thailium, Total Recoverable 3/	-	-	-	0.274 ug/l	0.548 ug/l	Weekly	Composite	-
Lead, Total (As Pb)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ For the purpose of demonstration of compliance with this parameter, "Total" and "Total Recoverable" shall be considered equivalent.

DSN0021 (continued): Process wastewater associated with silicon metal manufacturing and treated silica fume slurry to U.T. to Miller Creek.

Such discharge shall be limited and monitored by the permittee as specified below:

Euri disente Be same de amme de ma	DISCHARGE		<b>MONITORING I</b>	REQUIREMENTS 1/				
EFFLUENT CHARACTERISTIC Nickel, Total (As Ni)	Monthly Average	<u>Daily</u> <u>Maximum</u> -	<u>Daily</u> <u>Minimum</u> -	Monthly Average REPORT mg/l	<u>Daily</u> <u>Maximum</u> REPORT mg/l	Measurement Frequency 2/ Weekly	Sample Type Composite	Seasonal -
Zinc Total Recoverable 3/	-	-	-	0.197 mg/l	0.197 mg/l	Weekly	Composite	~
Antimony, Total (As Sb)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-
Copper Total Recoverable 3/	-	-	-	0.0128 mg/l	0.0180 mg/l	Weekly	Composite	-
Arsenic, Trivalent Dissolved	-	-	-	0.303 ug/l	0.60 <b>6</b> ug/l	Weekly	Composite	-
Flow, In Conduit or Thru Treatment Plant	REPORT MGD	RE <b>P</b> ORT MGD	-	-	-	Daily	Totalizer	-
BOD, Carbonaceous 05 Day, 20C	-	-	-	6.0 mg/l	9.0 mg/l	Weekly	Grab	-
Chemical Oxygen Demand (COD)	-	-	-	-	REPORT mg/l	Weekly	Grab	-

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ For the purpose of demonstration of compliance with this parameter, "Total" and "Total Recoverable" shall be considered equivalent.

DSN002Q: Process wastewater associated with silicon metal manufacturing and treated silica fume slurry discharging to U.T. to Miller Creek.

Such discharge shall be limited and monitored by the permittee as specified below:

	DISCHARGE	LIMITATIONS	2			MUNITURING	CEQUIREMENTS I	
	Monthly	<u>Daily</u>	<u>Daily</u>	<u>Monthly</u>	<u>Daily</u>	Measurement		
EFFLUENT CHARACTERISTIC	Average	Maximum	<u>Minimum</u>	<u>Average</u>	<u>Maximum</u>	Frequency 2/	Sample Type	<u>Seasonal</u>
Bis (2-Ethylhexyl) Phthalate 3/	-	-	-	1.28 ug/l	2.56 ug/l	Quarterly	Grab	-

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ The facility should monitor for Bis (2-Ethylhexyl) Phthalate at this outfall once per quarter until there have been 4 consecutive below detection samples. Monitoring for this parameter at this outfall will no longer be required after 4 consecutive quarterly below detection monitoring results, unless otherwise notified by the Department. If monitoring is not applicable during a monitoring period, the parameter should be marked with "\*9" on the discharge monitoring report.

DSN002T: Process wastewater associated with silicon metal manufacturing and treated silica fume slurry discharging to U.T. to Miller Creek. 3/

Such discharge shall be limited and monitored by the permittee as specified below:

	DISCHARGI	<u>ELIMITATIONS</u>				MONITORING R	REQUIREMENTS 1/	
	Monthly	<u>Daily</u>	<u>Daily</u>	<u>Monthly</u>	<u>Daily</u>	<u>Measurement</u>		
EFFLUENT CHARACTERISTIC	Average	<u>Maximum</u>	<u>Minimum</u>	<u>Average</u>	<u>Maximum</u>	Frequency 2/	Sample Type	<u>Seasonal</u>
Toxicity, Ceriodaphnia Chronic	-	0 pass(0)/fail(1)	-	-	-	Quarterly	Composite	~
Toxicity, Pimephales Chronic	-	0 pass(0)/fail(1)	-	-	-	Quarterly	Composite	-

# THE DISCHARGE SHALL HAVE NO SHEEN, AND THERE SHALL BE NO DISCHARGE OF VISIBLE OIL, FLOATING SOLIDS OR VISIBLE FOAM IN OTHER THAN TRACE AMOUNTS.

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ See Part IV.D for Chronic Toxicity Requirements.

2.

DSN003Q: Non-contact cooling wastewater associated with silicon metal manufacturing.

Such discharge shall be limited and monitored by the permittee as specified below:

	DISCHARGE	LIMITATIONS	<u>s</u>			MONITORING I	REQUIREMENTS 1/	
EFFLUENT CHARACTERISTIC Temperature, Water Deg. Fahrenheit	Monthly Average	<u>Daily</u> <u>Maximum</u> -	<u>Daily</u> <u>Minimum</u> -	Monthly Average	<u>Daily</u> <u>Maximum</u> 90 F	Measurement Frequency 2/ Quarterly	<u>Sample Type</u> Grab	<u>Seasonal</u> -
рН	-	-	6.0 S.U.	-	8.5 S.U.	Quarterly	Grab.	-
Flow, In Conduit or Thru Treatment Plant	-	REPORT MGD	•	-	-	Quarterly	Instantaneous	-
Chlorine, Total Residual 3/	-	-	-	0.011 mg/l	0.019 mg/l	Quarterly	Grab	-

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ A measurement of Total Residual Chlorine below 0.05 mg/L shall be considered in compliance with the permit limitations above and should be reported as NODI=B or \*B on the discharge monitoring reports.

DSN0041: Process wastewater and stormwater run-off associated with silicon metal manufacturing and treated silica fume slurry discharging to the Tallapoosa River. 3/

Such discharge shall be limited and monitored by the permittee as specified below:

<b>.</b>	DISCHARGE	<u>LIMITATIONS</u>	3			MONITORING 1	REQUIREMENTS 1/	
EFFLUENT CHARACTERISTIC	<u>Monthly</u> <u>Average</u>	<u>Daily</u> <u>Maximum</u>	<u>Daily</u> Minimum	Monthly Average	<u>Daily</u> Maximu <u>m</u>	Measurement Frequency 2/	Sample Type	Seasonal
Oxygen, Dissolved (DO)	-	-	REPORT mg/l	-	-	Weekly	Grab	-
pН	-	-	6.0 S.U.	-	9.0 S.U.	Weekly	Grab	-
Solids, Total Suspended	-	•	-	30.0 mg/l	60.0 mg/l	Weekly	Composite	-
Oil & Grease	•	-	-	-	15.0 mg/l	Weekly	Grab	-
Nitrogen, Ammonia Total (As N)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-
Arsenic, Total (As As)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-
Copper, Total (As Cu)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-
Lead, Total (As Pb)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ See Part IV.A for Best Management Practices (BMP) Plan Requirements.

DSN0041 (continued): Process wastewater and stormwater run-off associated with silicon metal manufacturing and treated silica fume slurry discharging to the Tallapoosa River. 3/

Such discharge shall be limited and monitored by the permittee as specified below:

<b>24-01-20-01-01-20-01-01-20-01</b>	DISCHARGE		MONITORING I	REQUIREMENTS 1/	ne Seasonal			
	Monthly	<u>Daily</u>	<u>Daily</u>	<b>Monthly</b>	<u>Daily</u>	Measurement	· · · · · · · · · · · · · · · · · · ·	
EFFLUENT CHARACTERISTIC	<u>Average</u>	<u>Maximum</u>	<u>Minimum</u>	<u>Average</u>	<u>Maximum</u>	Frequency 2/	Sample Type	<u>Seasonal</u>
Thallium, Total (As Tl)	-	•	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-
Nickel, Total (As Ni)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-
Zinc, Total (As Zn)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-
Antimony, Total (As Sb)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-
Selenium, Total (As Se)	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Composite	-
Flow, In Conduit or Thru Treatment Plant	REPORT MGD	REPORT MGD	-	•	-	Daily	Totalizer	-
BOD, Carbonaceous 05 Day, 20C	-	-	-	REPORT mg/l	REPORT mg/l	Weekly	Grab	-
Chemical Oxygen Demand (COD)	-	-	-	-	REPORT mg/l	Monthly	Grab	-

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ See Part IV.A for Best Management Practices (BMP) Plan Requirements.

DSN004Q: Process wastewater and stormwater run-off associated with silicon metal manufacturing and treated silica fume slurry discharging to the Tallapoosa River.

Such discharge shall be limited and monitored by the permittee as specified below:

	DISCHARGE	<u>LIMITATIONS</u>	<u>}</u>			MONITORING I	REQUIREMENTS 1/	
	Monthly	<u>Daily</u>	<u>Daily</u>	<u>Monthly</u>	<u>Daily</u>	Measurement		
EFFLUENT CHARACTERISTIC	Average	<u>Maximum</u>	<u>Minimum</u>	Average	<u>Maximum</u>	Frequency 2/	Sample Type	<u>Seasonal</u>
Bis (2-Ethylhexyl) Phthalate 3/	-	-	-	-	REPORT	Quarterly	Grab	-
					ug/l			

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ The facility should monitor for Bis (2-Ethylhexyl) Phthalate at this outfall once per quarter until there have been 4 consecutive below detection samples. Monitoring for this parameter at this outfall will no longer be required after 4 consecutive quarterly below detection monitoring results, unless otherwise notified by the Department. If monitoring is not applicable during a monitoring period, the parameter should be marked with "\*9" on the discharge monitoring report.

DSN004T: Process wastewater and stormwater run-off associated with silicon metal manufacturing and treated silica fume slurry discharging to the Tallapoosa River. 3/

Such discharge shall be limited and monitored by the permittee as specified below:

	DISCHARGE	<u>LIMITATIONS</u>		•		MONITORING I	REQUIREMENTS 1/	
	<u>Monthly</u>	<u>Daily</u>	<u>Daily</u>	<u>Monthly</u>	<u>Daily</u>	<u>Measurement</u>		
EFFLUENT CHARACTERISTIC	Average	<u>Maximum</u>	Minimum	<u>Average</u>	<u>Maximum</u>	Frequency 2/	Sample Type	<u>Seasonal</u>
Toxicity, Ceriodaphnia Acute	-	0 pass(0)/fail(1)	-	-	-	Quarterly	Grab	-
Toxicity, Pimephales Acute	-	0 pass(0)/fail(1)	-	-	-	Quarterly	Grab	-

- 1/ Samples collected to comply with the monitoring requirements specified above shall be collected at the following location: At the nearest accessible location just prior to discharge and after final treatment. Unless otherwise specified, composite samples shall be time composite samples collected using automatic sampling equipment or a minimum of eight (8) equal volume grab samples collected over equal time intervals. All composite samples shall be collected for the total period of discharge not to exceed 24 hours.
- 2/ If only one sampling event occurs during a month, the sample result shall be reported on the discharge monitoring report as both the monthly average and daily maximum value for all parameters with a monthly average limitation.
- 3/ See Part IV.C for Acute Toxicity Requirements.

#### B. DISCHARGE MONITORING AND RECORD KEEPING REQUIREMENTS

### 1. Representative Sampling

Samples and measurements taken as required herein shall be representative of the volume and nature of the monitored discharge and shall be in accordance with the provisions of this permit.

#### 2. Test Procedures

For the purpose of reporting and compliance, permittees shall use one of the following procedures:

- a. For parameters with an EPA established Minimum Level (ML), report the measured value if the analytical result is at or above the ML and report "0" for values below the ML. Test procedures for the analysis of pollutants shall conform to 40 CFR Part 136 and guidelines published pursuant to Section 304(h) of the FWPCA, 33 U.S.C. Section 1314(h). If more than one method for analysis of a substance is approved for use, a method having a minimum level lower than the permit limit shall be used. If the minimum level of all methods is higher than the permit limit, the method having the lowest minimum level shall be used and a report of less than the minimum level shall be reported as zero and will constitute compliance; however, should EPA approve a method with a lower minimum level during the term of this permit the permittee shall use the newly approved method.
- b. For pollutants parameters without an established ML, an interim ML may be utilized. The interim ML shall be calculated as 3.18 times the Method Detection Level (MDL) calculated pursuant to 40 CFR Part 136, Appendix B.

Permittees may develop an effluent matrix-specific ML, where an effluent matrix prevents attainment of the established ML. However, a matrix specific ML shall be based upon proper laboratory method and technique. Matrix-specific MLs must be approved by the Department, and may be developed by the permittee during permit issuance, reissuance, modification, or during compliance schedule.

In either case the measured value should be reported if the analytical result is at or above the ML and "0" reported for values below the ML.

c. For parameters without an EPA established ML, interim ML, or matrix-specific ML, a report of less than the detection limit shall constitute compliance if the detection limit of all analytical methods is higher than the permit limit using the most sensitive EPA approved method. For the purpose of calculating a monthly average, "0" shall be used for values reported less than the detection limit.

The Minimum Level utilized for procedures A and B above shall be reported on the permittee's DMR. When an EPA approved test procedure for analysis of a pollutant does not exist, the Director shall approve the procedure to be used.

## 3. Recording of Results

For each measurement or sample taken pursuant to the requirements of this permit, the permittee shall record the following information:

- a. The facility name and location, point source number, date, time and exact place of sampling;
- b. The name(s) of person(s) who obtained the samples or measurements;
- c. The dates and times the analyses were performed;
- d. The name(s) of the person(s) who performed the analyses;
- e. The analytical techniques or methods used, including source of method and method number; and
- f. The results of all required analyses.

#### 4. Records Retention and Production

The permittee shall retain records of all monitoring information, including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by the permit, and records of all data used to complete the above reports or the application for this permit, for a period of at least three years from the date of the sample measurement, report or application. This period may be extended by request of the Director at any time. If litigation or other enforcement action, under the AWPCA and/or the FWPCA, is ongoing which involves any of the above records, the records shall be kept until the litigation is resolved. Upon the written request of the Director or his designee, the permittee shall provide the Director with a copy of any record required to be retained by this paragraph. Copies of these records shall not be submitted unless requested.

All records required to be kept for a period of three years shall be kept at the permitted facility or an alternate location approved by the Department in writing and shall be available for inspection.

5. Monitoring Equipment and Instrumentation

All equipment and instrumentation used to determine compliance with the requirements of this permit shall be installed, maintained, and calibrated in accordance with the manufacturer's instructions or, in the absence of manufacturer's instructions, in accordance with accepted practices. The permittee shall develop and maintain quality assurance procedures to ensure proper operation and maintenance of all equipment and instrumentation. The quality assurance procedures shall include the proper use, maintenance, and installation, when appropriate, of monitoring equipment at the plant site.

# C. DISCHARGE REPORTING REQUIREMENTS

- Reporting of Monitoring Requirements
  - a. The permittee shall conduct the required monitoring in accordance with the following schedule:

MONITORING REQUIRED MORE FREQUENTLY THAN MONTHLY AND MONTHLY shall be conducted during the first full month following the effective date of coverage under this permit and every month thereafter.

QUARTERLY MONITORING shall be conducted at least once during each calendar quarter. Calendar quarters are the periods of January through March, April through June, July through September, and October through December. The permittee shall conduct the quarterly monitoring during the first complete calendar quarter following the effective date of this permit and is then required to monitor once during each quarter thereafter. Quarterly monitoring may be done anytime during the quarter, unless restricted elsewhere in this permit, but it should be submitted with the last DMR due for the quarter, i.e., (March, June, September and December DMR's).

SEMIANNUAL MONITORING shall be conducted at least once during the period of January through June and at least once during the period of July through December. The permittee shall conduct the semiannual monitoring during the first complete calendar semiannual period following the effective date of this permit and is then required to monitor once during each semiannual period thereafter. Semiannual monitoring may be done anytime during the semiannual period, unless restricted elsewhere in this permit, but it should be submitted with the last DMR for the month of the semiannual period, i.e. (June and December DMR's).

ANNUAL MONITORING shall be conducted at least once during the period of January through December. The permittee shall conduct the annual monitoring during the first complete calendar annual period following the effective date of this permit and is then required to monitor once during each annual period thereafter. Annual monitoring may be done anytime during the year, unless restricted elsewhere in this permit, but it should be submitted with the December DMR.

b. The permittee shall submit discharge monitoring reports (DMRs) on the forms provided by the Department and in accordance with the following schedule:

REPORTS OF MORE FREQUENTLY THAN MONTHLY AND MONTHLY TESTING shall be submitted on a monthly basis. The first report is due on the 28th day of January, 2019. The reports shall be submitted so that they are received by the Department no later than the 28th day of the month following the reporting period.

REPORTS OF QUARTERLY TESTING shall be submitted on a quarterly basis. The first report is due on the 28th day of April, 2019. The reports shall be submitted so that they are received by the Department no later than the 28th day of the month following the reporting period.

- c. Except as allowed by Provision I.C.1.c.(1) or (2), the permittee shall submit all Discharge Monitoring Reports (DMRs) required by Provision I.C.1.b by utilizing the Department's web-based Electronic Environmental (E2) Reporting System.
  - (1) If the permittee is unable to complete the electronic submittal of DMR data due to technical problems originating with the Department's E2 Reporting system (this could include entry/submittal issues with an entire set of DMRs or individual parameters), the permittee is not relieved of their obligation to submit DMR data to the Department by the date specified in Provision I.C.1.b, unless otherwise directed by the Department.

If the E2 Reporting System is down on the 28th day of the month in which the DMR is due or is down for an extended period of time, as determined by the Department, when a DMR is required to be submitted, the permittee may submit the data in an alternate manner and format acceptable to the Department. Preapproved alternate acceptable methods include faxing, e-mailing, mailing, or hand-delivery of data such that they are received by the required reporting date. Within 5 calendar days of the E2 Reporting System resuming operation, the permittee shall enter the data into the E2 Reporting System, unless an alternate timeframe is approved by the Department. An attachment should be included with the E2 DMR submittal verifying the

- original submittal date (date of the fax, copy of the dated e-mail, or hand-delivery stamped date), if applicable.
- The permittee may submit a request to the Department for a temporary electronic reporting waiver for DMR submittals. The waiver request should include the permit number; permittee name; facility/site name; facility address; name, address, and contact information for the responsible official or duly authorized representative; a detailed statement regarding the basis for requesting such a waiver; and the duration for which the waiver is requested. Approved electronic reporting waivers are not transferrable.
  - Permittees with an approved electronic reporting waiver for DMRs may submit hard copy DMRs for the period that the approved electronic reporting waiver request is effective. The permittee shall submit the Department-approved DMR forms to the address listed in Provision I.C.1.e.
- (3) If a permittee is allowed to submit a hard copy DMR, the DMR must be legible and bear an original signature. Photo and electronic copies of the signature are not acceptable and shall not satisfy the reporting requirements of this permit.
- (4) If the permittee, using approved analytical methods as specified in Provision I.B.2, monitors any discharge from a point source for a limited substance identified in Provision I.A. of this permit more frequently than required by this permit, the results of such monitoring shall be included in the calculation and reporting of values on the DMR and the increased frequency shall be indicated on the DMR.
- (5) In the event no discharge from a point source identified in Provision I.A. of this permit and described more fully in the permittee's application occurs during a monitoring period, the permittee shall report "No Discharge" for such period on the appropriate DMR.
- d. All reports and forms required to be submitted by this permit, the AWPCA and the Department's Rules, shall be electronically signed (or, if allowed by the Department, traditionally signed) by a "responsible official" of the permittee as defined in ADEM Administrative Code Rule 335-6-6-.09 or a "duly authorized representative" of such official as defined in ADEM Administrative Code Rule 335-6-6-.09 and shall bear the following certification:
  - "I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations."
- e. Discharge Monitoring Reports required by this permit, the AWPCA, and the Department's Rules that are being submitted in hard copy shall be addressed to:

Alabama Department of Environmental Management
Permits and Services Division
Environmental Data Section
Post Office Box 301463
Montgomery, Alabama 36130-1463

Certified and Registered Mail containing Discharge Monitoring Reports shall be addressed to:

Alabama Department of Environmental Management
Permits and Services Division
Environmental Data Section
1400 Coliseum Boulevard
Montgomery, Alabama 36110-2400

f. All other correspondence and reports required to be submitted by this permit, the AWPCA, and the Department's Rules shall be addressed to:

Alabama Department of Environmental Management
Water Division
Post Office Box 301463
Montgomery, Alabama 36130-1463

Certified and Registered Mail shall be addressed to:

Alabama Department of Environmental Management
Water Division

## 1400 Coliseum Boulevard Montgomery, Alabama 36110-2400

g. If this permit is a re-issuance, then the permittee shall continue to submit DMRs in accordance with the requirements of their previous permit until such time as DMRs are due as discussed in Part I.C.1.b above.

#### 2. Noncompliance Notification

a. 24-Hour Noncompliance Reporting

The permittee shall report to the Director, within 24-hours of becoming aware of the noncompliance, any noncompliance which may endanger health or the environment. This shall include but is not limited to the following circumstances:

- (1) does not comply with any daily minimum or maximum discharge limitation for an effluent characteristic specified in Provision I. A. of this permit which is denoted by an "(X)";
- (2) threatens human health or welfare, fish or aquatic life, or water quality standards;
- does not comply with an applicable toxic pollutant effluent standard or prohibition established under Section 307(a) of the FWPCA, 33 U.S.C. Section 1317(a);
- (4) contains a quantity of a hazardous substance which has been determined may be harmful to public health or welfare under Section 311(b)(4) of the FWPCA, 33 U.S.C. Section 1321(b)(4);
- (5) exceeds any discharge limitation for an effluent characteristic as a result of an unanticipated bypass or upset; and
- (6) is an unpermitted direct or indirect discharge of a pollutant to a water of the state (unpermitted discharges properly reported to the Department under any other requirement are not required to be reported under this provision).

The permittee shall orally report the occurrence and circumstances of such discharge to the Director within 24-hours after the permittee becomes aware of the occurrence of such discharge. In addition to the oral report, the permittee shall submit to the Director or Designee a written report as provided in Part I.C.2.c no later than five (5) days after becoming aware of the occurrence of such discharge.

- b. If for any reason, the permittee's discharge does not comply with any limitation of this permit, the permittee shall submit to the Director or Designee a written report as provided in Part I.C.2.c below, such report shall be submitted with the next Discharge Monitoring Report required to be submitted by Part I.C.1 of this permit after becoming aware of the occurrence of such noncompliance.
- c. Any written report required to be submitted to the Director or Designee by Part I.C.2 a. or b. shall be submitted using a Noncompliance Notification Form (ADEM Form 421) available on the Department's website (<a href="http://adem.alabama.gov/DeptForms/Form421.pdf">http://adem.alabama.gov/DeptForms/Form421.pdf</a>) and include the following information:
  - (1) A description of the discharge and cause of noncompliance;
  - (2) The period of noncompliance, including exact dates and times or, if not corrected, the anticipated time the noncompliance is expected to continue; and
  - (3) A description of the steps taken and/or being taken to reduce or eliminate the noncomplying discharge and to prevent its recurrence.

# D. OTHER REPORTING AND NOTIFICATION REQUIREMENTS

1. Anticipated Noncompliance

The permittee shall give the Director written advance notice of any planned changes or other circumstances regarding a facility which may result in noncompliance with permit requirements.

2. Termination of Discharge

The permittee shall notify the Director, in writing, when all discharges from any point source(s) identified in Provision I. A. of this permit have permanently ceased. This notification shall serve as sufficient cause for instituting procedures for modification or termination of the permit.

#### Updating Information

- a. The permittee shall inform the Director of any change in the permittee's mailing address, telephone number or in the permittee's designation of a facility contact or office having the authority and responsibility to prevent and abate violations of the AWPCA, the Department's Rules, and the terms and conditions of this permit, in writing, no later than ten (10) days after such change. Upon request of the Director or his designee, the permittee shall furnish the Director with an update of any information provided in the permit application.
- b. If the permittee becomes aware that it failed to submit any relevant facts in a permit application, or submitted incorrect information in a permit application or in any report to the Director, it shall promptly submit such facts or information with a written explanation for the mistake and/or omission.

#### Duty to Provide Information

The permittee shall furnish to the Director, within a reasonable time, any information which the Director or his designee may request to determine whether cause exists for modifying, revoking and re-issuing, suspending, or terminating this permit, in whole or in part, or to determine compliance with this permit.

## 5. Cooling Water and Boiler Water Additives

- a. The permittee shall notify the Director in writing not later than thirty (30) days prior to instituting the use of any biocide corrosion inhibitor or chemical additive in a cooling or boiler system, not identified in the application for this permit, from which discharge is allowed by this permit. Notification is not required for additives that do not contain a heavy metal(s) as an active ingredient and that pass through a wastewater treatment system prior to discharge nor is notification required for additives that should not reasonably be expected to cause the cooling water or boiler water to exhibit toxicity as determined by analysis of manufacturer's data or testing by the permittee. Such notification shall include:
  - name and general composition of biocide or chemical;
  - (2) 96-hour median tolerance limit data for organisms representative of the biota of the waterway into which the discharge will ultimately reach;
  - (2) quantities to be used;
  - (3) frequencies of use;
  - (4) proposed discharge concentrations; and
  - (6) EPA registration number, if applicable.
- b. The use of a biocide or additive containing tributyl tin, tributyl tin oxide, zinc, chromium or related compounds in cooling or boiler system(s), from which a discharge regulated by this permit occurs, is prohibited except as exempted below. The use of a biocide or additive containing zinc, chromium or related compounds may be used in special circumstances if (1) the permit contains limits for these substances, or (2) the applicant demonstrates during the application process that the use of zinc, chromium or related compounds as a biocide or additive will not pose a reasonable potential to violate the applicable State water quality standards for these substances. The use of any additive, not identified in this permit or in the application for this permit or not exempted from notification under this permit is prohibited, prior to a determination by the Department that permit modification to control discharge of the additive is not required or prior to issuance of a permit modification controlling discharge of the additive.

#### Permit Issued Based On Estimated Characteristics

- a. If this permit was issued based on estimates of the characteristics of a process discharge reported on an EPA NPDES Application Form 2D (EPA Form 3510-2D), the permittee shall complete and submit an EPA NPDES Application Form 2C (EPA Form 3510-2C) no later than two years after the date that discharge begins. Sampling required for completion of the Form 2C shall occur when a discharge(s) from the process(s) causing the new or increased discharge is occurring. If this permit was issued based on estimates concerning the composition of a stormwater discharge(s), the permittee shall perform the sampling required by EPA NPDES Application Form 2F (EPA Form 3510-2F) no later than one year after the industrial activity generating the stormwater discharge has been fully initiated.
- b. This permit shall be reopened if required to address any new information resulting from the completion and submittal of the Form 2C and or 2F.

#### E. SCHEDULE OF COMPLIANCE

1. The permittee shall achieve compliance with the discharge limitations specified in Provision I. A. in accordance with the following schedule:

#### COMPLIANCE SHALL BE ATTAINED ON THE EFFECTIVE DATE OF THIS PERMIT

No later than 14 calendar days following a date identified in the above schedule of compliance, the permittee shall submit either a report of progress or, in the case of specific actions being required by identified dates, a written notice of compliance or noncompliance. In the latter case, the notice shall include the cause of noncompliance, any remedial actions taken, and the probability of meeting the next scheduled requirement.

## PART II OTHER REQUIREMENTS, RESPONSIBILITIES, AND DUTIES

#### A. OPERATIONAL AND MANAGEMENT REQUIREMENTS

#### 1. Facilities Operation and Maintenance

The permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the permittee to achieve compliance with the conditions of the permit. Proper operation and maintenance includes effective performance, adequate funding, adequate operator staffing and training, and adequate laboratory and process controls, including appropriate quality assurance procedures. This provision requires the operation of backup or auxiliary facilities only when necessary to achieve compliance with the conditions of the permit.

#### 2. Best Management Practices

- a. Dilution water shall not be added to achieve compliance with discharge limitations except when the Director or his designee has granted prior written authorization for dilution to meet water quality requirements.
- b. The permittee shall prepare, implement, and maintain a Spill Prevention, Control and Countermeasures (SPCC) Plan in accordance with 40 C.F.R. Section 112 if required thereby.
- c. The permittee shall prepare, submit for approval and implement a Best Management Practices (BMP) Plan for containment of any or all process liquids or solids, in a manner such that these materials do not present a significant potential for discharge, if so required by the Director or his designee. When submitted and approved, the BMP Plan shall become a part of this permit and all requirements of the BMP Plan shall become requirements of this permit.

#### 3. Spill Prevention, Control, and Management

The permittee shall provide spill prevention, control, and/or management sufficient to prevent any spills of pollutants from entering a water of the state or a publicly or privately owned treatment works. Any containment system used to implement this requirement shall be constructed of materials compatible with the substance(s) contained and which shall prevent the contamination of groundwater and such containment system shall be capable of retaining a volume equal to 110 percent of the capacity of the largest tank for which containment is provided.

#### B. OTHER RESPONSIBILITIES

#### 1. Duty to Mitigate Adverse Impacts

The permittee shall promptly take all reasonable steps to mitigate and minimize or prevent any adverse impact on human health or the environment resulting from noncompliance with any discharge limitation specified in Provision I. A. of this permit, including such accelerated or additional monitoring of the discharge and/or the receiving waterbody as necessary to determine the nature and impact of the noncomplying discharge.

# 2. Right of Entry and Inspection

The permittee shall allow the Director, or an authorized representative, upon the presentation of proper credentials and other documents as may be required by law to:

- a. enter upon the permittee's premises where a regulated facility or activity or point source is located or conducted, or where records must be kept under the conditions of the permit;
- b. have access to and copy, at reasonable times, any records that must be kept under the conditions of the permit;
- e. inspect any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under the permit; and
- d. sample or monitor, for the purposes of assuring permit compliance or as otherwise authorized by the AWPCA, any substances or parameters at any location.

# C. BYPASS AND UPSET

### 1. Bypass

- a. Any bypass is prohibited except as provided in b. and c. below:
- b. A bypass is not prohibited if:
  - (1) It does not cause any discharge limitation specified in Provision I. A. of this permit to be exceeded;

- (2) It enters the same receiving stream as the permitted outfall; and
- (3) It is necessary for essential maintenance of a treatment or control facility or system to assure efficient operation of such facility or system.
- c. A bypass is not prohibited and need not meet the discharge limitations specified in Provision I. A. of this permit if:
  - (1) It is unavoidable to prevent loss of life, personal injury, or severe property damage;
  - (2) There are no feasible alternatives to the bypass, such as the use of auxiliary treatment facilities, retention of untreated wastes, or maintenance during normal periods of equipment downtime (this condition is not satisfied if adequate back-up equipment should have been installed in the exercise of reasonable engineering judgment to prevent a bypass which occurred during normal periods of equipment downtime or preventive maintenance); and
  - (3) The permittee submits a written request for authorization to bypass to the Director at least ten (10) days prior to the anticipated bypass (if possible), the permittee is granted such authorization, and the permittee complies with any conditions imposed by the Director to minimize any adverse impact on human health or the environment resulting from the bypass.
- d. The permittee has the burden of establishing that each of the conditions of Provision II.C.1.b. or c. have been met to qualify for an exception to the general prohibition against bypassing contained in a. and an exemption, where applicable, from the discharge limitations specified in Provision I. A. of this permit.

# 2. Upset

- a. A discharge which results from an upset need not meet the discharge limitations specified in Provision I. A. of this permit if:
  - (1) No later than 24-hours after becoming aware of the occurrence of the upset, the permittee orally reports the occurrence and circumstances of the upset to the Director or his designee; and
  - (2) No later than five (5) days after becoming aware of the occurrence of the upset, the permittee furnishes the Director with evidence, including properly signed, contemporaneous operating logs, or other relevant evidence, demonstrating that (i) an upset occurred; (ii) the permittee can identify the specific cause(s) of the upset; (iii) the permittee's facility was being properly operated at the time of the upset; and (iv) the permittee promptly took all reasonable steps to minimize any adverse impact on human health or the environment resulting from the upset.
- b. The permittee has the burden of establishing that each of the conditions of Provision II. C.2.a. of this permit have been met to qualify for an exemption from the discharge limitations specified in Provision I.A. of this permit.

# D. DUTY TO COMPLY WITH PERMIT, RULES, AND STATUTES

- 1. Duty to Comply
  - a. The permittee must comply with all conditions of this permit. Any permit noncompliance constitutes a violation of the AWPCA and the FWPCA and is grounds for enforcement action, for permit termination, revocation and reissuance, suspension, modification; or denial of a permit renewal application.
  - b. The necessity to halt or reduce production or other activities in order to maintain compliance with the conditions of the permit shall not be a defense for a permittee in an enforcement action.
  - c. The discharge of a pollutant from a source not specifically identified in the permit application for this permit and not specifically included in the description of an outfall in this permit is not authorized and shall constitute noncompliance with this permit.
  - d. The permittee shall take all reasonable steps, including cessation of production or other activities, to minimize or prevent any violation of this permit or to minimize or prevent any adverse impact of any permit violation.
  - e. Nothing in this permit shall be construed to preclude and negate the permittee's responsibility or liability to apply for, obtain, or comply with other ADEM, Federal, State, or Local Government permits, certifications, licenses, or other approvals.

# 2. Removed Substances

Solids, sludges, filter backwash, or any other pollutant or other waste removed in the course of treatment or control of wastewaters shall be disposed of in a manner that complies with all applicable Department Rules.

#### 3. Loss or Failure of Treatment Facilities

Upon the loss or failure of any treatment facilities, including but not limited to the loss or failure of the primary source of power of the treatment facility, the permittee shall, where necessary to maintain compliance with the discharge limitations specified in Provision I. A. of this permit, or any other terms or conditions of this permit, cease, reduce, or otherwise control production and/or all discharges until treatment is restored. If control of discharge during loss or failure of the primary source of power is to be accomplished by means of alternate power sources, standby generators, or retention of inadequately treated effluent, the permittee must furnish to the Director within six months a certification that such control mechanisms have been installed.

#### 4. Compliance with Statutes and Rules

- a. This permit has been issued under ADEM Administrative Code, Chapter 335-6-6. All provisions of this chapter, that are applicable to this permit, are hereby made a part of this permit. A copy of this chapter may be obtained for a small charge from the Office of General Counsel, Alabama Department of Environmental Management, 1400 Coliseum Blvd., Montgomery, AL 36130.
- b. This permit does not authorize the noncompliance with or violation of any Laws of the State of Alabama or the United States of America or any regulations or rules implementing such laws. FWPCA, 33 U.S.C. Section 1319, and Code of Alabama 1975, Section 22-22-14.

# E. PERMIT TRANSFER, MODIFICATION, SUSPENSION, REVOCATION, AND REISSUANCE

- Duty to Reapply or Notify of Intent to Cease Discharge
  - a. If the permittee intends to continue to discharge beyond the expiration date of this permit, the permittee shall file a complete permit application for reissuance of this permit at least 180 days prior to its expiration. If the permittee does not intend to continue discharge beyond the expiration of this permit, the permittee shall submit written notification of this intent which shall be signed by an individual meeting the signatory requirements for a permit application as set forth in ADEM Administrative Code Rule 335-6-6-0.99.
  - b. Failure of the permittee to apply for reissuance at least 180 days prior to permit expiration will void the automatic continuation of the expiring permit provided by ADEM Administrative Code Rule 335-6-6-.06 and should the permit not be reissued for any reason any discharge after expiration of this permit will be an unpermitted discharge.

## 2. Change in Discharge

- a. The permittee shall apply for a permit modification at least 180 days in advance of any facility expansion, production increase, process change, or other action that could result in the discharge of additional pollutants or increase the quantity of a discharged pollutant such that existing permit limitations would be exceeded or that could result in an additional discharge point. This requirement applies to pollutants that are or that are not subject to discharge limitations in this permit. No new or increased discharge may begin until the Director has authorized it by issuance of a permit modification or a reissued permit.
- b. The permittee shall notify the Director as soon as it is known or there is reason to believe:
  - That any activity has occurred or will occur which would result in the discharge on a routine or frequent basis, of any toxic pollutant which is not limited in this permit, if that discharge will exceed the highest of the following notification levels:
    - (a) one hundred micrograms per liter;
    - (b) two hundred micrograms per liter for acrolein and acrylonitrile; five hundred micrograms per liter for 2,4-dinitrophenol and for 2-methyl-4,6-dini-trophenol; and one milligram per liter for antimony;
    - (c) five times the maximum concentration value reported for that pollutant in the permit application; or
  - (2) That any activity has occurred or will occur which would result in any discharge, on a non-routine or infrequent basis, of a toxic pollutant which is not limited in the permit, if that discharge will exceed the highest of the following notification levels:
    - (a) five hundred micrograms per liter;
    - (b) one milligram per liter for antimony;
    - (c) ten times the maximum concentration value reported for that pollutant in the permit application.

#### Transfer of Permit

This permit may not be transferred or the name of the permittee changed without notice to the Director and subsequent modification or revocation and reissuance of the permit to identify the new permittee and to incorporate any other changes as may be required under the FWPCA or AWPCA. In the case of a change in name, ownership or control of the permittee's premises only, a request for permit modification in a format acceptable to the Director is required at least 30 days prior to the change. In the case of a change in name, ownership or control of the permittee's premises accompanied by a change or proposed change in effluent characteristics, a complete permit application is required to be submitted to the Director at least 180 days prior to the change. Whenever the Director is notified of a change in name, ownership or control, he may decide not to modify the existing permit and require the submission of a new permit application.

#### 4. Permit Modification and Revocation

- a. This permit may be modified or revoked and reissued, in whole or in part, during its term for cause, including but not limited to, the following:
  - (1) If cause for termination under Provision II. E. 5. of this permit exists, the Director may choose to revoke and reissue this permit instead of terminating the permit;
  - (2) If a request to transfer this permit has been received, the Director may decide to revoke and reissue or to modify the permit; or
  - (3) If modification or revocation and reissuance is requested by the permittee and cause exists, the Director may grant the request.
- b. This permit may be modified during its term for cause, including but not limited to, the following:
  - (1) If cause for termination under Provision II. E. 5. of this permit exists, the Director may choose to modify this permit instead of terminating this permit;
  - (2) There are material and substantial alterations or additions to the facility or activity generating wastewater which occurred after permit issuance which justify the application of permit conditions that are different or absent in the existing permit;
  - (3) The Director has received new information that was not available at the time of permit issuance and that would have justified the application of different permit conditions at the time of issuance;
  - (4) A new or revised requirement(s) of any applicable standard or limitation is promulgated under Sections 301(b)(2)(C), (D), (E), and (F), and 307(a)(2) of the FWPCA;
  - (5) Errors in calculation of discharge limitations or typographical or clerical errors were made;
  - (6) To the extent allowed by ADEM Administrative Code, Rule 335-6-6-.17, when the standards or regulations on which the permit was based have been changed by promulgation of amended standards or regulations or by judicial decision after the permit was issued;
  - (7) To the extent allowed by ADEM Administrative Code, Rule 335-6-6-.17, permits may be modified to change compliance schedules;
  - (8) To agree with a granted variance under 30l(c), 30l(g), 30l(h), 30l(k), or 3l6(a) of the FWPCA or for fundamentally different factors;
  - (9) To incorporate an applicable 307(a) FWPCA toxic effluent standard or prohibition;
  - (10) When required by the reopener conditions in this permit;
  - (11) When required under 40 CFR 403.8(e) (compliance schedule for development of pretreatment program);
  - (12) Upon failure of the state to notify, as required by Section 402(b)(3) of the FWPCA, another state whose waters may be affected by a discharge permitted by this permit;
  - (13) When required to correct technical mistakes, such as errors in calculation, or mistaken interpretations of law made in determining permit conditions; or
  - When requested by the permittee and the Director determines that the modification has cause and will not result in a violation of federal or state law, regulations or rules.

#### 5. Permit Termination

This permit may be terminated during its term for cause, including but not limited to, the following:

- a. Violation of any term or condition of this permit;
- b. The permittee's misrepresentation or failure to disclose fully all relevant facts in the permit application or during the permit issuance process or the permittee's misrepresentation of any relevant facts at any time;
- c. Materially false or inaccurate statements or information in the permit application or the permit;
- d. A change in any condition that requires either a temporary or permanent reduction or elimination of the permitted discharge;
- e. The permittee's discharge threatens human life or welfare or the maintenance of water quality standards;
- f. Permanent closure of the facility generating the wastewater permitted to be discharged by this permit or permanent cessation of wastewater discharge;
- g. New or revised requirements of any applicable standard or limitation that is promulgated under Sections 301(b)(2)(C), (D), (E), and (F), and 307(a)(2) of the FWPCA that the Director determines cannot be complied with by the permittee; or
- h. Any other cause allowed by the ADEM Administrative Code, Chapter 335-6-6.

## 6. Permit Suspension

This permit may be suspended during its term for noncompliance until the permittee has taken action(s) necessary to achieve compliance.

7. Request for Permit Action Does Not Stay Any Permit Requirement

The filing of a request by the permittee for modification, suspension or revocation of this permit, in whole or in part, does not stay any permit term or condition.

## F. COMPLIANCE WITH TOXIC POLLUTANT STANDARD OR PROHIBITION

If any applicable effluent standard or prohibition (including any schedule of compliance specified in such effluent standard or prohibition) is established under Section 307(a) of the FWPCA, 33 U.S.C. Section 1317(a), for a toxic pollutant discharged by the permittee and such standard or prohibition is more stringent than any discharge limitation on the pollutant specified in Provision I. A. of this permit, or controls a pollutant not limited in Provision I. A. of this permit, this permit shall be modified to conform to the toxic pollutant effluent standard or prohibition and the permittee shall be notified of such modification. If this permit has not been modified to conform to the toxic pollutant effluent standard or prohibition before the effective date of such standard or prohibition, the permittee shall attain compliance with the requirements of the standard or prohibition within the time period required by the standard or prohibition and shall continue to comply with the standard or prohibition until this permit is modified or reissued.

# G. DISCHARGE OF WASTEWATER GENERATED BY OTHERS

The discharge of wastewater, generated by any process, facility, or by any other means not under the operational control of the permittee or not identified in the application for this permit or not identified specifically in the description of an outfall in this permit is not authorized by this permit.

#### PART III OTHER PERMIT CONDITIONS

#### A. CIVIL AND CRIMINAL LIABILITY

#### 1. Tampering

Any person who falsifies, tampers with, or knowingly renders inaccurate any monitoring device or method required to be maintained or performed under the permit shall, upon conviction, be subject to penalties as provided by the AWPCA.

#### 2. False Statements

Any person who knowingly makes any false statement, representation, or certification in any record or other document submitted or required to be maintained under this permit, including monitoring reports or reports of compliance or noncompliance shall, upon conviction, be subject to penalties as provided by the AWPCA.

#### 3. Permit Enforcement

- a. Any NPDES permit issued or reissued by the Department is a permit for the purpose of the AWPCA and the FWPCA and as such any terms, conditions, or limitations of the permit are enforceable under state and federal law.
- b. Any person required to have a NPDES permit pursuant to ADEM Administrative Code Chapter 335-6-6 and who discharges pollutants without said permit, who violates the conditions of said permit, who discharges pollutants in a manner not authorized by the permit, or who violates applicable orders of the Department or any applicable rule or standard of the Department, is subject to any one or combination of the following enforcement actions under applicable state statutes.
  - (1) An administrative order requiring abatement, compliance, mitigation, cessation, clean-up, and/or penalties;
  - (2) An action for damages;
  - (3) An action for injunctive relief; or
  - (4) An action for penalties.
- c. If the permittee is not in compliance with the conditions of an expiring or expired permit the Director may choose to do any or all of the following provided the permittee has made a timely and complete application for reissuance of the permit:
  - (1) initiate enforcement action based upon the permit which has been continued;
  - issue a notice of intent to deny the permit reissuance. If the permit is denied, the owner or operator would then be required to cease the activities authorized by the continued permit or be subject to enforcement action for operating without a permit;
  - (3) reissue the new permit with appropriate conditions; or
  - (4) take other actions authorized by these rules and AWPCA.

## 4. Relief from Liability

Except as provided in Provision II.C.1 (Bypass) and Provision II.C.2 (Upset), nothing in this permit shall be construed to relieve the permittee of civil or criminal liability under the AWPCA or FWPCA for noncompliance with any term or condition of this permit.

#### B. OIL AND HAZARDOUS SUBSTANCE LIABILITY

Nothing in this permit shall be construed to preclude the institution of any legal action or relieve the permittee from any responsibilities, liabilities or penalties to which the permittee is or may be subject under Section 311 of the FWPCA, 33 U.S.C. Section 1321.

# C. PROPERTY AND OTHER RIGHTS

This permit does not convey any property rights in either real or personal property, or any exclusive privileges, nor does it authorize any injury to persons or property or invasion of other private rights, trespass, or any infringement of federal, state, or local laws or regulations, nor does it authorize or approve the construction of any physical structures or facilities or the undertaking of any work in any waters of the state or of the United States.

#### D. AVAILABILITY OF REPORTS

Except for data determined to be confidential under <u>Code of Alabama</u> 1975, Section 22-22-9(c), all reports prepared in accordance with the terms of this permit shall be available for public inspection at the offices of the Department. Effluent data shall not be considered confidential.

#### E. EXPIRATION OF PERMITS FOR NEW OR INCREASED DISCHARGES

- 1. If this permit was issued for a new discharger or new source, this permit shall expire eighteen months after the issuance date if construction of the facility has not begun during the eighteen-month period.
- 2. If this permit was issued or modified to allow the discharge of increased quantities of pollutants to accommodate the modification of an existing facility and if construction of this modification has not begun during the eighteen month period after issuance of this permit or permit modification, this permit shall be modified to reduce the quantities of pollutants allowed to be discharged to those levels that would have been allowed if the modification of the facility had not been planned.
- 3. Construction has begun when the owner or operator has:
  - a. begun, or caused to begin as part of a continuous on-site construction program:
    - (1) any placement, assembly, or installation of facilities or equipment; or
    - (2) significant site preparation work including clearing, excavation, or removal of existing buildings, structures, or facilities which is necessary for the placement, assembly, or installation of new source facilities or equipment; or
  - b. entered into a binding contractual obligation for the purpose of placement, assembly, or installation of facilities or equipment which are intended to be used in its operation within a reasonable time. Options to purchase or contracts which can be terminated or modified without substantial loss, and contracts for feasibility, engineering, and design studies do not constitute a contractual obligation under the paragraph. The entering into a lease with the State of Alabama for exploration and production of hydrocarbons shall also be considered beginning construction.

# F. COMPLIANCE WITH WATER QUALITY STANDARDS

- 1. On the basis of the permittee's application, plans, or other available information, the Department has determined that compliance with the terms and conditions of this permit should assure compliance with the applicable water quality standards.
- 2. Compliance with permit terms and conditions notwithstanding, if the permittee's discharge(s) from point sources identified in Provision I. A. of this permit cause or contribute to a condition in contravention of state water quality standards, the Department may require abatement action to be taken by the permittee in emergency situations or modify the permit pursuant to the Department's Rules, or both.
- 3. If the Department determines, on the basis of a notice provided pursuant to this permit or any investigation, inspection or sampling, that a modification of this permit is necessary to assure maintenance of water quality standards or compliance with other provisions of the AWPCA or FWPCA, the Department may require such modification and, in cases of emergency, the Director may prohibit the discharge until the permit has been modified.

# G. GROUNDWATER

Unless specifically authorized under this permit, this permit does not authorize the discharge of pollutants to groundwater. Should a threat of groundwater contamination occur, the Director may require groundwater monitoring to properly assess the degree of the problem and the Director may require that the Permittee undertake measures to abate any such discharge and/or contamination.

### H. DEFINITIONS

- Average monthly discharge limitation means the highest allowable average of "daily discharges" over a calendar month,
  calculated as the sum of all "daily discharges" measured during a calendar month divided by the number of "daily discharges"
  measured during that month (zero discharge days shall not be included in the number of "daily discharges" measured and a less
  than detectable test result shall be treated as a concentration of zero if the most sensitive EPA approved method was used).
- 2. Average weekly discharge limitation means the highest allowable average of "daily discharges" over a calendar week, calculated as the sum of all "daily discharges" measured during a calendar week divided by the number of "daily discharges" measured during that week (zero discharge days shall not be included in the number of "daily discharges" measured and a less than detectable test result shall be treated as a concentration of zero if the most sensitive EPA approved method was used).
- 3. Arithmetic Mean means the summation of the individual values of any set of values divided by the number of individual values.

- 4. AWPCA means the Alabama Water Pollution Control Act.
- 5. BOD means the five-day measure of the pollutant parameter biochemical oxygen demand.
- Bypass means the intentional diversion of waste streams from any portion of a treatment facility.
- CBOD means the five-day measure of the pollutant parameter carbonaceous biochemical oxygen demand.
- 8. Daily discharge means the discharge of a pollutant measured during any consecutive 24-hour period in accordance with the sample type and analytical methodology specified by the discharge permit.
- 9. Daily maximum means the highest value of any individual sample result obtained during a day.
- 10. Daily minimum means the lowest value of any individual sample result obtained during a day.
- Day means any consecutive 24-hour period.
- 12. Department means the Alabama Department of Environmental Management.
- Director means the Director of the Department.
- 14. Discharge means "[t]he addition, introduction, leaking, spilling or emitting of any sewage, industrial waste, pollutant or other wastes into waters of the state". Code of Alabama 1975, Section 22-22-1(b)(8).
- 15. Discharge Monitoring Report (DMR) means the form approved by the Director to accomplish reporting requirements of an NPDES permit.
- DO means dissolved oxygen.
- 17. 8HC means 8-hour composite sample, including any of the following:
  - a. The mixing of at least 5 equal volume samples collected at constant time intervals of not more than 2 hours over a period of not less than 8 hours between the hours of 6:00 a.m. and 6:00 p.m. If the sampling period exceeds 8 hours, sampling may be conducted beyond the 6:00 a.m. to 6:00 p.m. period.
  - b. A sample continuously collected at a constant rate over period of not less than 8 hours between the hours of 6:00 a.m. and 6:00 p.m. If the sampling period exceeds 8 hours, sampling may be conducted beyond the 6:00 a.m. to 6:00 p.m. period.
- 18. EPA means the United States Environmental Protection Agency.
- 19. FC means the pollutant parameter fecal coliform.
- 20. Flow means the total volume of discharge in a 24-hour period.
- 21. FWPCA means the Federal Water Pollution Control Act.
- 22. Geometric Mean means the Nth root of the product of the individual values of any set of values where N is equal to the number of individual values. The geometric mean is equivalent to the antilog of the arithmetic mean of the logarithms of the individual values. For purposes of calculating the geometric mean, values of zero (0) shall be considered one (1).
- 23. Grab Sample means a single influent or effluent portion which is not a composite sample. The sample(s) shall be collected at the period(s) most representative of the discharge.
- 24. Indirect Discharger means a nondomestic discharger who discharges pollutants to a publicly owned treatment works or a privately owned treatment facility operated by another person.
- 25. Industrial User means those industries identified in the Standard Industrial Classification manual, Bureau of the Budget 1967, as amended and supplemented, under the category "Division D Manufacturing" and such other classes of significant waste producers as, by regulation, the Director deems appropriate.
- 26. MGD means million gallons per day.
- 27. Monthly Average means, other than for fecal coliform bacteria, the arithmetic mean of the entire composite or grab samples taken for the daily discharges collected in one month period. The monthly average for fecal coliform bacteria is the geometric mean of daily discharge samples collected in a one month period. The monthly average for flow is the arithmetic mean of all flow measurements taken in a one month period.

- 28. New Discharger means a person, owning or operating any building, structure, facility or installation:
  - a. from which there is or may be a discharge of pollutants;
  - b. that did not commence the discharge of pollutants prior to August 13, 1979, and which is not a new source; and
  - which has never received a final effective NPDES permit for dischargers at that site.
- 29. NH3-N means the pollutant parameter ammonia, measured as nitrogen.
- Permit application means forms and additional information that is required by ADEM Administrative Code Rule 335-6-6-.08
  and applicable permit fees.
- Point source means "any discernible, confined and discrete conveyance, including but not limited to any pipe, channel, ditch, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, or vessel or other floating craft, . . . from which pollutants are or may be discharged." Section 502(14) of the FWPCA, 33 U.S.C. Section 1362(14).
- Pollutant includes for purposes of this permit, but is not limited to, those pollutants specified in Code of Alabama 1975, Section 22-22-1(b)(3) and those effluent characteristics specified in Provision I. A. of this permit.
- 33. Privately Owned Treatment Works means any devices or system which is used to treat wastes from any facility whose operator is not the operator of the treatment works, and which is not a "POTW".
- 34. Publicly Owned Treatment Works -- means a wastewater collection and treatment facility owned by the State, municipality, regional entity composed of two or more municipalities, or another entity created by the State or local authority for the purpose of collecting and treating municipal wastewater.
- 35. Receiving Stream means the "waters" receiving a "discharge" from a "point source".
- 36. Severe property damage means substantial physical damage to property, damage to the treatment facilities which causes them to become inoperable, or substantial and permanent loss of natural resources which can reasonably be expected to occur in the absence of a bypass. Severe property damage does not mean economic loss caused by delays in production.
- 37. Significant Source means a source which discharges 0.025 MGD or more to a POTW or greater than five percent of the treatment work's capacity, or a source which is a primary industry as defined by the U.S. EPA or which discharges a priority or toxic pollutant.
- 38. Solvent means any virgin, used or spent organic solvent(s) identified in the F-Listed wastes (F001 through F005) specified in 40 CFR 261.31 that is used for the purpose of solubilizing other materials.
- TKN means the pollutant parameter Total Kjeldahl Nitrogen.
- 40. TON means the pollutant parameter Total Organic Nitrogen.
- 41. TRC means Total Residual Chlorine.
- 42. TSS means the pollutant parameter Total Suspended Solids.
- 43. 24HC means 24-hour composite sample, including any of the following:
  - a. the mixing of at least 12 equal volume samples collected at constant time intervals of not more than 2 hours over a period of 24 hours;
  - b. a sample collected over a consecutive 24-hour period using an automatic sampler composite to one sample. As a minimum, samples shall be collected hourly and each shall be no more than one twenty-fourth (1/24) of the total sample volume collected; or
  - c. a sample collected over a consecutive 24-hour period using an automatic composite sampler composited proportional to
- 44. Upset means an exceptional incident in which there is an unintentional and temporary noncompliance with technology-based permit discharge limitations because of factors beyond the reasonable control of the permittee. An upset does not include noncompliance to the extent caused by operational error, improperly designed treatment facilities, inadequate treatment facilities, lack of preventive maintenance, or careless or improper operation.

- Waters means "[a]ll waters of any river, stream, watercourse, pond, lake, coastal, ground or surface water, wholly or partially within the state, natural or artificial. This does not include waters which are entirely confined and retained completely upon the property of a single individual, partnership or corporation unless such waters are used in interstate commerce." Code of Alabama 1975, Section 22-22-1(b)(2). Waters "include all navigable waters" as defined in Section 502(7) of the FWPCA, 22 U.S.C. Section 1362(7), which are within the State of Alabama.
- 46. Week means the period beginning at twelve midnight Saturday and ending at twelve midnight the following Saturday.
- Weekly (7-day and calendar week) Average is the arithmetic mean of all samples collected during a consecutive 7-day period or calendar week, whichever is applicable. The calendar week is defined as heginning on Sunday and ending on Saturday. Weekly averages shall be calculated for all calendar weeks with Saturdays in the month. If a calendar week overlaps two months (i.e., the Sunday is in one month and the Saturday in the following month), the weekly average calculated for the calendar week shall be included in the data for the month that contains the Saturday.

#### I. SEVERABILITY

The provisions of this permit are severable, and if any provision of this permit or the application of any provision of this permit to any circumstance is held invalid, the application of such provision to other circumstances, and the remainder of this permit, shall not be affected thereby.

## PART IV ADDITIONAL REQUIREMENTS, CONDITIONS, AND LIMITATIONS

#### A. BEST MANAGEMENT PRACTICES (BMP) PLAN REQUIREMENTS

#### BMP Plan

The permittee shall develop and implement a Best Management Practices (BMP) Plan which prevents, or minimizes the potential for, the release of pollutants from ancillary activities, including material storage areas; plant site runoff; in-plant transfer, process and material handling areas; loading and unloading operations, and sludge and waste disposal areas, to the waters of the State through plant site runoff; spillage or leaks; sludge or waste disposal; or drainage from raw material storage.

#### 2. Plan Content

The permittee shall prepare and implement a best management practices (BMP) plan, which shall:

- a. Establish specific objectives for the control of pollutants:
  - (1) Each facility component or system shall be examined for its potential for causing a release of significant amounts of pollutants to waters of the State due to equipment failure, improper operation, natural phenomena such as rain or snowfall, etc.
  - (2) Where experience indicates a reasonable potential for equipment failure (e.g., a tank overflow or leakage), natural condition (e.g. precipitation), or circumstances to result in significant amounts of pollutants reaching surface waters, the plan should include a prediction of the direction, rate of flow, and total quantity of pollutants which could be discharged from the facility as a result of each condition or circumstance.
- b. Establish specific best management practices to meet the objectives identified under paragraph a. of this section, addressing each component or system capable of causing a release of significant amounts of pollutants to the waters of the State, and identifying specific preventative or remedial measures to be implemented;
- c. Establish a program to identify and repair leaking equipment items and damaged containment structures, which may contribute to contaminated stormwater runoff. This program must include regular visual inspections of equipment, containment structures and of the facility in general to ensure that the BMP is continually implemented and effective;
- d. Prevent the spillage or loss of fluids, oil, grease, gasoline, etc. from vehicle and equipment maintenance activities and thereby prevent the contamination of stormwater from these substances;
- e. Prevent or minimize stormwater contact with material stored on site;
- f. Designate by position or name the person or persons responsible for the day to day implementation of the BMP;
- g. Provide for routine inspections, on days during which the facility is manned, of any structures that function to prevent stormwater pollution or to remove pollutants from stormwater and of the facility in general to ensure that the BMP is continually implemented and effective;
- h. Provide for the use and disposal of any material used to absorb spilled fluids that could contaminate stormwater;
- i. Develop a solvent management plan, if solvents are used on site. The solvent management plan shall include as a minimum lists of the solvents on site; the disposal method of solvents used instead of dumping, such as reclamation, contract hauling; and the procedures for assuring that solvents do not routinely spill or leak into the stormwater;
- j. Provide for the disposal of all used oils, hydraulic fluids, solvent degreasing material, etc. in accordance with good management practices and any applicable state or federal regulations;
- k. Include a diagram of the facility showing the locations where stormwater exits the facility, the locations of any structure or other mechanisms intended to prevent pollution of stormwater or to remove pollutants from stormwater, the locations of any collection and handling systems;
- Provide control sufficient to prevent or control pollution of stormwater by soil particles to the degree required to
  maintain compliance with the water quality standard for turbidity applicable to the waterbody(s) receiving discharge(s)
  under this permit;
- m. Provide spill prevention, control, and/or management sufficient to prevent or minimize contaminated stormwater runoff. Any containment system used to implement this requirement shall be constructed of materials compatible with the substance(s) contained and shall prevent the contamination of groundwater. The containment system shall also be

capable of retaining a volume equal to 110 percent of the capacity of the largest tank for which containment is provided;

- Provide and maintain curbing, diking or other means of isolating process areas to the extent necessary to allow segregation and collection for treatment of contaminated stormwater from process areas;
- o. Be reviewed by plant engineering staff and the plant manager; and
- Bear the signature of the plant manager.

#### 3. Compliance Schedule

The permittee shall have reviewed (and revised if necessary) and fully implemented the BMP plan as soon as practicable but no later than six months after the effective date of this permit.

#### Department Review

- a. When requested by the Director or his designee, the permittee shall make the BMP available for Department review.
- b. The Director or his designee may notify the permittee at any time that the BMP is deficient and require correction of the deficiency.
- c. The permittee shall correct any BMP deficiency identified by the Director or his designee within 30 days of receipt of notification and shall certify to the Department that the correction has been made and implemented.

#### 5. Administrative Procedures

- A copy of the BMP shall be maintained at the facility and shall be available for inspection by representatives of the Department.
- b. A log of the routine inspection required above shall be maintained at the facility and shall be available for inspection by representatives of the Department. The log shall contain records of all inspections performed for the last three years and each entry shall be signed by the person performing the inspection.
- c. The permittee shall provide training for any personnel required to implement the BMP and shall retain documentation of such training at the facility. This documentation shall be available for inspection by representatives of the Department. Training shall be performed prior to the date that implementation of the BMP is required.
- d. BMP Plan Modification. The permittee shall amend the BMP plan whenever there is a change in the facility or change in operation of the facility which materially increases the potential for the ancillary activities to result in a discharge of significant amounts of pollutants.
- e. BMP Plan Review. The permittee shall complete a review and evaluation of the BMP plan at least once every three years from the date of preparation of the BMP plan. Documentation of the BMP Plan review and evaluation shall be signed and dated by the Plant Manager.

# B. STORMWATER FLOW MEASUREMENT AND SAMPLING REQUIREMENTS

#### Stormwater Flow Measurement

- a. All stormwater samples shall be collected from the discharge resulting from a storm event that is greater than 0.1 inches
- b. The total volume of stormwater discharged for the event must be monitored, including the date and duration (in hours) and rainfall (in inches) for storm event(s) sampled. The duration between the storm event sampled and the end of the previous measurable (greater than 0.1 inch rainfall) storm event must be a minimum of 72 hours. This information must be recorded as part of the sampling procedure and records retained according to Part I.B. of this permit.
- c. The volume may be measured using flow measuring devices, or estimated based on a modification of the Rational Method using total depth of rainfall, the size of the drainage area serving a stormwater outfall, and an estimate of the runoff coefficient of the drainage area. This information must be recorded as part of the sampling procedure and records retained according to Part I.B. of this permit.

#### 2. Stormwater Sampling

- a. A grab sample, if required by this permit, shall be taken during the first thirty minutes of the discharge (or as soon thereafter as practicable); and a flow-weighted composite sample, if required by this permit, shall be taken for the entire event or for the first three hours of the event.
- b. All test procedures will be in accordance with part I.B. of this permit.

#### C. ACUTE TOXICITY LIMITATIONS AND BIOMONITORING REQUIREMENTS (DSN004)

- 1. The permittee shall perform 48-hour acute toxicity screening tests on the wastewater discharges required to be tested for acute toxicity by Part I of this permit.
  - a. Test Requirements:
    - (1) The tests shall be diluted using an appropriate control water, to the Instream Waste Concentration (IWC) which is 1% effluent. The IWC is the actual concentration of effluent, after mixing, in the receiving stream during a 1-day, 10-year flow period.
    - (2) Any test where survival in the effluent concentration is less than 90% and statistically lower than the control indicates acute toxicity and constitutes noncompliance with this permit.
  - b. General Test Requirements:
    - (1) A grab sample shall be obtained for use in above biomonitoring tests. The holding time for each sample shall not exceed 36 hours. The control water shall be a water prepared in the laboratory in accordance with the EPA procedure described in EPA 821-R-02-012 or most current edition or another control water selected by the permittee and approved by the Department.
    - (2) Effluent toxicity tests in which the control survival is less than 90% or in which the other requirements of the EPA Test Procedure are not met shall be unacceptable and the permittee shall rerun the tests as soon as practical within the monitoring period.
    - (3) In the event of an invalid test, upon subsequent completion of a valid test, the results of all tests, valid and invalid, are reported with an explanation of the tests performed and results.

# c. Reporting Requirements:

- (1) The permittee shall notify the Department in writing within 48 hours after toxicity has been demonstrated by the scheduled test(s).
- (2) Biomonitoring test results obtained during each monitoring period shall be summarized and reported using the appropriate Discharge Monitoring Report (DMR) form approved by the Department. In accordance with Section 2. of this part, an effluent toxicity report containing the information in Section 2. shall be included with the DMR. Two copies of the test results must be submitted to the Department no later than 28 days after the monitoring period in which the tests were performed.

#### d. Additional Testing Requirements:

- (1) If acute toxicity is indicated (noncompliance with permit limit), the permittee shall perform four additional valid acute toxicity tests in accordance with these procedures to determine the extent and duration of the toxic condition. The toxicity tests shall be performed once per week and shall be performed during the first four calendar weeks following the date on which the permittee became aware of the permit noncompliance and the results of these tests shall be submitted no later than 28 days following the month in which the tests were performed.
- After evaluation of the results of the follow-up tests, the Department will determine if additional action is appropriate and may require additional testing and/or toxicity reduction measures. The permittee may be required to perform a Toxicity Identification Evaluation (TIE) and/or a Toxicity Reduction Evaluation (TRE). The TIE/TRE shall be performed in accordance with the most recent protocols/guidance outlined by EPA (e.g., EPA/600/2-88/062, EPA/600/R-92/080, EPA/600/R-92/081, EPA/833/B-99/022 and/or EPA/600/6-91/005F, etc.).

#### e. Test Methods:

(1) The tests shall be performed in accordance with the latest edition of the "EPA Methods for Measuring the Acute Toxicity of Effluents to Freshwater and Marine Organisms" and shall be performed using the fathead minnow (Pimephales promelas) and the cladoceran (Ceriodaphnia dubia).

## 2. Effluent Toxicity Testing Reports

The following information shall be submitted with each discharge monitoring report unless otherwise directed by the Department. The Department may at any time suspend or reinstate this requirement or may increase or decrease the frequency of submittals.

#### a. Introduction

- (1) Facility Name, location and county
- (2) Permit number
- (3) Toxicity testing requirements of permit
- (4) Name of receiving water body
- (5) Contract laboratory information (if tests are performed under contract)
  - (a) Name of firm
  - (b) Telephone number
  - (c) Address
- (6) Objective of test

#### b. Plant Operations

- (1) Discharge operating schedule (if other than continuous)
- (2) Volume of discharge during sample collection to include Mean daily discharge on sample collection date (MGD: CFS, GPM)
- (3) Design flow of treatment facility at time of sampling

### c. Source of Effluent and Dilution Water

#### (1) Effluent samples

- (a) Sampling point
- (b) Sample collection dates and times (to include composite sample start and finish times)
- (c) Sample collection method
- (d) Physical and chemical data of undiluted effluent samples (water temperature, pH, alkalinity, hardness, specific conductance, total residual chlorine (if applicable), etc.)
- (e) Sample temperature when received at the laboratory
- (f) Lapsed time from sample collection to delivery
- (g) Lapsed time from sample collection to test initiation

# (2) Dilution Water Samples

- (a) Source
- (b) Collection date(s) and time(s) (where applicable)
- (c) Pretreatment
- (d) Physical and chemical characteristics (pH, hardness, water temperature, alkalinity, specific conductance, etc.)

## d. Test Conditions

- (1) Toxicity test method utilized
- (2) End point(s) of test
- (3) Deviations from referenced method, if any, and reason(s)
- (4) Date and time test started
- (5) Date and time test terminated
- (6) Type and volume of test chambers
- (7) Volume of solution per chamber
- (8) Number of organisms per test chamber
- (9) Number of replicate test chambers per treatment
- (10) Test temperature, pH and dissolved oxygen as recommended by the method (to include ranges)

- (11) Feeding frequency, and amount and type of food
- (12) Light intensity (mean)
- e. Test Organisms
  - (1) Scientific name
  - (2) Life stage and age
  - (3) Source
  - (4) Disease treatment (if applicable)
- f. Quality Assurance
  - (1) Reference toxicant utilized and source
  - (2) Date and time of most recent acute reference toxicant test(s), raw data, and current cusum chart(s)
  - (3) Dilution water utilized in reference toxicant test
  - (4) Results of reference toxicant test(s) (LC50, etc.), report concentration-response relationship and evaluate test sensitivity. The most recent reference toxicant test shall be conducted within 30-days of the routine.
  - (5) Physical and chemical methods utilized
- g. Results
  - (1) Provide raw toxicity data in tabular form, including daily records of affected organisms in each concentration (including controls) and replicate
  - (2) Provide table of endpoints: LC50, NOAEC, Pass/Fail (as required in the applicable NPDES permit)
  - (3) Indicate statistical methods used to calculate endpoints
  - (4) Provide all physical and chemical data required by method
  - (5) Results of test(s) (LC50, NOAEC, Pass/Fail, etc.), report concentration-response relationship (definitive test only), report percent minimum significant difference (PMSD)
- h. Conclusions and Recommendations
  - (1) Relationship between test endpoints and permit limits
  - (2) Action to be taken

1/ Adapted from "Methods for Measuring the Acute Toxicity of Effluents and Receiving Waters to Freshwater and Marine Organisms", Fifth Edition, October 2002 (EPA 821-R-02-012), Section 12, Report Preparation

## D. CHRONIC TOXICITY LIMITATIONS AND BIOMONITORING REQUIREMENTS (DSN002)

- 1. The permittee shall perform short-term chronic toxicity tests on the wastewater discharges required to be tested for chronic toxicity by Part I of this permit.
  - a. Test Requirements
    - (1) The tests shall be performed using undiluted effluent.
    - (2) Any test result that shows a statistically significant reduction in survival, growth, or reproduction between the control and the test at the 95% confidence level indicate chronic toxicity and constitute noncompliance with this permit.
  - b. General Test Requirements
    - (1) A minimum of three (3) 24-hour composite samples shall be obtained for use in the above biomonitoring tests and collected every other day so that the laboratory receives water samples on the first, third, and fifth day of the seven-day test period. The holding time for each composite sample shall not exceed 36 hours. The control water shall be a water prepared in the laboratory in accordance with the EPA procedure described in EPA 821-R-02-013 or the most current edition or another control water selected by the permittee and approved by the Department.
    - (2) Effluent toxicity tests in which the control survival is less than 80%, P. promelas dry weight per surviving control organism is less than 0.25 mg, Ceriodaphnia number of young per surviving control organism is less than 15, Ceriodaphnia reproduction where less than 60% of surviving control females produce three broods

or in which the other requirements of the EPA Test Procedure are not met shall be unacceptable and the permittee shall rerun the tests as soon as practical within the monitoring period.

(3) In the event of an invalid test, upon subsequent completion of a valid test, the results of all tests, valid and invalid, are reported with an explanation of the tests performed and results.

#### c. Reporting Requirements

- (1) The permittee shall notify the Department in writing within 48 hours after toxicity has been demonstrated by the scheduled test(s).
- (2) Biomonitoring test results obtained during each monitoring period shall be summarized and reported using the appropriate Discharge Monitoring Report (DMR) form approved by the Department. In accordance with Section 2 of this part, an effluent toxicity report containing the information in Section 2 shall be included with the DMR. Two copies of the test results must be submitted to the Department no later than 28 days after the monitoring period in which the tests were performed.

#### d. Additional Testing Requirements

- (1) If chronic toxicity is indicated (noncompliance with permit limit), the permittee shall perform two additional valid chronic toxicity tests in accordance with these procedures to determine the extent and duration of the toxic condition. The toxicity tests shall run consecutively beginning on the first calendar week following the date on which the permittee became aware of the permit noncompliance and the results of these tests shall be submitted no later than 28 days following the month in which the tests were performed.
- After evaluation of the results of the follow-up tests, the Department will determine if additional action is appropriate and may require additional testing and/or toxicity reduction measures. The permittee may be required to perform a Toxicity Identification Evaluation (TIE) and/or a Toxicity Reduction Evaluation (TRE). The TIE/TRE shall be performed in accordance with the most recent protocols/guidance outlined by EPA (e.g., EPA/600/2-88/062, EPA/600/R-92/080, EPA/600/R-91-003, EPA/600/R-92/081, EPA/833/B-99/022 and/or EPA/600/6-91/005F, etc.)

## e. Test Methods

(1) The tests shall be performed in accordance with the latest edition of the "EPA Short-Term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Water to Freshwater Organisms". The Larval Survival and Growth Test, Methods 1000.0, shall be used for the fathead minnow (*Pimephales promelas*) test and the Survival and Reproduction Test, Method 1002.0, shall be used for the cladoceran (*Ceriodaphnia dubia*) test.

# 2. Effluent Toxicity Testing Reports

The following information shall be submitted with each discharge monitoring report unless otherwise directed by the Department. The Department may at any time suspend or reinstate these requirements or may decrease or increase the frequency of submittals.

#### a. Introduction

- (1) Facility name, location, and county
- (2) Permit number
- (3) Toxicity testing requirements of permit
- (4) Name of receiving water body
- (5) Contract laboratory information (if tests are performed under contract)
  - (a) Name of firm
  - (b) Telephone number
  - (c) Address
- (6) Objective of test

# b. Plant Operation

- (1) Discharge Operating schedule (if other than continuous)
- (2) Volume of discharge during sample collection to include Mean daily discharge on sample collection dates (MGD, CFS, GPM)
- (3) Design flow of treatment facility at time of sampling

#### c. Source of Effluent and Dilution Water

- (1) Effluent samples
  - (a) Sampling point
  - (b) Sample collection dates and times (to include composite sample start and finish times)
  - (c) Sample collection method
  - (d) Physical and chemical data of undiluted effluent samples (water temperature, pH, alkalinity, hardness, specific conductance, total residual chlorine (if applicable), etc.)
  - (e) Sample temperature when received at the laboratory
  - (f) Lapsed time from sample collection to delivery
  - (g) Lapsed time from sample collection to test initiation

# (2) Dilution Water Samples

- (a) Source
- (b) Collection date(s) and time(s) (where applicable)
- (c) Pretreatment
- (d) Physical and chemical characteristics (pH, hardness, water temperature, alkalinity, specific conductance, etc.)

# d. Test Conditions

- (1) Toxicity test method utilized
- (2) End point(s) of test
- (3) Deviations from referenced method, if any, and reason(s)
- (4) Date and time test started
- (5) Date and time test terminated
- (6) Type and volume of test chambers
- (7) Volume of solution per chamber
- (8) Number of organisms per test chamber
- (9) Number of replicate test chambers per treatment
- (10) Test temperature, pH, and dissolved oxygen as recommended by the method (to include ranges)
- (11) Specify if aeration was needed
- (12) Feeding frequency, amount, and type of food
- (13) Specify if (and how) pH control measures were implemented
- (14) Light intensity (mean)

# e. Test Organisms

- (1) Scientific name
- (2) Life stage and age
- (3) Source
- (4) Disease(s) treatment (if applicable)

# f. Quality Assurance

- (1) Reference toxicant utilized and source
- (2) Date and time of most recent chronic reference toxicant test(s), raw data and current control chart(s). The most recent chronic reference toxicant test shall be conducted within 30 days of the routine.
- (3) Dilution water utilized in reference toxicant test
- (4) Results of reference toxicant test(s) (NOEC, IC25, PASS/FAIL, etc.), report concentration response relationship and evaluate test sensitivity
- (5) Physical and chemical methods utilized

# g. Results

- Provide raw toxicity data in tabular form, including daily records of affected organisms in each concentration (including controls) and replicate
- (2) Provide table of endpoints: NOECs, IC25s, PASS/FAIL, etc. (as required in the applicable NPDES permit)
- (3) Indicate statistical methods used to calculate endpoints
- (4) Provide all physical and chemical data required by method

- (5) Results of test(s) (NOEC, IC25, PASS/FAIL, etc.), report concentration-response relationship (definitive test only), report percent minimum significant difference (PMSD) calculated for sub-lethal endpoints determined by hypothesis testing.
- h. Conclusions and Recommendations
  - (1) Relationship between test endpoints and permit limits
  - (2) Actions to be taken
- i. Conclusions and Recommendations
  - (1) Relationship between test endpoints and permit limits
  - (2) Actions to be taken

1/ Adapted from "Short-Term Methods for Estimating the Chronic Toxicity of Effluents and Receiving Waters to Freshwater Organisms", Fourth Edition, October 2002 (EPA 821-R-02-013), Section 10, Report Preparation

# E. COOLING WATER INTAKE REQUIREMENTS

1. The entity providing water to the permittee is a public water system in accordance with Section 1401 of the Safe Drinking Water Act; therefore, the permittee is exempt from the requirements of this permit condition.

#### ADEM PERMIT RATIONALE

PREPARED DATE: July 8, 2019 REVISION DATE: December 3, 2019 REVISION DATE: February 19, 2020 REVISION DATE: September 8, 2020 REVISION DATE: November 30, 2020 REVISION DATE: March 30, 2021 PREPARED BY: Scott Jackson

Permittee Name: DC Alabama, Inc.

Permit Number: AL0083763

Facility Name:

# PERMIT IS MODIFICATION

# DISCHARGE SERIAL NUMBERS & DESCRIPTIONS:

DC Alabama, Inc.

DSN001: Uncontaminated groundwater and stormwater run-off associated with silicon metal manufacturing.

DSN002: Process wastewater associated with silicon metal manufacturing and treated silica fume slurry

discharging to U.T. to Miller Creek.

DSN003: Non-contact cooling wastewater associated with silicon metal manufacturing

DSN004: Process wastewater and stormwater run-off associated with silicon metal manufacturing and

treated silica fume slurry discharging to the Tallapoosa River.

INDUSTRIAL CATEGORY: NON-CATEGORICAL

MAJOR: N

# STREAM INFORMATION (DSN001, DSN002, DSN003):

Receiving Stream: Unnamed Tributary to Miller Creek

Classification: Fish & Wildlife

River Basin: Tallapoosa 7Q10: 0 cfs

7Q2: 0 cfs
1Q10: 0 cfs
Annual Average Flow: 0 cfs
303(d) List: NO

Impairment: N/A

TMDL: NO

# STREAM INFORMATION (DSN004):

Receiving Stream:

Tallapoosa River

Classification:

Public Water Supply

River Basin:

Tallapoosa

7Q10:

627.97 cfs

7Q2:

797.24 cfs

1010:

470.98 cfs

Annual Average Flow: 5881.82 cfs

303(d) List:

NO

Impairment:

N/A

TMDL:

NO

# DISCUSSION:

DC Alabama, Inc. produces silicon metal used in chemical and aluminum products. The facility also produces micro silica (fume) which is used as a strengthener and filler by concrete and refractory industries. The manufacturing processes includes melting raw materials (quartz rock, coal, charcoal, wood chips) in an electric arc furnace to produce molten silicon metal which is cast as ingots. The ingots are crushed before being packaged to be shipped.

Based on the modified permit application, DC Alabama, Inc. is requesting the NPDES Permit be modified to include the addition of stormwater discharges through Outfall DSN004 to the Tallapoosa River. The source of this stormwater is from the facility's industrial process area and routing of the treated stormwater to the outfall. There are no other modifications being made to this permit. All monitoring and reporting requirements will be continued.

ADEM Administrative Rule 335-6-10-.12 requires applicants to new or expanded discharges to Tier II waters demonstrate that the proposed discharge is necessary for important economic or social development in the area in which the waters are located. The application submitted by the facility is for a new discharge and the antidegradation rationale is attached.

# December 3, 2019 Revision

The Department completed a reasonable potential analysis (RPA) of the discharge based on laboratory data provided in the Permittee's application and groundwater data submitted to the Department by the facility (see attached). The RPA indicates whether pollutants in treated effluent have the potential to contribute to excursions of Alabama's instream water quality standards. Based on the data submitted by the facility, it appears that there is a reasonable potential and resulting limitation for Bis (2-Ethylhexyl) Phthalate in the discharge to the Unnamed Tributary to Miller Creek (DSN002). Monitoring for Bis (2-Ethylhexyl) Phthalate is also being proposed at Outfalls DSN001 and DSN004 due to the repeated occurrence of this parameter in sampling of various groundwater monitoring wells around the site as indicated in data submitted by the facility. Bis (2-Ethylhexyl) Phthalate is being proposed to be monitored at a quarterly frequency at all outfalls. The information gathered from the permittee's monitoring will be useful in determining the levels being discharged and to determine future permit limitations, if necessary.

# February 19, 2020 Revision

The facility submitted comments on the Revised Draft Permit Modification (sent December 3, 2019) to the Department on January 31, 2020. As a result of these comments, Permit Condition Part IV.C.1.c.(2) has been updated to clarify reporting requirements for the biomonitoring test results. Previously, this section required the Permittee to submit test results no later than 28 days after the month in which the tests were performed. The Permittee is only required to submit the test results quarterly and no later than the 28th day of the month following that monitoring period. To be consistent with other conditions of the permit, the last sentence of this permit condition will now read: "Two copies of the test results must be submitted to the Department no later than 28 days

after the monitoring period in which the tests were performed." In addition, Permit Condition Part IV.D.1.c.(2) has also been updated similarly to remain consistent with other conditions of the permit.

The facility has requested that ADEM suspend the requirement to submit the toxicity testing information as listed in Permit Condition Part IV.C.2. The information outlined in Permit Condition Part IV.C.2 is necessary in determining compliance with all toxicity limitations and biomonitoring requirements. The facility will be required to continue to submit this information to the Department with each DMR.

# September 8, 2020 Revision

The facility notified the Department on February 14, 2020 about an underdrain system that would be needed for the new stormwater retention basin. The facility determined this system was necessary to prevent damage to the basin and requested this groundwater be discharged to the stormwater drainage channel which eventually discharges through Outfall DSN001. The facility submitted laboratory results of a sample of the water in this underdrain system to the Department on July 14, 2020 (see attached). The results appear to show that the groundwater collected by the underdrain system is uncontaminated from operations onsite. Based on these discussions with the facility and the laboratory results, the description of Outfall DSN001 is being updated to include uncontaminated groundwater. There does not appear to be any new pollutants introduced that would be discharged in significant amounts based on the submitted data. All monitoring and reporting requirements for Outfall DSN001 will be continued.

# November 30, 2020 Revision

The facility submitted comments on the Revised Draft Permit Modification (sent October 2, 2020) to the Department on November 18, 2020. The facility has requested that limitations and monitoring requirements for Bis (2-Ethylhexyl) Phthalate (DEHP) at Outfalls DSN001, DSN002, and DSN004 be removed from the permit. The facility has provided supporting documentation including additional facility background information, peer-reviewed technical papers which have been published and indicate the difficulty in analyzing DEHP in laboratories, and guidance on false detections in groundwater samples from monitoring wells.

A reasonable potential analysis (RPA) showed the possibility for DEHP to cause a violation of water quality standards; however, the additional documentation submitted by the facility shows that DEHP is not present in the discharge and instead is a laboratory contaminant, which is a common occurrence with this pollutant. Therefore, based on the documentation provided by the facility, the limitations and monitoring requirements for DEHP at Outfalls DSN001, DSN002, and DSN004 will be removed from the permit.

# March 30, 2021 Revision

The Department has determined based on internal discussions and reviewing all available data submitted by the facility, that Bis (2-Ethylhexyl) Phthalate is proposed to be monitored in this permit modification. The Department completed a reasonable potential analysis (RPA) of the discharge based on the laboratory data provided by the facility. The RPA indicates whether pollutants in treated effluent have the potential to contribute to excursions of Alabama's in-stream water quality standards. Based on the data submitted by the facility, it appears that there is a reasonable potential and resulting limitation for Bis (2-Ethylhexyl) Phthalate in the discharge to the Unnamed Tributary to Miller Creek (DSN002). Monitoring for Bis (2-Ethylhexyl) Phthalate is also being proposed at Outfalls DSN001 and DSN004 due to the repeated occurrence of this parameter in sampling of various groundwater monitoring wells around the site as indicated in data submitted by the facility.

The facility is required to monitor for Bis (2-Ethylhexyl) Phthalate at outfalls DSN001, DSN002, and DSN004 until there have been 4 consecutive below detection sampling results. If the facility has four below detection results at one of the outfalls but not another, then monitoring would still be required at the other outfall(s) until 4 consecutive below detection results are reported for the specific outfall(s). A footnote has been added to the Pages 2, 5, and 10 of the permit to clarify monitoring and reporting requirements for Bis (2-Ethylhexyl) Phthalate at each outfall.

001Q: Uncontaminated groundwater and stormwater run-off associated with silicon metal manufacturing

<u>Parameter</u>	Monthly Avg Loading	Daily Max Loading	<u>Daily Min</u> Concentration	Monthly Avg Concentration	<u>Daily Max</u> <u>Concentration</u>	Sample Frequency	Sample Type	Basis*
pH	-	-	REPORT S.U.	_	REPORT S.U.	Quarterly	Grab	BPJ
Solids, Total Suspended	· -	_		REPORT mg/l	REPORT mg/l	Quarterly	Grab	ВРЈ
Oil & Grease	-	-	-	'	15.0 mg/l	Quarterly	Grab	BPJ
Arsenic, Total (As As)	! -	•	-		REPORT mg/l	Quarterly	Grab	BPJ
Chromium, Total (As Cr)	-			-	REPORT mg/l	Quarterly	Grab	BPJ
Copper, Total (As Cu)	-	-	_	-	REPORT mg/l	Quarterly	Grab	BPJ
Lead, Total (As Pb)	-	-			REPORT mg/l	Quarterly	Grab	ВРЈ
Nickel, Total (As Ni)	-		-		REPORT mg/l	Quarterly	Grab	ВРЈ
Aluminum, Total (As Al)			·	-	REPORT mg/l	Quarterly	Grab	ВРЈ
Selenium, Total (As Se)	-	-	<u>-</u>	!	REPORT mg/l	Quarterly	Grab	BPJ
Bis (2-Ethylhexyl) Phthalate	-	_	-	-	REPORT ug/l	Quarterly	Grab	BPJ
Flow, In Conduit or Thru Treatment Plant	REPORT MGD	REPORT MGD		-		Quarterly	Instantaneous	ВРЈ
Solids, Total Dissolved		-	-	-	REPORT mg/l	Quarterly	Grab	BPJ

002Q: Process wastewater associated with silicon metal manufacturing and treated silica fume slurry discharging to U.T. to Miller Creek.

! !	<u> </u>	Ionthly Avg	Daily Max	i	Daily Min	Monthly Avg	Daily Max	•	Sample	Sample Type	_
Parameter	1	<u>Loading</u>	<u>Loading</u>	! !	Concentration	Concentration	Concentration		Frequency :		Basis*
Bis (2-Ethylhexyl) Phthalate	1	<u>-</u>		ŀ	<u>-</u>	1.28 ug/l	2.56 ug/l	- :	Quarterly	Grab	WQBEL/BPJ

004Q: Process wastewater and stormwater run-off associated with silicon metal manufacturing and treated silica fume slurry discharging to the Tallapoosa River.

·	Monthly Avg	Daily Max	Daily Min	Monthly Avg	Daily Max	Sample	Sample Type	
<u>Parameter</u>	Loading	Loading	<u>Concentration</u>	Concentration	Concentration	Frequency		Basis*
Bis (2-Ethylhexyl) Phthalate	-	<u> </u>	<b>-</b>		REPORT ug/l	Quarterly	Grab	BPJ

# \*Basis for Permit Limitation

- BPJ Best Professional Judgment
- WQBEL Water Quality Based Effluent Limits
- EGL Federal Effluent Guideline Limitations
- 303(d) 303(d) List of Impaired Waters
- TMDL Total Maximum Daily Load Requirements

$Q_d*C_d + Q_{d2}*$	-02	45	Beckground	Background	Beckground	Sedgrand	Dedy Discharge as	Distrige as	Parte
D NAME N	Carconigan	Tipe	murce (Ca)	source (C <sub>62</sub> )	(C <sub>k</sub> ) Donly	Instream (C <sub>s</sub> ) Heatsily Are	regainted by Applicant (Cd) Max	reported by Applicant (C <sub>e</sub> ) Ave.	Lak
			Dank Plan	Mapthis Are.	up/i	. Apr.	160		
I Actionny Z Accesic*,**	YES	Mesais Metais	0	0	0	0	0 0	0	0.5
3 Berylum 4 Cadmism**		Metals Metals	0	0	0	0 0	0	0	0.2
5 Chromium / Chromium III** 5 Chromium / Chromium Vi**		Metals Metals	0	6	8	0	0	D	0.2
7 Copper**	1	Metals			0		0	0	0.3
E Lead** 9 Hercury**		Metals Metals	0	0	0	0	0	0	0.2
10 Nicker** 11 Selenium	1	Metals Metals	0	0	a u	0	0	0	0.5
12 Siver	1	Metals.	0	0	0	10 May 10	0	0	
13 Thefium 14 Zinc**		Metals Metals	0	0	3	0	0	0	03
15 Cyanide 15 Total Phenolic Compounds		Metals Metals	0	0		0	0	9	
17 Hardnesa (As CaCO3) 18 Accoloin		Metais VOC	0	6	0		0	0	
19 Acrylenitythe*	YES	ACC	0	0		0	0	0	1
29 Aldrin 21 Benzena*	VES	VOC	0	0	0	0	0	a o	1
72 Brannsform* 73 Carbon Totzachloride*	YES 1155	VOC	0	0	0	0	0	0	
24 Chiudane	AEZ	VOC	0	0	Sec. 0.	J. S. S. W. 1970.	. 0	0	
25 Clorotenzerie 25 Chloroditurano Hetisane*	YES	ADC	0	0		6	0	0	
27 Chloroethane 28 2-Chloro-Ethylynyl Ether	1	VOC	0	9	0	0		6	
25 Chloroform*	YES	VOC	0	. 0	COLUMN TO	6	0	0	
30 4,4'-000 31 4,4'-000	YES YES	ADC	0	0	0	0	0	0	
32 4.4'-DDT 33 Dicklersbrame-Mathane*	YES	VOC	0	0	0	8	0	0	
34 1, I-Dichloroethane	-	voc	0	0	0	The state of the	0	0	
35 1, 2-Dichloroethane* 36 Trace I, 2-Dichloro-Ethylene	YES	ACC.	3	0	100		0	0	
37 1. 1-Dichlorsetirylena* 38 1. 2-Dichlorspropane	YES	NOC	2				0	0	
39 S. 3-Dichicco-Propylene	-	VOC	3.		200	9	0	0	
40 Diedeles 41 Ethyltenzene	YKS	AOC AOC	0	0		B B	0	0	
42 Methyl Bromide 43 Methyl Chluride		VOC	8	0		0	0	0	
44 Mathylmus Chloride*	YES	VOC.				9	0	0	
45 L. L. 2, 2-Tetracistere-Ethane* 46 Tetracistere-Ethylene*	PES	VOC	0	0	0	0	0	0	1
47 Toluerie 48 Teramphone	YES	ACC.	0	0	0	0	0	0	1
49 Telbutyllina (TBT)	HER	AOC.	0	0.0	0	0	0	9	
SG 1. 1. 1-Trichloroethene 51 1. 1. 2-Trichloroethene*	YES	VOC	0	9	0	0	0 0	9	
52 Trichlerethpione* 53 Vioyl Chloride*	TES	ACC	0	0	0	0	0	3 0	:
54 P-Chlore-M-Cresol		Acids	0	0	0	Ø	0	0	
SS 2-Chicrophenol S6 2. 4-Dechlorophenol		Acids Acids	0	0	0	9	0 .	9	
57 2, 4-Dimethylphenol 58 4, 6-Dimetry-O-Cresol		Acids Acids	0	0 0	0	9		0	:
59 2, 4-Dintrophenol		Acids	0		0	0	.0	e	
60 4,6-Dintro-3-methylophomal 61 Dissain (2,3,7,8-TCDD)	YES	Acids Acids	0	0	0	0	0	0	
62 2-Nitropherel 63 4-Nitropherel		Acids Acids	0	0	0	0	0	0	
54 Pentachlorophenel*	YES	Acids	0	0	0	0	0	0	
65 Phenoi 65 2, 4, 6-Trichlersphenoi*	1955	Acids Acids	0	0	0	0	0 0	0	
67 Acenaphthene 68 Acenaphthylene		Bases	0	0		0	0	0	
69 Anthracene 70 Recolumn		Bases	0	0			0	0	
71 Benzu(A)Amhracane*	YES	Bases	0	0	0	0	0	6	
72 Besse (A)Pyrane* 73 3, 4 Besso-Husrarthese	AEZ	Saues Bases	9	0	0	0	0	9	
74 Berusi(IHI)Perviere 75 Berusi(K)Fluoranthere		Sases Bases	0	0	100		0	9	
76 Six (2-Chloroethory) Methane	-	Sases	0	9	SHAP BUDG	0	0	0	
77 Bin (2-Chloroethyl)-Ether* 78 Bin (2-Chloroen-Propyl) Ether	YES	Bases Bases	8	0	0	0	0	0	
79 Bia (2-Ethylhosyl) Phtholate* 50 + Bromophenyl Phenyl Ether	YES	Bases Bases	9	9	0	9	20	28	:
63 Butsi Bercyi Phitsalate 82 3-Chlororaphthalana	1	Bases	0		0	8			
83 *-Chloropherol Phenyl Stier 84 Chrysene*	YES	Saces	0			0			
85 Di-N-Buryl Phthalate	1	Bases	0		0	9	0	0	
56 Di-H-Cityl Phthalate 87 Difference(A,H)Anthrocene*	YES	Bases Bases	0	8	0	9	0	0	
36 1, 2-Dichlorobenzene 89 1, 3-Dichlorobenzene		Bases Bases	0 0	0 5	0	30.007	0	6	
90 1. 4-Dichlorobenzene		Bases	0	0	W.	man a con	0	0	
91 3, 3-Diebiersbessiding* 92 Diebyl Phthalate	YES	Bases	0	0	0	9	0	0	:
93 Directivi Mehalata 94 3. 4-Dinitrataluana*	HES	Bases Bases	0	0	0		0	0	
95 Z, 6-Dinkrotokuene 96 1,2-Dishenyihydrazine		Bases Sesan	0	0	9	0	0	0	
97 Endustifat (alpha)	YES	Bases	0	0	0		0	0	
90 Endomitus (beta) 99 Endomitus sulfate	YES	Bases Bases	0	0	0	0	0	9	
00 Endrin 01 Endrin Alderhide	YES	Bases	0	0	0	6	9	0	:
02 Fluoranthene	_	Bases	0.	0	0	0	0	0	
03 Plucrene 04 Heytochkur	YES	Bases Bases	0	9	0	0	9	8	
05 Heptachlor Epoxide 06 Hexachlorobenzene*	YES	Bases Bases	0	9	v	0	9	0	1
07 Hazachinrobutadione*	YES	Sases	.0		0	0	0	0	
08 Hexachlerocyclohezan (alpa) 09 Hexachlerocyclohezan (beta)	YES YES	Bases Bases	0	0	0	9	9	0	
10 Hezachiorocyclohezan (gamma)	MEZ.	Sases	0	0	6		0	0	-
11 HexachiorocycloPentadene 12 Hexachioroethane		Bases Bases	0			9	0	6	1
13 Indens(1, 2, 3-CK)Pyrene*	YES	Bates	0	8	0	9	0	0	
14 Isophorone 15 Nachthalene		Bases Bases	0	6	0	0	0	0	٠,
16 Mirobenzene 17 N-Nikrossell-M-Prosylomiae*	YES	Bases Bases	0	6	0	0	0	0	
18 N Oltroandi N Methylamine*	YES	Bases	0	0	2001 NO. CO.	0	0	α	
19 Pt Nitrosedi N-Phenylamine* 20 PCB-1016	YES	Sases Sases	0	0	0	0	0	0	
21 PCB-1221 22 PCB-1231	YES	Bases Bases	0	9		0	3 9	0	
23 PCB-1242	YES	Bases	6	0	0	0	0	0	
24 PCB-1248 25 PCB-1254	HEZ.	Bases	8	0	0	0	9	0	
125 PCB-1260	Y25	Bases	0	0	0	0	0	0	
127 Phenarthrene	1	Bases	4	0	. 0	0	0	0	1 '

0.2	Enter Q <sub>4</sub> = wastewater drucharge flow from facility (NGC)
0.3094458	Q <sub>0</sub> = watstewater discharge flow (rfs) (this value is caluclased from the MG(I)
	Erner flow from upstream discharge Gd2 = background stream flow in MGD allows print of discharge
9	Ori2 4 background steam flow from operation source (cfs)
	Enter 7Q18, Q, = background stream flow in cfs above point of discharge
ß	Enter or estimated, 1910, G, a background stream flow in ch. above paint of discharge (1910 estimated at 75% of 7910)
	Enter Mean Annual Plow, Q <sub>6</sub> = beckground stream from in ch above point of discharge
1	Enter PGI, Q, < taxtiground stream flow in cfs above paint of discharge (For LWF class streams)
Enter to	Britist G., a hackground in-pheson pollutant concentration in µg/ (polluming this is pero "O" unless there is data)
1, +942+0,	CL = resultant in-sizeam New, after discharge
Calculated on other	C, in resultant in stream poliulant concentration in µgf in the stream (after complete mixing access)
50	Sinter: Berligmund Hardnass allows point of descharge (assume 50 South of Berningbarn and 100 North of Berningbarn)
7.00 544	Enter, Bucinground pit above point of discharge
TES	Enter, is discharge to a stream? "YES" Other option would be to a Late. (This changes the pacifics coefficients to: Se mutuly)

<sup>\*\*</sup> Using Pertition Coefficient

December 3, 2019

Fixely Hame, DC Alabama Inc. (UT to Miller Cree NPOCO No.: ALDRESTES = Arrival Fish only (4) 9 = Arrival Average span Q = 7010 Prestourne FLYP plantification - TO10 Background from operations source (CsC) Deby Mart Sadground from vanious scurce (Cat) Northly Ave Water I. Grady Starts (C.) Carceopin APT. 1 Amenium
2 America
3 Deptum
5 Chormand Chromous VI
7 Copper
5 Chormand Chromous VI
7 Copper
5 Leed
8 Mescury
15 Dicked
11 Salman
12 Shee
13 Theisen
14 Zinc
15 Operate
15 Dicked
11 Salman
15 Shee
16 Tool Phenotic Compounds
17 Methodes (Na CopCOS)
18 Actical
17 Methodes (Na CopCOS)
18 Actical
19 Actical
19 Actical
19 Actical
19 Actical
20 Operation
20 Operation
20 Operation
21 Operation
22 Operation
23 Operation
24 Operation
25 Operation
26 Operation
27 Operation
27 Operation
28 Operation
28 Operation
29 Operation
29 Operation
20 Operation
20 Operation
21 Operation
22 Operation
23 Operation
24 Operation
25 Operation
26 Operation
27 Operation
27 Operation
28 Operation
29 Operation
29 Operation
20 Operation
20 Operation
20 Operation
20 Operation
21 Operation
21 Operation
22 Operation
23 Operation
24 Operation
25 Operation
26 Operation
27 Operation
27 Operation
28 Operation
29 Operation
29 Operation
20 Operation
20 Operation
20 Operation
20 Operation
21 Operation
21 Operation
22 Operation
23 Operation
24 Operation
25 Operation
26 Operation
26 Operation
27 Operation
28 Operation
29 Operation
29 Operation
29 Operation
20 Operation
20 Operation
20 Operation
20 Operation
20 Operation
21 Operation
21 Operation
22 Operation
23 Operation
24 Operation
25 Operation
26 Operation
27 Operation
27 Operation
28 Operation
29 Operation
29 Operation
29 Operation
20 Operation
20 Operation
20 Operation
20 Operation
21 Operation
21 Operation
22 Operation
23 Operation
24 Operation
25 Operation
26 Operation
27 Operation
27 Operation
28 Operation
29 Operation
29 Operation
20 Operation
20 Operation
20 Operation
20 Operation
21 Operation
21 Operation
22 Operation
23 Operation
24 Operation
25 Operation
26 Operation
27 Operation
27 Operation
28 Operation
29 Operation
29 Operation
20 Operation
20 Operation
20 Ope 723 1337912 1337913 1337912 1337913 14000 1 14000 14000 1 14001 14000 1 14000 14000 1 14000 14000 1 14000 14000 1 14000 14000 1 14000 100 mm 0800 307 141 3 200 1600 20258 0 460 103 145 0 644 200,051 11 000 12 766 5 701 0 012 57 297 5 000 0 728 40 010 2 300 2 303 1 140 4 002 11 656 1 000 424-01 424-00 8 mil-00 8 878-02 9 ME-07 1508-02 1248-02 2 028-03 4 668-02 1248-01 2 028-03 4 668-02 1445-01 1425-04 2 008-01 1405-06 1425-04 2 008-01 1805-086921 6 308-03 1 875-03 4 000 0 195 Tenail 1973ce 7 1973ce 122.000.1 27.000 25 47 6 4 400 100.983 5.200 33 797 1 040 PECCENT SCIE-CO 100E-CO FIAE-COT LANGO 200E-CO 100E-CO TES TES TES TES TES TES 2300€3 3000 0.600 E2200 2 2400 0 604 Spirit 3 9001 YES | Table | Tabl Extended Services of The Control of A52 A52 A53 A53 A53 Mo 7 400s 1.100 0 220 , econ 0.501 0.000 YTS 723 TODAL COR YES 20:4Z 0011 -TABLE TO SEE OF THE SE YES YES YES # 6 mo 1 0 mo 0.1=8 0.092 123 153 713 713 713 AST ASS I/60I YES Tara 🗆 1 330 YES YZS House of the control Ýť. YES YES YES YES TEB TES 0 044 0 044 0 017 AE2 AE2 AE3 AE3 0 051 0 071 0 007 0000 0 00m 0 2 2 2 2 0 2 2 2 2 : : 00000 032 ... 2012 ... 0.0000 0.0000 0 004 0 004 YES YES YES YES YES 0.520 0.520 0,104 0,104 No. 0 001 0 001 : TES **ZD1023** 0250 0.130 : Ÿ£B a.h AE2 AE2 AE2 AE2 AE2 AE3 AE3 donal 0014 0014 0014 0014 0014 0014 6 003 6 003 6 003 6 003 6 003

7232-03 2332-03 4672-02 2 2-008-01 4008-01 8198-00

	$Q_{d}^{*}C_{d} + Q_{d2}^{*}$	C <sub>12</sub> + C	d2 + Qs*Cs = Qr*Cr					Entar Mas Club	Entry toty Dolly	Partition
10	36 Februari	Carpengan	Doe	homeone homeone exerci (Ce)	Sectoral Source (Co)	Industrial (C <sub>L</sub> ) Duty	Industrial Interest (C <sub>1</sub> )	Declarps as recorded by Apparate	Distriction as reported by Applicant	Conficient (Scena ) Late)
Ŀ		700		Day to a	100 to (Cg)	H=	Harstly Am	(C3 inc.	(C) ==	
1	Armenica, a u	NEE,	Mesats Heriori	0	, B	- 0 H	4 O. 7	0	-	0.574
. 4	Berytum		Metals Metals	0	0			0	0	0 226
\$	Ostonem ( Ostonem 13.4 Ostonem ( Ostonem 13.4	_	Metab Metab	0	9			a.	0	0.210
7	Copper**		***	0	`0 0	, 10 10 10 10 10 10 10 10 10 10 10 10 10 1		8	0	0.346 0.205
10	Mercury** Nickel**		*****	8		0	ija D	Ç D	9	0.303 0.505
11	Scientum Sher		Notice Percent	0	0	0	3	.5	٥	:
13	Tradese Zoc-		Metals Metals		:	B / 7		. 0	0	9220
16	Chands Total Phonolic Corresounds		Pletais Pletais		8	0 1	10 A		,8	. :
18	Hardvese (As CaCO3) Acrolein		Motata VOC	: 0	. 0	125 D 116	٠, الم	₽.	0	:
19 20 21	Aldrin	42	88.88 88.88	D:	3 0 0	30		0	0 0	-
22	Brometern"	125	VOX.	.0	2		All the	ő	,0	:
	Circulate Contoccere	462	VOC	B	0	. 27.01		8		:
26	Chiaracthrone McChase" Chiaracthron	AED	AOC AOC	8 .	. 0	0 6	# B +	.0		• :
29	2-Chipro-Ethylemyl Ethyl Chiary Farm	755	AX.	<b>1</b> 00 %		0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0	Q B	0	•
32	44-000 44-001 44-007	755	VOC	6		D M	3 D	5	8 ,	:
H H	0.61-007 Dicklarshraum Helbang* 1, 1-Oxtoro/Date	125	A00.	0,		0		2	0 `	-
35	1, 2-Okthernouse* There 1, 2-Okthern-Ethern	TES .	VOC	0	;	C C	14. 0	a 8	, A	:
37 38	1, 1-Dickharacthylane <sup>2</sup> 1, 2-Dickharacroome	712	VOC.	0 0	0	A Section	1.50	a 11		:
39 40	1, 3-Dehicro-Propriette Deshifte	Y63	VOC			0 0 0 0	0	0	9	:
± 0 0	Ethyltacone Methyl Burndy		88			30 10 m		ā	0 .	:
4 4	Herryk Orlenda Hathytana Orlenda* 1, 1, 2-Tetrachiera-Ethana*	Y23	888		- 0		- 1		0	:
46	Catachina Citylera*	118	AOC AOC			1. 0.25161		6		
9		42	VOC	0	. 8	0	1,78	ê	0	
\$0 51	L. L. F-Trichistorbane L. L. 2-Trichistorbane*	725	VOC.	0 1	;	<b>3</b> 6.5	* D	8	0.	:
S C	Viery) Chinaride*	162 163	ACC ACC	1 8		18.9 <sub>~</sub>		9	6	:
.55		٠.	Aods Aods	, .		0 (d)		0	9	:
35 37 38	2, 4 Denotry Schemal		Acids Acids Acids	8	1.	0		a	D 0 0	:
39 60	4, 5-Cherry-Cress Z. 4-Cherry-hand 4,5-Cherry-2-mc/2-ylaphasad	TES.	Accts Accts	3		Aler D		2°.		:
61 62	Director (2,3,7,8-7CDD)	AER	Acada Acada	1 1		. 20 or 13		0		:
83	4-Notrophonol	145 J	Acids. Acids	8	-			0	ا ئ ا	:
63 66	Phones 2, 4, G-Tricking spherosis	115	Acida Acida	10,		4. F. A. A. S. A. S. A.	0	0	0 5	: .
6.5		,	Bases Seres	:	6	0 0			8	:
70	Rengitives		Rents Rents		0	0	1	6 B	0	:
77 73		AER	Bhes Cues Erecs	, a .	0	Derry 1		6	0	
75 75	Seco(Od)Payers		Ses Bee	و ا				0	8	
7	Sis (2-Oxforcethons) Methers Bin (2-Chlorosthy))-Ethers	1955	lanes Later	'8	0	Hai a lin	经补收费	2	a a	:
7	Bis (2-Ethylberyl) Pidhelsta"	115	Sec.	0	:	#10 H		3	23	:
80 01	Day Burgs Foreign	i	1000	3						:
8 2 3	2-Odgranuckthukene 4-Odgranuckungs Phonel Ether Chrystene*	בוו	Bases General	8 -		1012		6	î	Ĩ.
45	Delt-Subyl Pro-visite Delt-Outer Pro-visite		Danes Denne	D .	8	1.3	**** 0 · · ·	0 1		: :
E7	Décesso (AM) Ambraceses* L. 2-De Voissessonium	115	Best	0	. G	1 200	-6-	D D		:
90	L +Out-lander-to-e		Beres Beres	6	0	0.00	- 5	8		:
91 92 97	Darthyl Probability	TES.	Canera Benera Benera Benera Benera Benera Canera Benera Canera Benera Ca	B ,	: رق		000000000000000000000000000000000000000	9	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	
l sa		185	Bases	0 2 0 (∰2		200	10.	0 0 0		;
1	2, 6-Destrotores 1,2-Destrotores Endoculos (alpha)	YES	Course		. ق		, fa. 0 . 1	0 0	:	:
9	(Maio Maio (Maio) Terio maio maio maio maio maio maio maio ma	西西	Berers Bases	0				0	0.	:
100	Endris Alderhide	AS2 AS2	Renes Renes			0		0		:
103	Flarene		Barous		0	HHO.			0	
105	Heptachlor Econom	755 753	Care	6	0		R Ireal	l a		:
107	Next characteristics	AG .	EASES EASES	0	0	1 0 0	100	9	0 9 9	:
109	Hermanner (beta)	2000	Janes Janes Janes	0		0.2				1 :
111	HauditurorduPerticlere	"	Sees	0	1. 0	1.6	0			] :
112	Indexe(1, 2, 3-CX)Pyrese*	, xca	Bross	0.	0	il oilh		0	۵٠	:
115 116	Nachthalore		Bases Bases	i .	0	, al	0			:
112	N-1859andi N-Propphening* N-185randi N-Padrylaning*	AZZ	Same Same Same Same		0		2.0	I 0	0 0 0 0	:
111	PCS-1018	7E3	Same:	, o		1 1	- 0		6	:
122	PCB-1222 PCB-1232 PCB-3242	AER			ļ	L D		, B	0	:
127	PCB-1248	755 783	Bases Davis			To Military		6		:
121	PCB-1262	MER .	Bases Bases		. :	964				:
12	Phopustives	1	Rates	1 3	1 :	D 2	E San Lan		1 8	ı :

0.2	Enter Co = treatmenter discharge flow from facility (MGII)
0.370+458	Q = macleorater then harge flow (chi) (this value is cultristed from the \$400)
0	Enter from from spell over descharge Dd2 is last sprouted stream from m MGD above panel of studiosys
0	Col) is territorized about few from applicant source (ch)
127.97	Enter 7(310, Q, 4 Incliground streets fore in the score point of decharge
470,98	Enter of estimated, 1014, Q. = sector aund shown flow in othe stone point of decharge (1010 estimated at 75% of 7010)
(AN LAS	Entire bless Annual Flow, O., a purporand stream flow in of, specie part of discharge
197.24	Sittle 702, Q, a backgrain'd street flow in the share point of drackurge (For LYYF class schools)
	Enter C became on company polyteric consumerant or pop-
C Flat	(estimate the is pure V unless there is distri-
of +013+0*	D, a provident in servan flow, after descharge
Calculated	C, in Productional In-ethicaria publicaria concembration in 140/1 in the
-	stream (after complete mixing novime
2	Enter, Exclaranti Hardress obers part of decharge (pagement SC Smath of Bernmettern and 100 North of Bernmettern)
7.00 EA	Errier, Seckground pit shows part of decharge
Ą	Enter, is decharge to a stream? "YES" Other spigor would be to a Eake. (This changes the partition coefficients for the michity)

as prod bactor trailer

December 3, 2018

Г	raine jume , NFEE ha.			<del>,,,,,</del>	-	_					_									
200	manager Pitts department. Special Section 1997				Address		Larry States W	- 45.800.3	1 Page 1	(Det)	-	been A FTG	193 45	Harris Santi	Carretor A	For & Water too	Town	or Care.	- Made	
112	The second second	MONN	Amost as	San Control	Mar Cory Decreça es Approación	Fertilian Comp	4 - V	Luc Q Lucy		Decrees to	Harry St.				Table No.		<b>職權。</b>	1970	and the second	CLIMBERS' THE
		(P)	5 W.	1	Appendix		Part of			Table of the control			982	ENEW PPI	Hope (IL)	1 1		And Could	Prof. Person	
=		.4	F. 2	Constant	1	Creen (C.) TOTAL C.		-		15	Come (C	6.3	12 mil	秀	30.4 A		- T	2.00	TETRACE I	(===-
1	Autorice .	-				Card Stage		10004414		i	201274	\$30674 GE	70E11E2001	- 🚣	1200	121-01	4 PASS-03 - 14	3 736 -C2 3 036 -61	\$74E40)	1 chillengy and
13	Services Coulesce		1	1		4347	10 E 777	(32) 1,6334 B	-		سەن		ACTA LET	÷	:	. :	- :		• :	
1 :	Control Control 8 Control Control 8	"	1	1	6	1637 913	70349 501	4973 63917 N		0 4	11 (CC) 17 700	EUR2714	BARA PASTAN BARA PASTAN	· h	1	1000	Canada In	<del>-                                   </del>		:
1			1	1		1 0 000 1 00 001 3 400	27411 JA4	4040.8700 H			E 701		1314 047213 6 1472114337	22	4150	Hiteet	170E-07 M	476 02	NACE-CO	1125-b 10
~;;	Verse					4154G4 20 020	Free Par	137121 263 H		👬	100	10137 471	D24	***	4114-45 1634-62	1346-06 3316-08	1677-08 has 8672-04 has	} 434.40	202700 172700	4 (23)-04 No.
1 1	مندو		<u>.</u> .	: '	1 :	D 878	40.00	297 4 2002		1 .	:	: .		.:	124.01	1 Inter	7016-61 No	1141	. s kë-a	1112 m
1- ;;	for Cycles	,		:		12 007	pre to	47718 PRAST P	:  :		9 200 9 200	1753×714	2117 M1114	The Control	1 ME-03	(E3-67	1808-05 Ho 1808-04 Ho	148-04 11E-03	) MC-CI	S FRENCH PAR
1	Fatal Promote Composite Hardware (An CeCCC) Agricus	١.		3		.:	;	:	:   ;	-	:	:	:	;	1 :_		. 1			
1.5	Apple dis		763 VK#			_ <u>:</u>	:	et) 801777 h		:	;	•	:	:	४१६४०) १४७१-ध्री १३०१-६	\$ 612-03 \$ 607-02 \$ 440-01	1705-03 10- 1705-03 10- 1702-01 10-	144E400	174E-03	273-00 to 142-00 to 142-00 to 142-00 to 144-00 to
1 2	3000 30000		145	1 :	; '	100			[ ]	1 :	i i		:	:	4128402	\$ 1.00-00 \$ 1.00-00	1 10051001 100	13/23-07	1145-0	5 HZ-01 W
1 2	Coffee Talkarden		TES		ì	140	MM 227	E31 040417 A	.   .	1 :		e Tad	17-matus44	Me	Preses ATIX DE	1442-01	176-2 14	178.06	1年中	184-0 m
1 25	Contraction of the Contraction o		ÝEJ	:	1 2	;	-:-	:			;		:	:	1 172 -C1 3 946-01	3 44E - CL 7 BOE - CJ	1807-01 14	7 61E+02	1412+06	3 ELE-04 - 64
1 3	Chapter Character Char		l .	:		:	:	1	:   :	9	1 ;	:	:	:	: -	.:	;	<u>:</u>		
1 20	6.7 (200		A.1	•	*	:	:	:		8	:	•			\$436-00 15:544 1299-44	1 010-05 1 441-10 7 411-20	ESTE-DA THE SHALET HE CHECT HE	11150	1 ME-19 3 455-00 3 456-00	10 10 20 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
"	16.007		YES TES	!		1100	1879 217	angire .			p 2005	2020	0.000001	÷	(TEMOR	141-0 141-0	4 (40) (40) (40)	1 205-0-	3 436+90 3 436+00 1 216+55	4 123 01 Ha
	1, 1 Deline Compan 1 2 Deline Compan		785	<b>i</b> .		[	:	: .		1	H	:			3720	7116-63		1145-01	105-0	40344 N
:	Trettleren		1785	[ '		:	:	:	.		H		:	:	124-0	2 142+04 8 165-04	12Y-01 to	1176-03	1,000-411 3422-47	2 40E 40F DE
1 5	1,2 Contintationers 1,3 Contint Programs					;	•	:	:   :			•	•	:	4 87,8 61 3 e08,61	9 (10E-42) 9 (1)E-42) 1 (1)E-47)	12K-62 Pe	8 4 MG-003 1 3 PG-01	1755-04 2445-34	347-03 12
4	Distriction Fringery and		423	!	9	0,540	307 1537	72 2065417 6	•   •	1	S 0788	112444	E INSTRUIT	Ha.	3 tans cap 4 and 4 ta	# 17 - OL	11750 Po	1747-03 1747-03 1716-02	\$ 96E-07	1 1mC 01 100
5	Maria Barrata Maria Catalan			;		;	:	:			:	:	:	:	1942/01	10244			1,775-64	
4	1 1 2 2 (Continuitions 1 1 2 2 (Continuitions 1 (Continuitions)		70	;		:	:	:		:	:	:	:	:	143441 143441	\$ Paleon \$005-00 \$ 100-00 \$ 205-00	175-04 to 175-03 to 175-03 to	3 mi -c2	日本年代 日本年代 日本年代	1312-00 for 4471-00 for 1302-01 for
	T####			:		S FMG	111178	2231644		:	£ 0003		6 cm 13,1800 m	Ŀ	1215-05	126-0	11240 10	1 678-00 3 738-00 1 6.75 01	1/75-07	417 HD No 734 HD No 114 HD No 4101 PM
1 4	TIPANITES		781	:		.046	700 146	340 117000 F		}	0 672	100764	20 20 0057	N.				7-	¬ ; -	- :-
18	1, 1 2 Problemations Trementaryland		427	1		] :	:			6		•	:	:	576E41	1 CM -DA	3146-63 10	9 10E+00	1706 · 22 1727 • 45	3 ASSESSED THE
1 1	Verd Chiangs Pr-Closes 41-Closes		YEA	l i	8	:	:	-:	:   :	- :	÷		;	:	246.00	11/2:0	Paul Pi	1 422 100	2.7×8+64	1425-00 1
1 2	1 Opportuni			1	, s	1:	:	: -		- 8	} :	-:	:	:	551E+01 862E+01	THE OF	230E+04 Ha 246E+04 Ha	9.710-01 _ 1.720-02	1 17E-01 1 45E-08 1 0TE-08	1645104 No.
8	1.40-00-00-00 4.60-00-00-00			:	8	: '	: -	· :-	:   :	1 8 '	1 :	2	:	:	2819-07	(m.		444		-302-in- in-
1 8	2 ADrianos		ME8	;	-	:	:	:	:   🚦	1 -	:	:	:	:	6 356+01 1242+01	122-01	A PREVIOUS TO	\$165-07	3 (SE-CA	STATE OF THE
	24751CDC		1815	;	•§·	:		; -	1		· .	- :	:	÷	1626	i pay on	TANK OF HE	1372.00	SPT-CA_	TENEOR FA
1 6	f transport Participation and Participation and		YÊT	- <u>                                  </u>		*****	100 70	अध्यक्षेत्रक ।			7 453	175A2 304	2717 04047	•	2 545 UT	1.765-43 2.066-47 1.865-44	0520402 Ha	1771-00	1426-00 1426-00	1725-01 1± 1925-01 1±
	1, i Si-piiropina Nonellan		7E3		ř	l :	:	:	1 :		I :	:		:	578.45 1345.45	1.845-04 8.312 Hz	175-00 W	114-6	204E+04	1 ME - 03 Au
	terminano terminano		1	:	9	:	:	:	:   ;	:	1	:	:	:	324E163	1 173+07	2142-00 15	2335164	414.0	147E-01 No.
	Specialisms Specialisms		771		3	:	:	:		1	:	:	:	:	1140 D	1 345 47	1307-07 10	1166 04	2302 01 2008-02	4 256-41 No
	Security and the security of t		421	;	.5	] :	:	:	:   :		:	:	:	:	1340	8 24E-04 8 7 · E-02	1.25E-01 Au 1.84E-00 Au	1075.03	3 442 451 4	4000-PH No 4100-PB No
l n	Service Company trees Service Company trees			1		:	:	:			;		:		thic	B 11E+00	134E-00 Pm	1078.61	\$165-01	6 33E-00 No
1 73	Sie (3-Chieramana Velhaus Sie (3-Chieraeth) (5-Ether		***	1 1	:	:	':	:		l i	, :	:	;	:	1266-01	3100-01	1 108-427 194 1 408-401 194	3 1/10 DF	\$ 84E+02 7 4PE+01	1972-03 60
1 25	Self-Companient Com Self-Companient Commit		rt.)	[	*	:	:	:	: I		:		:	÷	6471-01	1815-10	1775-CD 14	1261-00	1 CAZ-CA	FERENCE NO
1 6	Literature from the Berteri Privata 20-manifes					:	:	:			Ιí	:	:	:	6711-61 6861-60	1 177-60	144-9 1	1181-65	3793-01 1863-03	1387-00 to
1 5	6 Charlestony Righty Char Chromas		Y43			ΙĖ	:	:			H	:	:	:	3250	a TIC-PI	122-01 1	1 PTE 42	2054F	ADER N
:	DA BAIFREUR DA Dej Peters				5	:	:		-  }		H	- 1	:	:	1 22 400	344.44	100.00	24-11-03	NX-W	1045-34 (10
	1.200 mary and a second		YE9 .			:	:	:	:   🎄	8.	;	:	:	:	111E-D) 544E-DI 240E-DI	4 PE+44	THE AND THE	1.60E-02 6.60E-02	大円兵(日)   大坂(内)	4078-01 to 1471-25 to
:	1,5Debestages		٠.	·{·		:	:	:	:   :	- B	:	:	:	:	\$ 41E+01	196.0	PET SEASONS	1 (25-22	116E+08	1 12 C - C - C - C - C - C - C - C - C - C
:	1 10ctravers Day Phase		×	! '	1 1	:		:	:   :	' 0	:	:	:	:	134444	1 PE-07	1401-00 00	1 100 A	1:底·四 1:底·四 13底·四	1125-01 No 1040-07 No
:	E sometimes E sometimes		125			:	:	:		, ,	1	:	:	:	1004 (1	1 (TE 40)	100E+63 (4)	1867-40) 1 mg 420	1754	125-04 h
	1.POmteroflictum Etites.Pat Lettes		453		:	;;	m 22	erbaleme .			-	121,000	; ====================================		116540 616540	6 47 E+01 7 EEE+01	1 225-09 4m	1 11E41	134E-07	177-0
	Endon-Aur Greig		461	1	"; "	672	129 062	ES DUTCHME .			0,000	11350	za ramen za	7	5.364+01 4.165+05	1 8075 - CR	1 000-000 Am	10-94 B	0 <del>400 - 40</del> 0 400 - 60	1 E7E+25 No.
100	Engin Naturals	4.	VES.	1	; '	0.000	150 978	257967941			4004	73.100	14 everypta	÷	1 7 15 di	3 KE-61	1 6225-02 HP 4 548 HP , No.	BANEST LTHEST	8 Post -02	A PORTOR NA
116	Page 100 and 1	_		1	9	:	:	:			.:		:		7 &16+03 2 852+02	1 MIE-05 1 MIE-08 5 PMI-01	3122-01 No 3035-03 No 1756-01 No	1 12E+01 3 114+03 4 63E-05	6 Table 04	1325-30 ha
101			12		, .	617 510	Pp 1 Cma Pp 1 Small	796 3031 74 A		:	100	7775	t franklin S la Piena	7	1 82 CA 2 70 CA 1 8 CA	6 PM 61 6 LIF 61 6 178+00	1 EC 00 1-	4 CM 45 2 700 40 1 400 C4	10年代 11年代 11年代	1 385-00 PO 1 706-07 Po 5 PLE 07 Po 6 385-07 Po 1 006-07 No 1 1 26-07 No
194			753		1 :	:	:	:	:   ;		;	· ;	:	:	45.BE24	\$ 1 mm etc.	1045-25 14	4 0018+63	3.002 -05	1 10 C-06 4m
"			451	!		1	:				:	÷	;	:	1420	1717-02		117.4	1 ME-73	108-01 No 312-01 No
111			7(1)	!	9	***	1486 571	750 272144			;	,			\$1.00 en \$440400 1 000400	1 ME +04 2 ME +04 2 ME +04	1805-01 H	1 (#5-00 1 #55-00 1 #55-00	\$ 505-404 \$ \$76-604 \$ 505-603	4 CONFICE 100 2 ECSING 100 1 PME-02 344
100	named 2 3 ChiPrison		723	!				:				3	•	:	13:643	6 May + 41	178247 10	1645	105-01	4 四字位 100 2 四字位 100 2 四字位 100 2 四字位 100 2 2 五字 100
1:					\$ \$	1 :	:	:			:		:	:						• •
1 12	National Superson		AET AET		}	:	:	:			: .	. :	:	:	1 406 407 CO 2730 0 2500 CO 2500	1 3X-01	357E-04 No.	1 PM 47	174-0 186-0 186-0 186-4	113-0 W
			WEI .		1. }	:	:	;	:   :			37 425	********	No.	1013	9 30C-91 1 30C-91 1 407E-03 2 00E-01 2 00E-01	LOTO No	4 (mil -42) 2 mail 47 1 MS-40 3 EDG-40 2 7 ef 40	THEO	1945/00 No 1135-00 No 1956/00 No 1956/00 No 1456/01 No 1436/01 No
12	PCB-1018 PCB-1227 PCB-1022 PCB-1013		ACI	1	1	:	:	:	:		8 014 0 014	,34 LD		No No	17Maica	7 CHE-61	1.47E-61 Fm	3745-03	7 116 01	
12	PCB-1246 PCB-1246 PCB-1214		40000			:	:	:			6 P14 6 P14	78.425 28.425	\$ \$440-130E	*	\$735.06 1746.03 3745.03	FOREAR FOREAR FOREAR	1.47型07 Na 1.47型07 Na 1.47型07 Na	114 G	7316 01	1 42E OF Feb. 147E OF May
1 12	LPCB-1300		45		8	:	:	:		:	9034	2 43 2 43	1 MAGE	***	3745.05	100041	1020 6	1146.00	711E-61	1478-01 No 1478-01 No
	1,2 61/Personano		1		8	:	:	:		:	1 :	:	:	:	1244 CZ 2146 HH	1 (PE-04 53:E-04	344-CS 441	2 8 M 475 4 Cast + 57	476-04	-
<u> </u>	ii'' siwanana	ш.			1 2		•	_ <u>-</u> _	<u> </u>	<u> </u>	<u></u>	<del></del>	•	•	1 1 20 101	77.5	TEMPORE NO	400,00	CT:E=	A SEC. AND ADDRESS OF THE PERSON NAMED IN

# ANTIDEGRADATION RATIONALE

Permit Number: AL0083763

Facility Name: DC Alabama, Inc. Receiving Water: Tallapoosa River

Stream Category: Tier 2 as defined by ADEM Admin. Code 335-6-10-.12

Discharge Description: Process Water and Stormwater

The following preliminary determination was prepared in accordance with ADEM Admin. Code 335-6-10-.12 (7) (c):

The Department has reviewed the information submitted by applicant in accordance with ADEM Admin. Code 335-6-10-.12 (9). The applicant has demonstrated that there are no alternative options which are economically feasible or technically viable. In the case of technically viable options, the applicant has shown them to be cost prohibitive through the alternatives analysis required by the permit application.

The permit applicant has indicated that the following economic and/or social benefits will result from the issuance of this permit:

- The new stormwater discharge to the Tallapoosa River will prevent inadvertent overflow of water outside the process water containment and reduce the amount of stormwater from the industrial areas to the Unnamed Tributary to Miller Creek.
- There will be approximately 25 contractors employed during the length of the project.
- The facility currently employs 200 DC Alabama, Inc. and contract employees. There is no anticipated reduction in employment as a result of the new discharge.
- The new treatment process and discharge will create an estimated \$30,000 in local and state taxes.
- Land application is not viable for the discharge due to insufficient land area owned by the
  facility, shallow soil surrounding the facility which has limited water absorption qualities,
  and metals concentrations present in the water.

The Department has determined that the discharge as proposed by the permit applicant is necessary for important economic and social development in the area in which the receiving water is located.


Prepared By: Scott Ramsey Date: July 8, 2019



November 16, 2020

The Dow Chemical Company 1940 Ohio Ferro Road Mt. Meigs, AL 36057

Scott Jackson Alabama Department of Environmental Management Water Division – Industrial/Municipal Branch Industrial Section P.O. 301463 Montgomery, Alabama 36130-1463



**Re:** Comments on the Revised Draft NPDES Permit Modification NPDES Permit Number AL0083763

Dear Mr. Jackson:

DC Alabama, Inc. (DCA) appreciates the opportunity to provide comments on the draft modified NPDES permit dated October 20, 2020. Our review of the draft permit reveals that DCA's requested changes have been incorporated. However, additional requirements, including permit limitations and monitoring requirements for bis (2-ethylhexyl) phthalate (DEHP or BEHP) have also been added to the draft modified permit. This letter provides comments on those additional requirements.

We understand that ADEM has included DEHP (or BEHP) based on the inclusion of low levels of these constituents in analytical sample results submitted with our NPDES permit applications. DCA requests that limitations and monitoring requirements for these compounds be removed from the facility's modified NPDES permit based on the following data and information, as listed below.

- DCA manufactures silica metal using quartz river rock (silica), charcoal, and wood chips as basic ingredients in the manufacturing process. DEHP is a semi-volatile organic compound broadly classified as a phthalic acid ester (PAE) and is widely used as a plasticizer in the manufacture of plastics, especially polyvinyl chloride (PVC). It is ubiquitous in the environment and can be found around the world wherever plastic products are made, used, or disposed of. DCA does not believe that DEHP is present in any of the materials used in its manufacturing process or in any of the facility's stormwater source areas, thus, there is no reason to expect that it is present in the facility's stormwater outfalls
- A number of peer-reviewed technical papers have been published which indicate
  the difficulty in accurately analyzing for the presence of DEHP in laboratories. A
  sampling of these documents is provided for your reference in Attachment A and
  includes the following:



- The Wisconsin Department of Natural Resources special guidance to address the issue of false detections of DEHP in groundwater monitoring wells (Publication Number PUB-WA-1011 Rev. 2002).
- A 2013 paper Net, et al discussing the difficulty of accurately quantifying low concentrations of phthalic acid esters (including DEHP). The authors stated that this was because "they are ubiquitous and could be present in water, organic solvents, air, glassware and the plastic material used for the analysis." The paper presented the authors' findings regarding specific laboratory quality control procedures intended to minimize sample contamination during analyses to measure phthalates.
- Similar permittees have evaluated reports of the presence of DEHP in manufacturing processes that would not made use of the material. Specifically, a study conducted at the U. S. Steel Fairfield, AL facility in 2017 was conducted as DEHP was intermittently reported to be present in some of the stormwater samples collected at the facility. The results of a split sample study concluded that "no consistent detections of BEHP (DEHP)" were observed at the facility's process wastewater outfall or at internal source waters.
- ODCA reached a similar conclusion to U.S. Steel regarding DEHP detections in samples collected during preparation of DCA's initial NPDES permit application in 2018. Of the 42 samples analyzed for DEHP between February 2018 and April 2018 by the TestAmerica laboratory in Pensacola, Florida, 20 samples contained detectable amounts of DEHP. However, 18 of the 20 samples also had detectable amounts of DEHP in the laboratory method blank, indicating laboratory contamination.
- In October 2019, Jacobs Engineering Group, Inc. (Jacobs) completed a study to determine the cause of unexpected and inconsistent DEHP concentrations in groundwater samples collected from monitoring wells at the DCA facility. Groundwater samples were collected from five monitoring wells and split samples were sent to the TestAmerica laboratory in Pensacola, Florida, the lab used for previous sample analyses, and the TestAmerica Laboratory in Houston, Texas. The TestAmerica laboratory in Pensacola, Florida detected DEHP in three of the five samples at concentrations greater than the maximum contaminant level (MCL) for groundwater. DEHP was not detected in any of the samples sent to the TestAmerica laboratory in Houston, Texas. This information is summarized in the Semi-Annual Groundwater Monitoring Report for the first half of 2020 that will be submitted to ADEM. These results, in combination with the stormwater results referenced from 2018, indicated that DEHP may have been a laboratory contaminant from the TestAmerica Pensacola, Florida location.



Based on the information presented above, DCA requests that limitations and monitoring requirements for DEHP be removed from DCA's draft modified NPDES permit. DCA appreciates this opportunity to provide comments and is available to answer questions or discuss this issue further.


Sincerely,

Meredith Bruick Site Leader DC Alabama, Inc.

Attachments

Problems Associated with bis(2-ethylhexyl)phthalate Detections in Groundwater Monitoring Wells

PUB-WA-1011 Rev. 2002





Waste & Materials Management P.O. Box 7921 Madison, WI 53707-7921

**Description:** This document provides guidance for investigating whether phthalate detections in monitoring wells are false exceedances or real groundwater contaminants, and the application of ss. NR 50716, NR 507.17, NR 507.28(3), NR 508.05 and NR 140.16, Wis. Adm. Code, in these situations.

**Applicability:** This guidance primarily is intended for evaluating the need for assessment monitoring when di(2-ethylhexyl)phthalate is detected in monitoring wells at landfills regulated under ch. NR 507, Wis. Adm. Code. In addition, it may be applicable to landfills for which corrective action is necessary or cases where NR 507 and NR 716 may both be applicable. The recommendations contained in this guidance may have general applicability to site investigations, brownfields, or remediation sites; however, it is not intended to supersede Superfund guidance or existing guidance in the Department of Natural Resources Remediation and Redevelopment Program related to acceptable levels of contamination.

# **Problem Statement:**

Consultants, facilities, and staff have had questions about the validity of bis(2-ethylhexyl)phthalate in landfill monitoring wells, particularly when it is the only contaminant detected.

Bis(2-ethylhexyl)phthalate is a semi-volatile organic compound (SVOC) that is also known as di-(2-ethylhexyl)phthalate, and DEHP. Some DNR programs refer to this compound as BEHP; however, this is not a recognized synonym in many chemical databases. Using this acronym can cause confusion because in scientific literature, BEHP usually refers to butyl(2-ethylhexyl)phthalate (cas number 85-69-8). Although DEHP has been identified as a common laboratory contaminant, phthalates are prevalent in the environment because of their use in plastics like PVC. Groundwater monitoring plans may include SVOCs when facilities investigate elevated indicator parameter concentrations, leachate results indicate possible problems, special circumstances at a landfill raise concerns or a general site investigation is being performed by the Department or others. Data in GEMS indicates that most detection limits reported are at or above the NR 140 Groundwater Quality Preventive Action Limit (PAL) of 0.6 ug/L, so almost every quantifiable result is a PAL exceedance. This guidance attempts to lay out the problems and appropriate approaches to assessing whether with phthalates are really present in the groundwater or an artifact of the sampling and analysis procedures (in other words, a false exceedance). We have reviewed a number of reports for Wisconsin sites and queried other states for their experience with this problem.

# Recommendations

Whether DEHP is detected during assessment monitoring or in conjunction with other monitoring done at a site, staff should ask the facility to investigate whether the DEHP is a false exceedance attributable to sampling or laboratory procedures.

If sampling procedures or field conditions are identified as contamination sources, the facility should be instructed to change their sampling procedures to eliminate the contamination source. This may mean changing sampling equipment, materials or collection method. Although some have proposed filtering as a

means of excluding DEHP particulates from sampling, there is a general consensus that **filtering samples is not an appropriate option.** 

If the source of DEHP is attributed to laboratory contamination, the facility should be directed to obtain additional analyses for which laboratory contamination is controlled. The facility may need to switch laboratories if their laboratory is unable to control contamination adequately.

If the facility is requesting the cessation of assessment monitoring and DEHP is the only substance detected above the NR 140 PAL and the facility has demonstrated that DEHP is a false exceedance as per 508.05(1), then staff may allow the facility to discontinue assessment monitoring. If the concentrations of DEHP cannot be fully attributed to a false exceedance, staff should consider whether it is more appropriate to discontinue assessment monitoring or to propose alternate assessment monitoring as provided in NR 508.05(2) and (3)(a).

If the facility has not begun assessment monitoring, DEHP is the only substance detected above the PAL and there are no other reasons for assessment monitoring, then it would not be necessary for the facility to initiate assessment monitoring.

# Suggested Approach to Determine the Credibility of DEHP Detects

Given the prevalence of DEHP in the environment and the high potential for contaminating samples, the source of DEHP in groundwater cannot be dismissed automatically as sampling or laboratory error. It may be necessary to modify sampling plans to incorporate additional blanks and to change sampling protocols. Ultimately, any corrective action or requirements for assessment monitoring will need to be based on evaluation of all available information and the applicable rules.

# **Assess Blank Results**

Method blanks are useful for determining whether laboratory procedures introduced any contamination into the analysis. Although facilities are supposed to flag data when a contaminant is detected in the method blank, you should not rely solely on the flag in assessing the source. Experience has taught us that data is not flagged reliably and even when flags are present, the concentration of the contaminant in the method blank may not be reported or available in GEMS. If method blank results are available and the concentration of the blank is less than 5% of the sample concentration, the DEHP concentrations in the sample may be biased high, but cannot be attributed entirely to laboratory contamination. If the concentration of the sample is in the same range as the method blank, sample results may be the result of laboratory contamination. If the concentration of the method blank is near the detection limit or less than the limit of quantitation and sample results are in the same range, we suggest that sample results could be attributed to contamination. If method blank results exceed the LOQ, the facility should take steps to obtain sample results under circumstances in which laboratory contamination is better controlled.

<u>Field blanks</u> may be quite useful in determining whether sampling is contributing contamination. You should be clear about how these blanks were collected and what they represent. To the extent possible, field blanks should be collected in the same manner as the samples, i.e. be exposed to the same equipment and materials as the samples. In evaluating these results, you may need to consider what water was used for a field blank. If the water in the blank is from the same container as was used to clean equipment and without additional information, it may not be possible to determine whether the water or the sampling equipment is the source of contamination.

<u>Rinsate blanks</u> may also be useful indicators that sampling is the source of DEHP. As with field blanks, investigators should be clear about what rinsate blanks represent. Typically, these blanks are collected after equipment is cleaned and represent potential carry-over between sampling stations. These blanks may also provide an indication of rinse water contamination if this blank is from the same source as the rinse water.

<u>Trip blanks</u> are not generally collected or used for semi-volatiles and may have limited use in evaluating the source of the contamination because DEHP does not volatilize at an appreciable rate. These blanks typically are supplied by the laboratory and accompany samples without direct exposure to field conditions.

# **Change Sampling Procedures**

Although evaluating blanks is an important first step in investigating sources of contamination, not all procedural problems result in contaminated blanks. The <u>History</u> section below highlights possible sampling artifacts that are not easily proven or addressed. Obviously, any equipment or supplies that are plastic or are in contact with plastics should be carefully evaluated. It may be necessary to choose another sampling procedure and compare results. For instance, if investigators believe that bailing is causing abrasion to the well casing or that the well casing is flaking, it may be wise to sample using a pumping procedure. Because DEHP adheres strongly to any particulates, filtering the samples is not an acceptable modification to sampling procedures nor can it be used to "prove" that the source of DEHP is the well casing.

#### Other Considerations

In addition to evaluating blank results, facility or staff investigations of DEHP detections should include the following considerations:

- What about well construction materials?
- Is the piping or casing PVC or other plastic?
- Is the piping or casing steel?
- Is there other evidence that the landfill is leaking?
  - o Are indicator parameters elevated or do they show a trend?
  - Are VOCs present? (VOCs may increase DEHP solubility)
  - Are petroleum contaminants present? (As with VOCs, gasoline and other petroleum products can act as a solvent for DEHP)
- Is there a pattern to the detected values?
  - o Is it detected in the leachate?
  - o Was it detected in background or up-gradient wells in the "same" concentration range?
  - o Has it been detected historically in the affected wells?
  - o Are detected concentrations consistent over time? Are they erratic?
  - o Were affected wells constructed in the same time period?

Evaluating whether the detected concentrations in the down-gradient wells are the "same" as background wells can be somewhat subjective. Usually there is only one result per sample, so investigators may not be able to determine the variability associated with sampling and laboratory analysis adequately. Absent other information and as a rule of thumb, down-gradient results two to five times the concentration in the background well may be considered to be in the same concentration range. This evaluation can easily be complicated if blanks also show contamination. Frequently, there are insufficient data to apply statistical techniques to determine whether differences are significant. For instance, to understand and assess the variability in various data points, multiple analyses of the same samples may be necessary. Before using a statistical approach, it is important to consider the underlying principles and assumptions of the statistical tool proposed to assure that it can be applied appropriately to the data set.

#### History – Sites Where DEHP is Attributed to Sampling

After detecting DEHP in groundwater monitoring wells at concentrations in excess of the NR 140 PAL, a number of consultants and laboratories performed investigations to determine whether the source was sample contamination. The investigations generally ruled out laboratory contamination as the source because method blanks were either free of contamination or the concentrations of DEHP in the method blanks were much lower than concentrations in the samples. The investigators have attributed detects in the wells to degradation (aging) of the well casing, microbial action (iron bacteria) on sample tubing and abrasion on well casing, bailer and rope associated with bailing procedures.

At this point, contamination from sampling cannot be attributed to any single sampling technique. At one facility using bailers, the field collection personnel reported that visually turbid samples seemed to be a predictor of phthalate concentrations. Subsequent analyses of scrapings from the bailer and ropes indicated the presence of DEHP. They proposed filtering samples as a means to more accurately assess the true DEHP concentrations in the wells. At another facility where sample crews used low-flow pumping and collected field blanks, investigators visually examined tubing that had been dedicated to sampling an affected monitoring well and noted the presence of black mucilaginous material on the walls. Field blanks collected through new tubing did not contain detectable DEHP concentrations; however, blanks prepared using the tubing dedicated to the well contained significant concentrations of DEHP.

During Superfund Site Inspections in Northeast Region, DNR staff found phthalates both in groundwater and rinsate samples, regardless of the site under investigation. The investigators traced the phthalates to contaminated rinse water. They tested water directly from the still and found that it, too, contained high phthalates so contamination could not be attributed solely to storing the rinse water in plastic carboys. There are sites, however, for which phthalate concentrations cannot be attributed to sampling or laboratory analysis.

Additional Chemical Information and Environmental Fate of Bis(2-ethylhexyl)phthalate Bis(2-ethylhexyl)phthalate (CAS Number 117-81-7) is one of several common names for 1,2-Benzenedicarboxylic acid, bis(2-ethylhexyl) ester. DEHP is common in the environment because of its use in plastics. Sampling and laboratory equipment, monitoring wells, and waste disposed in landfills may contain or be constructed of plastics. In addition to its use in plastics, DEHP is also used in inks, adhesives, coatings, pesticides, cosmetics, vacuum pump oil and as a dielectric fluid in ballast capacitors and other electrical equipment (e.g., transformers).

DEHP has low solubility in water (300 - 400 µg/L), is soluble in most organic solvents, and evaporates slowly into the air. In the environment, DEHP will attach strongly to soil particles or humic material. Although DEHP may biodegrade under aerobic conditions (e.g. in lakes or rivers), DEHP has not been shown to degrade in anaerobic conditions, such as landfill leachate. Additional information on DEHP, its environmental fate and toxicity can be obtained through EPA's Substance Registry System (SRS) by searching for the compound and following the Related Links at the end of the compound listing (<a href="http://ofmpub.epa.gov/sor\_internet/registry/substreg/home/overview/home.do">http://ofmpub.epa.gov/sor\_internet/registry/substreg/home/overview/home.do</a>). The TOXNET website accesses several chemical databases and is also good source of information. <a href="http://toxnet.nlm.nih.gov/cgibin/sis/htmlgen?TOXLINE">http://toxnet.nlm.nih.gov/cgibin/sis/htmlgen?TOXLINE</a>

# Contact <u>DNRWasteMaterials@Wisconsin.gov</u> for further information.

**Disclaimer:** This document is intended solely as guidance and does not contain any mandatory requirements except where requirements found in statute or administrative rule are referenced. Any regulatory decisions made by the Department of Natural Resources in any matter addressed by this guidance will be made by applying the governing statutes and administrative rules to the relevant facts.

**Equal Opportunity Employer and Americans with Disabilities Act Statement:** The Wisconsin Department of Natural Resources provides equal opportunity in its employment, programs, services, and functions under an Affirmative Action Plan. If you have any questions, please write to Chief, Public Civil Rights, Office of Civil Rights, U.S. Department of the Interior, 1849 C. Street, NW, Washington, D.C. 20240.

This publication is available in alternative format (large print, Braille, etc.) upon request. Please call 608-266-2111 for more information. Note: If you need technical assistance or more information, call the Accessibility Coordinator at 608-267-7490 / TTY Access via relay — 711.



# WISCONSIN DEPARTMENT OF NATURAL RESOURCES NOTICE OF FINAL GUIDANCE & CERTIFICATION

Pursuant to ch. 227, Wis. Stats., the Wisconsin Department of Natural Resources has finalized and hereby certifies the following guidance document.

# **DOCUMENT ID**

WA-19-1011-C

# **DOCUMENT TITLE**

Problems Associated With bis(2-ethylhexyl)phthalate Detections in Groundwater Monitoring Wells

# PROGRAM/BUREAU

Waste and Materials Management

# STATUTORY AUTHORITY OR LEGAL CITATION

Ch. 289, Wis. Stats.; chs. NR 507, 508, 140, Wis. Adm. Code

# DATE SENT TO LEGISLATIVE REFERENCE BUREAU (FOR PUBLIC COMMENTS)

11/25/2019

# DATE FINALIZED

December 18, 2019

# **DNR CERTIFICATION**

Sept Plan Rossen

I have reviewed this guidance document or proposed guidance document and I certify that it complies with sections 227.10 and 227.11 af the Wisconsin Statutes. I further certify that the guidance document or proposed guidance document contains no standard, requirement, or threshold that is not explicitly required or explicitly permitted by a statute or a rule that has been lawfully promulgated. I further certify that the guidance document or proposed guidance document contains no standard, requirement, or threshold that is more restrictive than a standard, requirement, or threshold contained in the Wisconsin Statutes.

December 18, 2019

Signature

Date



# Reliable quantification of phthalates in environmental matrices (air, water, sludge, sediment and soil): A review

Sopheak Net, Anne Delmont, Richard Sempere, Andrea Paluselli, Baghdad Ouddane

# ▶ To cite this version:

Sopheak Net, Anne Delmont, Richard Sempere, Andrea Paluselli, Baghdad Ouddane. Reliable quantification of phthalates in environmental matrices (air, water, sludge, sediment and soil): A review. Science of the Total Environment, Elsevier, 2015, 515-516, pp.162-180. 10.1016/j.scitotenv.2015.02.013. hal-01784708

# HAL Id: hal-01784708

https://hal-amu.archives-ouvertes.fr/hal-01784708

Submitted on 3 May 2018

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

# Reliable quantification of phthalates in environmental matrices (air, water, sediment and soil): A review

Sopheak Net<sup>1\*</sup>, Richard Sempéré<sup>2</sup>, Anne Delmont<sup>2</sup>, Andrea Paluselli<sup>2</sup> and Baghdad Ouddane<sup>1</sup>

<sup>1</sup>Université Lille 1, Laboratoire LASIR (UMR 8516 CNRS), Equipe de Chimie Analytique et Marine Cité Scientifique 59655 Villeneuve d'Ascq, France

<sup>2</sup>Aix-Marseille University, Mediterranean Institute of Oceanography (M I O), 13288, Marseille, Cedex 9; Université de Toulon, 83957, CNRS/IRD, France

# Submitted to Science of the Total Environment

Net, S., Delmont, A., Sempéré, R., Paluselli, A., Ouddane, B. Reliable quantification of phthalates in environmental matrices (air, water, sludge, sediment and soil): A review. The Science of Total Environment. 515–516 (2015) 162–180. http://dx.doi.org/10.1016/j.scitotenv.2015.02.013.

\* Corresponding auteur: Dr. Sopheak NET

Email: sopheak.net@univ-lille1.fr

Tel: +33 (0)3 28 77 85 24 Fax: +33 (0)3 20 43 48 22

#### Abstract

Because of their widespread application, phthalates are ubiquitous in the environment. Their presence in the environment has attracted considerable attention due to their potential impacts on ecosystem functioning and on public health, and their quantification has become a necessity. However, PAEs are ubiquitous in the laboratory environment/products; analysis of real samples with a low PAE background can be difficult. Therefore, accurate analysis of PAEs in environmental matrices is a challenging task. This paper is a synthesis of the extensive literature data on the most performance methods for extraction/pretreatment and quantification recently developed for quantifying PAEs in different environmental matrices (air, water, sediment and soil). The procedures of quality control and quality assurance are also presented to overcome the problem of sample contamination and the problems encountered due to matrix effects. This paper also provides useful information about the material preparation, sample pretreatment and the quantification to avoid overestimating PAE concentrations in environmental matrices.

**Keywords**: phthalates, DEHP, environmental matrices, quantification, derivatization, GC/MS, LC/MS.

# Table of contents

SUB	JBMITTED TO SCIENCE OF THE TOTAL ENVIRONMENT	1
ABS	BSTRACT	2
INTI	TRODUCTION	3
1. 0	QUALITY CONTROL AND QUALITY ASSURANCE	3
	1.1. Materials and chemical preparation	
	1.2. Procedural blank	4
	1.3. Quantification of concentration	
	1.4. Recoveries studies	
	1.5. Sample storage and transport	
2.	EXTRACTION OR PRETREATMENT TECHNIQUES	6
	2.1. Water sample	6
	2.1.1. Liquid-liquid extraction (LLE)	6
	2.1.2. Solid phase micro extraction (SPME)	7
	2.1.3. Solid phose extraction (SPE)	7
	2.2. Sludge, sediment, SSM and soil samples	8
	2.3. Air samples (gas and particulate phases)	8
3. C	CHROMATOGRAPHIC ANALYSIS	
	3.1. Direct analysis of PAEs	
	3.1.1. Gas chromatography	
	3.1.2. Liquid chromotogrophy (LC)	9
	3.2. Derivatization method	9
CON	ONCLUSIONS	10
ACK	CKNOWLEDGMENTS	10
RFF	FERENCES	10

#### Introduction

Phthalates or phthalic acid esters (PAEs) are widely used since 1920s in the manufacture and processing of plastic products as plasticizers. To date, PAEs are used in a very broad range of industrial applications (Serôdio et al., 2006; Simoneit et al., 2005). Not chemically but only physically bound to the polymeric matrix, PAEs can easily be released into the environment directly and/or indirectly, during manufacture, use, and disposal (Cadogan et al., 1993). PAEs can be eliminated from several environmental matrices by different biotic and abiotic pathways and are not expected to be highly persistent in most media (Barreca et al., 2014; Cartwright et al., 2000; Yuan et al., 2010). However, their extensive use and permanent emissions have resulted in their ubiquitous presence in the environment. PAEs have been widely detected throughout the worldwide environment, including atmospheric aerosols and air (Barreca et al., 2014; Fu et al., 2009; Wang et al., 2014; Xie et al., 2007), in municipal solid waste compost (Farrell et al., 2009), sludge from sewage and wastewater treatment (Dargnat et al., 2009; Reid et al., 2009), river and marine waters/sediments (Blair et al., 2009; Net et al., 2014; Xie et al., 2007), wastewater (Gao et al., 2014) and in drinking water (Gao et al., 2014; Liou et al., 2014). Indoor air where people spend 65-90% of their time is also highly contaminated by various PAEs released from plastics, consumer products within homes, suspended particulate matters and house dusts (Pei et al., 2013; Wang et al., 2014).

A large variety of field and laboratory studies reveal high exposure and evident toxicity of PAEs affecting human health and ecosystems functionning (Cartwright et al., 2000; Kolena et al., 2014). Due to their potential health and environmental risk, PAEs have become a matter of worldwide concern. The use of PAEs is now subject to stricter control and some PAEs have been prohibited or their reduction in numerous products has been recommended (Bette, 2007; Official Journal of the European Communities, 1999). The constraint on industrial wastewater discharges and stricter regulation on the release of PAEs, the quantification of their contamination levels in the environment has become a necessity. In addition, for removal purposes, for the protection of water resources and in the general environment, different environmental matrices should be monitored. However, PAEs are ubiquitous in the laboratory (air, products, reagents, solvents); analysis of real samples with a low PAE background can be difficult. This review provides a summary of the literature data on the most performance methods of pretreatment and quantification recently developed for analysis of PAEs in different environmental matrices. It provides also some useful information to avoid overestimating PAE concentrations. A list of acronyms and abbreviations used in this review is provided in Table 1S in Supporting Information.

# 1. Quality control and quality assurance

Several methods of extraction and analysis that can be applied with good efficiency for determination of PAE concentrations in environmental matrices are briefly presented in Table 1. One of the main problems for PAEs analysis is the risk of contamination, as PAEs are ubiquitous and could be present in water, organic solvents, air, glassware and in the plastic material used for the analysis. Thus, the primary issue for the quantification of PAEs is not the trace analysis itself but the risk of contaminating the environmental samples during the analytical procedure, which can often lead to false positive or overestimated results (Fankhauser-Noti et al., 2007; Marega et al., 2013). Contamination can occur at different stages including during field sampling, sample preparation and up to the chromatographic analysis itself. In real samples, a high background can be observed for the analysis of PAEs. Sample contamination can occur throughout the different steps of the procedures as well (e.g., extraction, transfer or storage). All the steps must be subjected to strict quality control procedures. There are not reliable methods to carry out in situ analysis of PAEs in the environment. All samples should be transported to the laboratory within 24 h. Water samples should be stored at 4°C, and solid matrix samples (i.e., sediment, sludge, suspended solid matter (SSM), atmospheric particle retained on filter, soil, etc.) should be kept at

-20°C. The analysis should be performed as soon as possible. In this section, some useful information about the material preparation, procedural blanks, recoveries studies and the quantification of PAEs are presented.

# 1.1. Materials and chemical preparation

Contamination from the ambient air of the laboratory can be significant. Concentrations of DnBP, DiBP and DEHP in laboratory air have been reported between 0.37 and 3.0 µg/m<sup>3</sup> (Baram et al., 2000; Fankhauser-Noti et al., 2007), which can cause contamination of glassware and solvents. To avoid overestimating PAE concentrations during sampling and the experiment, it is recommended to avoid the personal use of hand creams, perfumes, deodorants, and any cosmetic products that contain PAEs (Félix-Cañedo et al., 2013). Ideally, a room dedicated to the analysis of PAEs with a purified air filter should be used. All the materials handled during sampling and sample treatment should be made of glass, Teflon, polytetrafluoroethylene, aluminum or stainless steel. To minimize PAEs contamination, rigorous control measures are required to prevent sample contamination and to maintain a low background concentration. These procedures include prewashing the laboratory material and equipment. All laboratory glassware should be washed with an appropriate organic solvent such as cyclohexane, n-hexane, isooctane, methanol or 2,2,4trimethylpentane (Hashizume et al., 2002; Tienpont et al., 2004). An acidic solution such as hydrochloric acid, sulfochromic mixture or mixture of ammonium persulfate and sulfuric acid (Cincinelli et al., 2001; Dargnat et al., 2009; Mousa et al., 2013) or a 1 M potassium hydroxide solution (Baram et al., 2000) can also be used.

The glassware should be calcinated at 450-550°C overnight to remove organic materials. The use of plastic materials throughout the procedure is absolutely prohibited (Teil et al., 2007). Moreover, the adsorption of PAEs on the glassware walls can be minimized by calcination (Blair et al., 2009; Dévier et al., 2013; Fankhauser-Noti et al., 2007; Félix-Cañedo et al., 2013; Marega et al., 2013; Teil et al., 2007). The glassware should be washed and kept in an appropriate box with a lid (glass or PTFE) and/or calcinated aluminium to avoid the adsorption of PAEs from ambient air (Tienpont et al., 2004). Possible souces of contamination can also be derived from SPE cartridges, filters, vial caps, syringes and septa.

PAEs have been reported in some commercial organic solvents. For example, DnBP and DEHP have been measured on the order of  $100~\mu g/L$  in hexane (Fankhauser-Noti et al., 2007). For this reason, all solvents used should be of high purity and should be pre-checked for the presence of PAEs. To increase its purity, organic solvents can be distilled (Cincinelli et al., 2001) or pre-baked aluminum oxide can be added at 3% (w/v) (Fankhauser-Noti et al., 2007; Luo et al., 2012; Wu et al., 2013). Attention should also be given to the use of deionized water, which can sometimes contain a significant amount of PAEs (Cao et al., 2008; Hashizume et al., 2002). Other chemical products, such as salts (e.g., aluminium oxide, silica, sodium carbonate, sodium chloride, sodium sulfate) should be decontaminated by calcination at  $400-550^{\circ}$ C from 4h to overnight (Cao et al., 2008; Teil et al., 2007).

# 1.2. Procedural blank

The first step of PAEs quantification is quality control and quality assurance. Quality control should be routinely implemented to minimize the risk of sample contamination. Analytical blanks for each step of the procedure should be performed to track the source of sample contamination and thus find an appropriate solution, if required. The blank should be free of targeted compounds or they should be present at low levels. A blank must be used at each step of the sample treatment (i.e., extraction, purification and pre-concentration) or, at the very least, one blank for the entire analytical procedure could be used in triplicate. The blank should be free from any targeted PAEs to ensure that no significant contamination occurs during the procedure. Moreover, to minimize the error of quantification, procedural blanks should be extracted together

with each set of the samples measured in triplicate. Method blanks and field blanks are strongly recommended for each environmental sample batch. DnBP and DEHP are found frequently in procedural blanks. If they are present at low concentrations, which account for less than a few % of those in the targeted sample, it is not necessary to subtract them from the sample measurement. However, if they are present at significant levels, they must be eliminated or subtracted from the sample measurement. It is also noteworthy that deionized water from purification systems (e.g., Milli-Q RG, Millipore, USA) can contain PAEs. The common background contamination was estimated at 0.02, 0.15, 0.005 and 0.49  $\mu$ g/L for DEP, DnBP, BBzP and DEHP, respectively (Prokůpková et al., 2002). The DEHP concentrations in blanks can be up to 90-1640 ng/L, with a mean value of approximately 500 ng/L (11 laboratories) (INERIS, 2009).

# 1.3. Quantification of concentration

The quantification of PAEs can be performed either with an external or internal standard. Nevertheless, the use of internal standard(s) is strongly recommended because of the many steps required between the initial sampling and final analysis. The loss of targeted compounds could be significant during the different experimental steps (i.e., extraction, purification, pre-concentration, transfer, storage). For example, PAEs with short alkyl chain lengths (i.e., DMP, DEP) are quite volatile, and thus their loss during the pre-concentration step could be significant. Using an internal standard allows one to correct for the eventual loss of each targeted compound. Additionally, it allows one to correct for the error caused by variations of the injected volume and the response of the detector, especially when the analysis is performed using the GC-MS. In addition to the advantages mentioned, the internal standard allows one to monitor matrix effects. The choice of an appropriate internal standard is important for precise quantification. For these reasons, the use of deuterated analogs of the targeted compounds as internal standards is generally recommended. The internal standards that are most often used and proved to be efficient for the GC quantification of PAEs are: DiPhP, DnPhP, DnBzP, dimethyl isophthalate DMIP, benzyl benzoate or deuterated PAEs (DMP-d4, DEP-d4, DnBP-d4, BBzP-d4, DEHP-d4, DiDP-d4, BEHP-d4, DHxP-d4, DnPhP-d4, DnOP-d4 and DiNP-d4) (Table 1).

The linear range and limits of detection/quantification (LOD/LOQ) should be studied initially. Generally, the LOD of PAEs using the performance methods cited in table 1 gives satisfactory values, ranging from less than 1  $\mu$ g/kg to dozens of  $\mu$ g/kg dw for solid matrices (i.e., soil, sludge and sediment) and from less than 10 ng/L to dozens ng/L for liquid matrices (i.e., surface water, wastewater). For more precise measurements, a procedural blank and a spiked matrix sample are strongly recommended, and both should be performed in duplicate (at least) with each set of samples.

#### 1.4. Recoveries studies

Recoveries of targeted PAEs and internal standards (if any) in the matrix of interest should be evaluated initially by spiking a certain amount of standard mixture, with a concentration similar to those in the real samples, into the matrix and performing the entire analytical procedure. Spike recovery rates should be within acceptable limits to ensure either good efficiency and no significant loss or interference during the procedure. The recoveries of PAEs in real sample can be different for one PAE to another, which might be affected by the organic contents of blank matrices and the extraction efficiency of the method used. To date, many performance methods for quantifying PAEs in different environmental matrices have been developed, and the extraction yield are generally very satisfactory as presented in table 1.

# 1.5. Sample storage and transport

After sampling, the water samples are stored and transported in aluminium or stainless steel containers at 4°C (Caroli et al., 2011; Furtmann, 1994; Wu et al., 2013). PAEs are biodegradable in aqueous media. Nevertheless, many authors have reported superior preservation of water samples by stabilizing them and by limiting bacterial growth following the addition of either sodium azide (500 mg/L sample) (Fromme et al., 2002; Tienpont, 2004) or an acid (e.g., hydrochloric acid to pH 2, commercial formic acid to pH 2.5, nitric acid 0.01 M, or sulfuric acid at 3 % to pH 2-3) (Blair et al., 2009; Félix-Cañedo et al., 2013; Huang et al., 2008; Vogelsang et al., 2006). Liquid samples should be stored in a refrigerated chamber at 4°C (± 3°C) in darkness and treated (i.e., extraction, analysis) as soon as possible within a maximum period of 14 days to reduce losses by adsorption on the walls of the container (EPA, 1995). While solid sample should be stored at -20°C until the treatment can be performed (He et al., 2013; Liou et al., 2014; Wang et al., 2013).

# 2. Extraction or pretreatment techniques

# 2.1. Water sample

Many different methods could be applied to determine the concentration of PAEs in water. To collect wastewater from WWTP, 1 L aluminium sample bottles were chosen (Dargnat et al., 2009). Amber glass bottles can also be used. To collect seawater, it is strongly recommended to use a Go-Flo bottle that is coated with Teflon rather than a Niskin bottle. Using Teflon minimizes the degree of contamination. Moreover, when collecting the water sample at a depth of 10 m (Dargnat et al., 2011; Wurl, 2009), for example, the sample should be kept in a closed system, which limits its interaction with the atmosphere.

Among the large variety of extraction methods, the methods most often used and that have shown good efficiency are liquid-liquid extraction (LLE), solid-phase micro-extraction (SPME) and solid-phase extraction (SPE). Other recent extraction methods for PAEs from aqueous matrices have been developed; for example, the LLE associated with a large volume injection (LVI), the liquid phase microextraction (LPME) (Farahani et al., 2008), and the microextraction by liquid-liquid dispersion (DLLME) (Yan et al., 2010). PAEs are adsorbed on SSM, approximately 70 % of DnOP, 55 % of DEHP and 10-20 % of other PAEs (Furtmann, 1994). Consequently, the quantification should be performed both on the dissolved and particulate phases to better represent the global contamination and their distribution in the water column.

# 2.1.1. Liquid-liquid extraction (LLE)

The LLE technique consists of adding organic solvent (approximately 50 to 200 mL) into the aqueous sample (500 to 1000 mL, in general) and shaking the contents. This step collects the maximum of PAEs in the organic phase following the decantation step. Cai et al. (2007) reported that propanol was the best solvent for the extraction of PAEs from water. In this case, organic salts must be added to the mixture to separate the two phases (i.e., the water and organic solvent) because propanol is soluble in water. To allow the best phase separation, ammonium sulphate should be added (Cai et al., 2007). However, good efficiency can also be obtained by using hexane and/or DCM, which are non-miscible with water (Gao et al., 2014; Liu et al., 2013; Net et al., 2014). Furthermore, the addition of an organic modifier (e.g., 50 % methanol) can be necessary for the extraction of the most apolar PAEs such as DEHP and DnOP (Bergström et al., 2007). For successive extractions of the same sample (n=1-3), recovery yields above 80 % are generally obtained (Table 1).

In the presence of SSM, the LLE technique is feasible without separating SSM from water. The resulting emulsion involving water and SSM can be removed by various techniques (e.g., EPA-Method 506 (EPA, 1995)) including centrifugation, the addition of salts (e.g., 20-150 g of NaCl per liter of water) (Adewuyi et al., 2012; Hashizume et al., 2002), ultrasound, freezing or

vigorous stirring. However, the presence of emulsions can affect the extraction efficiency of the compounds present in the SSM. With for exception of DMP, Farahani et al. (2008) showed that the addition of salt (NaCl) does not always improve the efficiency of the extraction of analytes.

Using non-miscible organic solvent allows one to avoid the addition of organic salt. This approach saves time and involves less preparatory steps, which could be a source of sample contamination. In this regard, Method 8061 of the US-EPA is the most often used approach (Gao et al., 2014; Liu et al., 2013; Zeng et al., 2008a, b). For this method, 2 L of water should first be filtered with 0.7 µm glass fiber filters, spiked with the internal standard, and then extracted with 3×100 mL of DCM. Traces of water can be eliminated with sodium sulphate and then solvent exchanged with 1 mL hexane prior to GC-MS analysis. Overall, the LLE technique is simple to implement but requires the use of a large volume of organic solvents (up to 500 mL) and thus expensive. Additionally, the LLE technique is very labor intensive and time consuming. It requires the use of many pieces of glassware, which further increases the potential for sample contamination.

# 2.1.2. Solid phase micro extraction (SPME)

The SPME technique is a solvent-free method. It involves the use of a fiber coated with an extracting phase, which can be a liquid (polymer) or a solid (sorbent) that extracts PAEs from water. After extraction/concentration, the SPME fiber is transferred to the injection port of the separating instruments, such as GC, where thermal desorption of PAEs occurs and analysis is performed. The extraction involves the equilibrium sorption of analytes onto a microfiber coated with a hydrophilic polymer. There are numerous fiber coatings available based on the solid sorbents. Poly(dimethylsiloxane) (PDMS), which is relatively non-polar, is the most frequently used fiber. Among a large variety of fiber coatings, polydimethylsiloxane and divinyl benzene (PDMS-DVB), hand-made polyaniline, and polyacrylate fibers has been successfully used to analyze the 6 PAEs listed in the priority list of the US-EPA (Li et al., 2006a, b, c; Polo et al., 2005; Prokůpková et al., 2002). The advantage of the SPME is organic solvents-free technique, which avoids the risk of secondary contamination that may occur during the pretreatment step. Further, the fiber can be reused (for 100-300 cycles). However, it appears that the SPME method for the quantification of PAEs remains in the development phase. To date, very few data are available in the literature that have used this technique and most did not report good efficiency for all of the selected PAEs.

# 2.1.3. Solid phase extraction (SPE)

SPE is another extraction technique that is an alternative method to LLE. SPE has received increasing attention because of its ease of implementation, its ability to save time and solvent, ant to eliminate the emulsions. In addition, high enrichment factors are usually obtained with SPE technique. To date, SPE has been shown to be a powerful method for the extraction, pre-concentration and cleanup of water samples. Furthermore, SPE is semi-automatic and allows for the simultaneous extraction of up to 12 or 24 water samples. Briefly, PAEs are transferred from the water sample (100-1000 mL) to a previously activated solid phase. PAEs are recovered by elution with an appropriate solvent. Typical cartridge devices consist of short columns; conventionally, an open syringe barrel contains the sorbent with different particulate sizes, usually between 50-60 µm. Cartridges that have been reported to provide good extraction efficiency for PAEs are: C18, HLB, and a mixture of LiChrolut RP18 and Lichrolut EN (2.5/1 by weight) (Fromme et al., 2002; He et al., 2013; Liou et al., 2014; Zheng et al., 2014). The water sample can be extracted directly without filtration, but in most cases, filtration is a necessity step to avoid clogging, especially when the sample contains a high level of SSM. Internal standards (if any) should be spiked into the sample prior to extraction. MeOH, DCM, hexane and acetone are commonly used as eluting solvent, either as individual solvents or as mixtures (Table 1).

Magnetic SPE (MSPE) using iron-based magnetic nanotubes of carbon can be used as an alternative to SPE for the extraction of PAEs in mineral and tap waters (Luo et al., 2012). Two examples of the SPE method for the extraction and cleanup of PAEs from water samples are presented in Figure 1S in Supporting Information.

# 2.2. Sludge, sediment, SSM and soil samples

Based on the literature data, the extraction of PAEs from solid matrices such as sludge, SSM, sediment and soil can be performed with common methods. Common methods have been reported that extract with good efficiency PAEs in both SSM and sediment (Zheng et al., 2014), soil and sediment (Zeng et al., 2008a, b, 2009), sediment, sludge and soil (Reid et al., 2009). The analysis of PAEs in a solid matrix generally includes extraction, clean up, column fractionation and chromatographic separation. A large variety of solvents, such as acetone, acetonitrile, DCM, hexane, ethyl acetate can be used to extract PAEs with good efficiency (Table 1). The extraction of PAEs from solid environmental matrices is conventionally performed by the Soxhlet extraction technique (Meng et al., 2014; Wang et al., 2008, 2014). Soxhlet technique offers good extraction yields. However, it is time and solvent consuming and thus expensive.

Other extraction techniques have also been developed for PAEs not only to reduce the volume of solvents and extraction times but also to improve the precision of the recovery of the analytes. Such techniques include microwave-assisted extraction (MAE), supercritical fluid extraction (SFE), ultrasonic and accelerated solvent extraction (ASE) (Table 1). Among these techniques, ASE, also known as pressurized liquid extraction (PLE), has received increased attention because of its ease to implement and its ability to save time. Further, this approach allows one to extract with high pressure. This means that solvents can be heated to temperatures above their boiling points, which make them much more efficient to dissolve target compounds from their matrix. Moreover, this technique maintains constant extraction conditions and its automation provides reliable repeatability (Hubert et al., 2001; Schantz, 2006). In general, solid matrices should be dried, finely ground and sieved at 0.2-2 mm prior to extraction for better efficiency (Ma et al., 2014; Meng et al., 2014; Wang et al., 2013; Zeng et al., 2008a). For coastal and port samples, the optimum extraction yield was obtained when sediments were sieved at 0.2 mm (Muñoz-Ortuño et al., 2014). Indeed, reducing the particle size improves the extraction yield by providing better contact of the solvent with the sample. A hydromatrix or diatomaceous earth dispersing agent can be added to the sample to prevent aggregation of sample particles when using the ASE technique (Reid et al., 2009). Two protocols for analyzing PAEs from solidmatrices are presented in Figure 2S in Supporting Information.

# 2.3. Air samples (gas and particulate phases)

Air samples can be collected on quartz fiber filters (QFFs) (25×25 cm) previously calcinated (450°C), and then stored at -20°C until the analysis is performed (Fu et al., 2013). PAEs can be collected either by pumping an air sample through ethylene glycol or directly through an activated Florisil column, with a detection limit of 10 ng per injection using GC-ECD. Passive sampling on charcoal, which is less expensive than active sampling but requires much longer sampling times, can also perform measurements in air. In this case, the detection limit is 200 ng/m<sup>3</sup>. PAEs in the gas phase can be collected on polyurethane foam plugs (PUFs). QFFs and PUFs should be then wrapped in aluminum foil and stored in Teflon bags and kept at -20°C until the analysis is performed. PAEs in QFFs and PUFs can be extracted using the many different techniques as previously reported for solid matrices.

# 3. Chromatographic analysis

# 3.1. Direct analysis of PAEs

The identification and quantification of PAEs in environmental matrices require an appropriate pre-treatment step, as reported previously, followed by an analysis using different separation and detection techniques. PAEs can be quantified using chromatographic techniques such as liquid chromatography (LC) or gas chromatography (GC). GC equipped with mass spectrometry (MS) is the most common technique used for the determination of PAEs (Table 1). However, LC is a useful technique for analyzing non-volatile PAEs and their degradation products (Silva et al., 2004a, b). A mass spectrometer is the most common detector used; it is an efficient tool for the identification and quantification of each targeted PAE with low LOD (ng/L or  $<\mu$ g/kg). To achieve accurate quantification, compounds must be fully resolved from each other with a low signal-to-noise background.

# 3.1.1. Gas chromatography

PAEs are weakly polar compounds. The columns most commonly used for PAEs separation in GC/MS are non-polar capillary columns such as DB-5MS and HP-5MS (Table 1). Other columns such as DB-XLB, Rxi-5MS, SLB-5MS, Phenomenex XLB, Ultra-2 and DB-35 can be also used with good efficiency (Table 1). After the separation step, each compound is transported into a MS detector where compounds can be ionized with electronic impact (EI) or chemical ionization (CI) and can be detected in full scan, SIS, SIM, MS/MS or MRM mode. Programming the temperature at 50°C for 1 min until 320°C for 2 min (ramp 10°C/min) with a HP-5MS column is typical for the determination of PAEs by the GC/MS technique. These conditions are a good compromise between resolution and the run time for the PAE analysis. With a non-polar column, the separation of analytes is based on the low boiling point of the analytes (Tienpont, 2004). Table 2 presents the quantifier/qualifier ions of PAEs using a Rxi®-5ms capillary column.

#### 3.1.2. Liquid chromatography (LC)

According to the literature data, PAEs can also be quantified using the LC. However, compared to GC/MS, a lower sensitivity is obtained with LC/MS. Indeed, LC is more appropriate for analyzing mono phthalate esters (MPEs) and degradation products of PAEs than PAEs themselves. With LC, PAEs separation is commonly achieved on an apolar C18 (octadecylsilicagel, ODS) analytical column, using a mobile phase containing an organic solvent such as methanol or ACN and Milli-Q water, both generally buffered (e.g, with 10 mM ammonium formate, ammonium acetate) or acidified (0.05-0.1 % AcOH or TFA). However, a C8 column provides better separation peaks for the isomeric mixtures, well defined and narrower peaks than on a classical C18. Better separation can be obtained when the column is thermostated between room temperature to 80°C. Table 2S presents the columns commonly used in LC for the analysis of PAEs. MS or UV detector can perform the detection of PAEs using LC. Table 3 presents the quantifier and qualifier ions of PAEs with MS detector. By MS, PAEs can be analyzed by electrospray (ESI) (Masia et al., 2013) or atmospheric pressure chemical (APCI) (Castillo and Barcelo, 2001) ionization in positive mode.

# 3.2. Derivatization method

Generally, PAEs can be easily identified and quantified by direct analysis as reported in the previous section. PAEs are sufficiently volatile to be analyzed directly by GC/MS. Nevertheless, their derivatization can make them more volatile. Although this step facilitates their analysis by GC, it is used very little. The peaks of silylated derivatives in the GC chromatograms are more symmetrical and thinner than those of corresponding PAEs, and the retention times are shorter. For the derivatization technique, PAEs are first hydrolyzed using an alkaline solution of

NaOH or KOH. Following by the acidification step and the obtained phthalic acid (PA) are then extracted with organic solvents and then derivatized (e.g., by silylation as showed in Figure 1) prior to GC/MS analysis.

For the derivatization of PAEs, first, alkaline hydrolysis can be performed with 1 M NaOH, or at pH  $\geq$  12, at 90°C for 30 min or at room temperature (Kim et al., 2007; Peng et al., 2013). Following alkaline hydrolysis, the solution can be acidified with HCl to pH  $\leq 2$  and convert carboxylates into carboxylic acids. PA and alcohols obtained are usually extracted with ethyl acetate according to Kim et al. (2007). Under anhydrous conditions, these analytes can be derivatized by silylation. The derivatizing agent most commonly used is pentafluorobenzyl chloride (PFBCl). However, other derivatization reagents such as N-Methyl-N-tertbutyldimethylsilyltrifluoroacetamide (MTBSTFA) and N,O-bis(trimethylsilyl) trifluoroacetamide (BSTFA) can be used (Ballesteros et al., 2006; Félix-Cañedo et al., 2013; Fu et al., 2013; Schreiber et al., 2011). The quantifier and qualifier ions of silvl derivatives of phthalic esters are presented in Table 4. This method allows to quantifing the total PAEs with good efficiency and low LOQ. However, this technique does not allow the determination of the contamination level of individual PAE. Indeed, this derivatization technique gives the sum of concentration of PA, mono-alkyl phthalate esters, and PAEs. Thus, to determine the real contamination level PAEs, other measurement should be performed to quantify the concentration of PA and mono-alkyl phthalate ester present initialy in the sample.

# Conclusions

To date, PAEs are the most common chemicals that humans are in contact with daily. They are ubiquitous in all invironmental compartments incuding urban and industrial effluents. In order to answer to the constraint on industrial wastewater discharges, stricter regulation on the release of PAEs and especially to minimize the health and environmental risk, the quantification of their contamination levels in the environment should be monitored. During these last few decades, there has been considerable improvement in PAEs extraction and analysis techniques. Numerous pretreatment techniques and detection methods can be now applied for identifying and quantifying these compounds in different environmental matrices throughout the worldwide environment, including atmospheric aerosols, indoor and outdoor air, in municipal solid waste compost, sludge, river and marine waters/sediments, SSM and drinking water. Generally, these compounds present in the environmental matrices at the concentration level that can be easily identified and quantified by commun techniques of extraction (i.e., LLE, SPE, SPME, ASE, Soxhlet, sonication...) and analysis (i.e., GC/MS, LC/MS). However, the problem is not the trace analysis itself but the risk of contamination during the analytical procedure due to its ubiquity in the laboratory environment/producsts/solvents/reagents, which can often lead to false positive or overestimated results. This paper is a synthesis of the extensive literature data on the most performance methods of pretreatment and quantification recently developed for analysis of PAEs in different environmental matrices. Some useful information to avoid overestimating PAEs is also reviewed. To get reliable results, stricter quality control and quality assurance must be respected.

# Acknowledgments

The authors are grateful for the financial support provided by the Mediterranean Institute of Oceanography (MIO) of Aix-Marseille University.

#### References

- Adewuyi GO. High performance liquid chromatographic identification and estimation of phthalates in sewer waste and a receiving river in Ibadan city, Southwestern Nigeria. Journal of Water Resource and Protection 2012;4:851-858.
- Alzaga R, Pena A, Bayona JM. Determination of phthalic monoesters in aqueous and urine samples by solid-phase microextraction-diazomethane on-fibre derivatization-gas chromatography-mass spectrometry. J Sep Science 2003;26:87-96.
- Amiridou D, Voutsa D. Alkylphenols and phthalates in bottled waters. J Hazard Mater 2011;185: 281-286.
- Aparicio I, Santos JL, Alonso E. Simultaneous sonication-assisted extraction, and determination by gas chromatography-mass spectrometry, of di-(2-ethylhexyl)phthalate, nonylphenol, nonylphenol ethoxylates and polychlorinated biphenyls in sludge from wastewater treatment plants. Anal Chim Acta 2007;584(2):455-461.
- Bach C, Dauchy X, Severin I, Munoz JF, Etienne S, Chagnon MC. Effect of temperature on the release of intentionally and non-intentionally added substances from polyethylene terephthalate (PET) bottles into water: chemical analysis and potential toxicity. Food Chem 2013;139:672-680.
- Ballesteros O, Zafra A, Navalon A, Vilchez JL. Sensitive gas chromatography-mass spectrometric method for the determination of phthalate esters, alkylphenols, bisphenol A and their chlorinated derivatives in wastewater samples. J Chromatogr A 2006;1121:154-162.
- Baram GI, Azarova IN, Gorshkov AG, Vereshchagin AL, Lang B, Kiryukhina ED. Determination of bis(2-ethylhexyl) phthalate in water by high-performance liquid chromatography with direct on-column preconcentration. J Anal Chem 2000;55:750-754.
- Barreca S, Indelicato R, Orecchio S, Pace A. Photodegradation of selected phthalates on mural painting surfaces under UV light irradiation. Microchemical J 2014;114:192-196.
- Batlle R, Nerín C. Application of single-drop microextraction to the determination of dialkyl phthalate esters in food simulants. J Chromatogr A 2004;1045(1-2):29-35.
- Bell J. Barsh R. Development and application of a method for the analysis of diethylhexyl phthalate (DEHP) in San Juan county waters. Report, pp. 9, 2010.
- Bergh C, Torgrip R, Emenius G, Ostman C. Organophosphate and phthalate esters in air and settled dust-a multi-location indoor study. Indoor Air 2011;21(1):67-76.
- Bergé A. Identification des sources d'alkylphénols et de phtalates en milieu urbain-Comparaison des rejets à dominante urbaine (domestique) par rapport à des rejets purement industriels. Thèse, 2012.
- Bergström S, Barri T, Norberg J, Jönsson JA, Mathiasson L. Extracting syringe for extraction of phthalate esters in aqueous environmental samples. Anal Chim Acta 2007;394:240-247.
- Bette H. California bans phthalates in toys for children. Chemical and Engineering News, 12. 2007. http://pubs.acs.org/cen/news/85/i43/8543news4.html.
- Blair JD, Ikonomou MG, Kelly BC, Surridge B, Gobas FAPC. Ultra-trace determination of phthalate ester metabolites in seawater, sediments, and biota from an urbanized marine inlet by LC/ESI-MS/MS. Environ Sci Technol 2009;43(16):6262-6268.
- Cadogan DF. Papez M. Popp¢ AC, Scheubel J. An assessment of the release, occurrence and possible effect of plasticizers in the environment. Progress in Rubber and Plastics Technology 1993;10:1-19.
- Cai QK, Jiang GB, Liu JF, Zhou QX. Multi-walled carbon nanotubes packed cartridge for the solid-phase extraction of several phthalate esters from water samples and their determination by high performance liquid chromatography. Anal Chim Acta 2003;494:149-156.
- Cai Y, Cai Y, Shi Y, Liu J, Mou S, Lu Y. A liquid-liquid extraction technique for phthalate esters with water-soluble organic solvents by adding inorganic solvents. Microchim Acta 2007;157(1-2):73-79.
- Cao XL. Determination of phthalates and adipate in bottled water by headspace solid-phase microextraction and gas chromatography/mass spectrometry. J Chromatogr A 2008;1178:231-238.

- Caroli S, Cescon P, Valton DWH. Environmental contamination in Antarctica: A challenge to analytical chemistry, book, Kindle Edition, pp. 424, 2011.
- Cartwright CD, Thompson IP, Burns RG. Degradation and impact of phthalate plasticizers on soil microbial communities. Environ Toxicol Chem 2000;19:1253-1261.
- Castillo M, Barcelo D. Characterisation of organic pollutants in textile wastewaters and landfill leachate by using toxicity-based farctionation methods floowed by liquid and gas chromatography couped to mass spectrometric detection. Anal Chim Acta 2001;426:253-264.
- Castillo M, Barcelo D. Identification of polar toxicants in industrial wastewaters using toxicity-based fractionation with liquid chromatography/mass spectrometry. Anal Chem 1999;71:3769-3776.
- Chao YY, Jian ZX, Tu YM, Huang YL. Rapid on-line microextraction of neutral analytes in plastic-bottled beverages through ultrasound-assisted push/pull perfusion hollow-fiber liquid-liquid-liquid microextraction. Microchem J 2013;110:386-394.
- Chao YY, Lee CH, Chien TY, Shih YH, Lu YA, Kuo TH, Huang YL. Effects of push/pull perfusion and ultrasonication on the extraction efficiencies of phthalate esters in sports drink samples using on-line hollow-fiber liquid-phase microextraction. J Agric Food Chem 2013;61(34):8063-8071.
- Choi H, Schmidbauer N, Spengler J, Bornehag CG. Sources of propylene glycol and glycol ethers in air at home. Int J Environ Res Public Health 2010;7:4213-4237.
- Cincinelli A, Stortini AM, Perugini M, Checchini L, Lepri L. Organic pollutants in sea-surface microlayer and aerosol in the coastal environment of Leghorn (Tyrrhenian Sea). Mar Chem 2001;76:77-98.
- Cousins AP, Holmgren T, Remberger M. Emissions of two phthalate esters and BDE 209 to indoor air and their impact on urban air quality. Sci Total Environ 2014;470-471:527-535.
- Dargnat C, Teil MJ, Chevreuil M, Blanchard M. Phthalate removal throughout wastewater treatment plant: case study of Marne Aval station (France). Review. Sci Total Environ 2009;407(4):1235-1244.
- Das MT, Ghosh P, Thakur IS. Intake estimates of phthalate esters for South Delhi population based on exposure media assessment. Environ Pollut 2014;189:118-125.
- Dévier MH, Le Menach K, Viglino L, Di Gioia L, Lachassagne P, Budzinski H. Ultra-trace analysis of hormones, pharmaceutical substances, alkylphenols and phthalates in two French natural mineral waters. Sci Total Environ 2013;443:621-632.
- Dumitrascu I. Method validation for phthalate analysis from water, Advances in Environmental Sciences. Int J Bioflux Soc 2013;5(2):63-69.
- EPA (Environmental Protection Agency), Determination of phthalate and adipate esters in drinking water by liquid-liquid extraction or liquid-solid extraction and gas chromatography with photoionization detection. Method 506. Rev. 1.1, 1995.
- Espadaler I, Caixach J, Om J, Ventura F, Cortina M, Pauné F, Rivera J. Identification of organic pollutants in Ter River and its system of reservoirs supplying water to Barcelon (Catalona, Spain): a study by GC/MS and FAB/MS. Wat Res 1997;31(8):1996-2004.
- Fankhauser-Noti A, Grob K. Blank problems in trace analysis of diethylhexyl and dibutyl phtalate: investigation of the sources, tips and tricks. Anal Chim Acta 2007;582:353-360.
- Farahani H, Ganjali MR, Dinarvand R, Norouzi P. Screening method for phthalate esters in waterusing liquid-phase microextraction based on the solidification of a floating organic microdrop combined with gas chromatography-mass spectrometry. Talanta 2008;76:718-723.
- Farahani H, Norouzi P, Dinarvand R, Ganjali MR. Development of dispersive liquid-liquid microextraction combined with gas chromatography-mass spectrometry as a simple, rapid and highly sensitive method for the determination of phthalate esters in water samples. J Chromatogr A 2007;1172:105-112.
- Farrell M, Jones DL. Critical evaluation of municipal solid waste composting and potential compost markets. Bioresour Technol 2009;100(19):4301-4310.

- Fatoki OS, Bornman M, Ravandhalala L, Chimuka L, Genthe B, Adeniyi A. Phthalate ester plasticizers in freshwater systems of Venda, South Africa and potential health effects. ISSN 1816-7950 (On-line) Water SA 36(1), January 2010.
- Félix-Cañedo TE, Durán-Alvarez JC, Jiménez-Cisneros B. The occurrence and distribution of a group of organic micropolluants in Mexico City's water sources. Sci Total Environ 2013;454-455:109-118.
- Fromme H, Küchler T, Otto T, Pilz K, Müller J, Wenzel A. Occurrence of phthalates and bisphenol A and F in the environment. Water Res 2002;36(6):1429-1438.
- Fu P, Kawamura K, Barrie LA. Photochemical and other sources of organic compounds in the Canadian high Arctic aerosol pollution during Winter-Spring. Environ Sci Technol 2009;43:286-292.
- Fu PQ, Kawamura K, Chen J, Charrière B, Sempéré R. Organic molecular composition of marine aerosols over the Arctic Ocean in summer: contributions of primary emission and secondary aerosol formation. Biogeosciences 2013;10:653-667.
- Furtmann K. Phthalates in surface water-a method for routine trace level analysis. Fresenius J Anal Chem 1994;348:291-296.
- Gao D, Li Z, Wen Z, Ren N. Occurrence and fate of phthalate esters in full-scale domestic wastewater treatment plants and their impact on receiving waters along the Songhua River in China. Chemosphere 2014;95:24-32.
- Guo L, Lee HK. Vortex-assisted micro-solid-phase extraction followed by low-density solvent based dispersive liquid-liquid microextraction for the fast and efficient determination of phthalate esters in river water samples. J Chromatogr A 2013;1300:24-30.
- Hara H, Stewart GR, Mohn WW. Involvement of a novel ABC transporter and monoalkyl phthalate ester hydrolase in phthalate ester catabolism by *Rhodococcus jostii* RHA1. Appl Environ Microbiol 2010;76(5):1516-1523.
- Hashizume K, Nanya J, Toda C, Yasui T, Nagano H, Kojima N. Phthalate esters detected in various water samples and biodegradation of the phthalates by microbes isolated from river water. Biol Pharm Bull 2002;25(2):209-214.
- He W, Qin N, Kong X, Liu W, He Q, Ouyang H, Yang C, Jiang Y, Wang Q, Yang B, Xu F. Spatio-temporal distributions and the ecological and health risks of phthalate esters (PAEs) in the surface water of a large, shallow Chinese lake. Sci Total Environ 2013;461-462: 672-680.
- Holadová K, Prokůpková G, Hajŝlová J, Poustka J. Headspace solid-phase microextraction of phthalic acid esters from vegetable oil employing solvent based matrix modification. Anal Chim Acta 2007;582:24-33.
- Huang DY, Zhou SG, Hong W, Feng WF, Tao L. Pollution characteristics of volatile organic compounds, polycyclic aromatic hydrocarbons and phthalate esters emitted from plastic wastes recycling granulation plants in Xingtan Town, South China. Atmos Environ 2013;71:327-334.
- Huang PC, Tien CJ, Sun YM, Hsieh CY, Lee CC. Occurrence of phthalates in sediment and biota: Relationship to aquatic factors and the biota-sediment accumulation factor. Chemosphere 2008;73(4):539-544.
- Hubert A, Wenzel KD, Engewald W, Schüürmann G. Accelerated solvent extraction-more efficient extraction of POPs and PAHs from real contaminated plant and soil samples. Rev Anal Chem 2001;20(2):101-144.
- INERIS (Institut National de l'Environnement Industriel et des Risques), 2009. Report on the French interlaboratory exercice on the Water Framework Directive priority substances Phathalates. INERIS Report No. DRC-09-95687-06768B, June. 48 pp, 2009.
- Jara S, Lysebo C, Greibrokk T, Lundanes E. Determination of phthalates in water samples using polystyrene solid-phase extraction and liquid chromatography quantification. Anal Chim Acta 2000;407(1-2):165-171.
- Khedr A. Optimized extraction method for LC-MS determination of bisphenol A, melamine and di(2-ethylhexyl) phthalate in selected soft drinks, syringes, and milk powder. J Chromatogr B 2013;930:98-103.

- Kim M, Li D, Shim WJ, Oh JR, Park J. Simultaneous gas chromatography-mass spectrometric determination of total and individual phthalic esters utilizing alkaline hydrolysis and silyl derivatization technique. Bull Korean Chem Soc 2007;28(3):432-438.
- Kolena B, Petrovicova I, Pilka T, Pucherova Z, Munk M, Matula B, Vankova V, Petlus P, Jenisova Z, Rozova Z, Wimmerova S, Trnovec T. Phthalate exposure and health-related outcomes in specific types of work environment. Int. J. Environ. Res. Public Health 2014;11(6):5628-5639.
- Kong S, Ji Y, Liu L, Chen L, Zhao X, Wang J, Bai Z, Sun Z. Spatial and temporal variation of phthalic acid esters (PAEs) in atmospheric PM10 and PM2.5 and the influence of ambient temperature in Tianjin, China. Atmos Environ 2013;74:199-208.
- Li HY, Qu JH, Liu HJ. Removal of a type of endocrine distruptors di-n-butyl phtalate from water by ozonation. J Environ Sci 2006a;18(5):845-851.
- Li X, Zhong M, Xu S, Sun C. Determination of phthalates in water samples using polyaniline-based solid-phase microextraction coupled with gas chromatography. J Chromatogr A 2006b;1135(1):101-108.
- Lin ZP, Ikonomou MG, Jing H, Mackintosh C, Gobas FAPC. Determination of phthalate ester congeners and mixtures by LC/ESI-MS in sediments and biota of an urbanized marine inlet. Environ Sci Technol 2003;37(10):2100-2108.
- Liou SH, Yang GCC, Wang CL, Chiu YH. Monitoring of PAEMs and beta-agonists in urine for a small group of experimental subjects and PAEs and beta-agonists in drinking water consumed by the same subjects. J Hazard Mater 2014;277:169-179.
- Liu Y, Chen Z, Shen J. Occurrence and removal characteristics of phthalate esters from typical water sources in Northeast China. J Anal Meth Chem 2013;ID 419349,doi: 10.1155/2013/419349.
- Luo YB, Yu QW, Yuan BF, Feng YQ. Fast microextraction of phthalate acid esters from beverage, environmental water and perfume samples by magnetic multi-walled carbon nanotubes. Talanta 2012;90:123-131.
- Ma TT, Christie P, Luo YM, Teng Y. Physiological and antioxidant responses of germinating mung bean seedlings to phthalate esters in soil. Pedosphere 2014;24(1):107-115.
- Marega M, Grob K, Moret S, Conte L. Phthalate analysis by gas chromatography-mass spectrometry: Blank problems related to the syringe needle. J Chromatogr A 2013;1273:105-110
- Masia A, Moliner-Martinez Y, Munoz-Ortuno M, Pico Y, Campins-Falco P. Multiresidue analysis of organic pollutants by in-tube solid phase microextraction coupled to ultra-high pressure liquid chromatography-electrospray-tandem mass spectrometry. J Chromatogr A 2013;1306:1-11.
- Meng XZ, Wang Y, Xiang N, Chen L, Liu Z, Wu B, Dai X, Zhang YH, Xie Z, Ebinghaus R. Flow of sewage sludge-borne phthalate esters (PAEs) from human release to human intake: Implication for risk assessment of sludge applied to soil. Sci Total Environ 2014;476-477:242-249.
- Mousa A, Basheer C, Al-Arfaj AR. Application of electro-enhanced solid-phase microextraction for determination of phthalate esters and bisphenol A in blood and seawater samples. Talanta 2013;115:308-313.
- Muñoz-Ortuño M, Argente-García A, Moliner-Martínez Y, Verdú-Andrés J, Herráez-Hernández R, Picher MT, Campíns-Falcó P. A cost-effective method for estimating di(2-ethylhexyl)phthalate in coastal sediments. J Chromatogr A 2014;1324:57-62.
- Net S, Dumoulin D, El-Osmani R, Rabodonirina S, Ouddane B. Case study of PAHs, Me-PAHs, PCBs, phthalates and pesticides contamination in the Somme River water, France. Int J Environ Res 2014;8(4):1159-1170.
- Official Journal of the European Communities, 1999. L 315/46, 9 December 1999.
- Pei XQ, Song M, Guo M, Mo FF., Shen XY. Concentration and risk assessment of phthalates present in indoor air from newly decorated apartments. Atmos Environ 2013;68:17-23.

- Peng X, Feng L, Li X. Pathway of diethyl phthalate photolysis in sea-water determined by gas chromatography-mass spectrometry and compound-specific isotope analysis. Chemosphere 2013;90(2):220-226.
- Polo M, Llompart M, Garcia-Jares C, Cela R. Multivariate optimization of a solid-phase microextraction method for the analysis of phthalate esters in environmental waters. J Chromatogr A 2005;1072(1):63-72.
- Prokůpková G, Holadová K, Poustka J, Hajšlová J. Development of a solid-phase microextraction method for the determination of phthalic acid esters in water. Anal Chim Acta 2002;457:211-223.
- Reid AM, Brougham CA, Fogarty AM, Roche JJ. Accelerated solvent-based extraction and enrichment of selected plasticisers and 4-nonylphenol, and extraction of tin from organotin sources in sediments, sludges and leachate soils. Anal Chim Acta 2009;634(2):197-204.
- Rhind SM, Kyle CE, Kerr C, Osprey M, Zhang ZL, Duff EI, Lilly A, Nolan A, Hudson G, Towers W, Bell J, Coull M, McKenzie C. Concentrations and geographic distribution of selected organic pollutants in Scottish surface soils. Environ Pollut 2013;182:15-27.
- Schantz M. Pressurized liquid extraction in environmental analysis. Anal Bioanal Chem 2006;386:1043-1047.
- Schreiber A, Fu F, Yang O, Wan E, Gu E, Le Blanc Y. Increasing selectivity and confidence in detection when analyzing phthalates by LC-MS/MS. AB Sciex, AN 3690411-01, 2011.
- Serôdio P, Nogueira JMF. Considerations on ultra-trace analysis of phthalates in drinking water. Water Res 2006;40:2572-2582.
- Silva MJ, Reidy JA, Herbert AR, Preau Jr JL., Needham LL, Calalipid AM. Determination of phthalate metabolites in human amniotic fluid. Bull Environ Contam Toxicol 2004;72:1226-1231.
- Silva MJ, Slakman AR, Reidy JA, Preau JL, Herbert AR, Samandar E, Needham LL, Calafat AM. Analysis of human urine for fifteen phthalate metabolites using automated solid-phase extraction. J Chromatogr B 2004:805:161-167.
- Simoneit BRT, Medeiros PM, Didyk BM. Combustion products of plastics as indicators for refuse burning in the atmosphere. Environ Sci Technol 2005;39:6961-6970.
- Sun J, Huang J, Zhang A, Liu W, Cheng W. Occurrence of phthalate esters in sediments in Qiantang River, China and inference with urbanization and river flow regime. J Hazard Mater 2013;248-249:142-149.
- Teil MJ, Blanchard M, Dargnat C, Larcher-Tiphagne K, Chevreuil M. Occurrence of phthalate diesters in rivers of the Paris district (France). Hydrol Process 2007a;21:2515-2525.
- Teil MJ, Blanchard M, Dargnat C, Tiphagne K, Desportes A, Chevreuil M. Dynamique des apports et comportement de perturbateurs endocriniens et de médicaments dans les réseaux d'assainissement : exemple des phtalates et des antibiotiques Caractérisation des phtalates dans les échantillons de station d'épuration. Rapport GDR PIREN-SEINE 2006, Axe Thématique IV, 11 p., 2007b.
- Toda H, Sako K, Yagome Y, Nakamura T. Simultaneous determination of phosphate esters and phthalate esters in clean room air and indoor air by gas chromatography—mass spectrometry. Anal Chim Acta 2004;519:213-218.
- Tienpont B. Determination of phthalates in environmental, food and biomatrices An analytical challenge. Thesis, 2004.
- Vikelsée J, Thomsen M, Carlsen L. Phthalates and nonylphenols in profiles of differently dressed soils. Sci Total Environ 2002;296:105-116.
- Vogelsang C, Grung M, Jantsch TG, Tollefsen KE, Liltved H. Occurrence and removal of selected organic micropollutants at mechanical, chemical and advanced wastewater treatment plants in Norway. Wat Res 2006;40:3559-3570.
- Wang J, Luo Y, Teng Y, Ma W, Christie P, Li Z. Soil contamination by phthalate esters in Chinese intensive vegetable production systems with different modes of use of plastic film. Environ Pollut 2013;180:265-273.

- Wang P, Wang SL, Fan CQ. Atmospheric distribution of particulate- and gas-phase phthalic ester (PAEs) in a Metropolitan City, Nanjing, East China. Chemosphere 2008;72(10):1567-1572.
- Wang X, Tao W, Xu Y, Feng J, Wang F. Indoor phthalate concentration and exposure in residential and office buildings in Xi'an, China. Atmos Environ 2014;87:146-152.
- Wu X, Hong H, Liu X, Guan W, Meng L, Ye Y, Ma Y. Graphene-dispersive solid-phase extraction of phthalate acid esters from environmental water. Sci Total Environ 2013;444:224-230.
- Wurl O. Practical guidelines for the analysis of seawater, book, Ed. CRC Press Inc., pp 408, 2009.
- Xie Z, Ebinghaus R, Temme C, Caba A, Ruck W. Atmospheric concentrations and air-sea exchanges of phthalates in the North Sea (German Bight). Atmos Environ 2005;39:3209-3219.
- Xie Z, Ebinghaus R, Temme C, Lohmann R, Cara A, Ruck W. Occurrence and air-sea exchange of phthalates in the Arctic. Environ Sci Technol 2007;41(13):4555-4560.
- Xu G, Li FS, Wang QH. Occurrence and degradation characteristics of dibutyl phthalate (DBP) and di-(2-ethylhexyl) phthalate (DEHP) in typical agricultural soils of China. Sci Total Environ 2008;393(2):333-340.
- Yan H, Liu B, Du J, Row KH. Simultaneous determination of four phthalate esters in bottled water using ultrasound-assisted dispersive liquid-liquid microextraction followed by GC-FID detection. Analyst 2010;135:2585-2590.
- Yang GCC, Yen CH, Wang CL. Monitoring and removal of residual phthalate esters and pharmaceuticals in the drinking water of Kaohsiung City, Taiwan. J Hazard Mater 2014;doi: 10.1016/j.jhazmat.2014.03.005.
- Yuan SY, Huang IC, Chang BV. Biodegradation of dibutyl phthalate and di-(2-ethylhexyl) phthalate and microbial community changes in mangrove sediment. J Hazard Mater 2010;184:826-831.
- Zeng F, Cui K, Xie Z, Liu M, Li Y, Lin Y, Zeng Z, Li F. Occurrence of phthalate esters in water and sediment of urban lakes in a subtropical city, Guangzhou, South China. Environ Int 2008a;34:372-380.
- Zeng F, Cui K, Xie Z, Wu L, Liu M, Sun G, Lin Y, Luo D, Zeng Z. Phthalate esters (PAEs): emerging organic contaminants in agricultural soils in peri-urban areas around Guangzhou, China. Environ Pollut 2008b;156:425-434.
- Zeng F, Cui KY, Xie ZY, Wu LN, Luo DL, Chen LX, Lin YJ, Liu M, Sun GX. Distribution of phthalate esters in urban soils of subtropical city, Guangzhou, China. J Hazard Mater 2009;164(2):1171-1178.
- Zeng F, Lin Y, Cui K, Wen J, Ma Y, Chen H, Zhu F, Ma Z, Zeng Z. Atmospheric deposition of phthalate esters in a subtropical city. Atmos Environ 2010;44(6):834-840.
- Zheng X, Zhang BT, Teng Y. Distribution of phthalate acid esters in lakes of Beijing and its relationship with anthropogenic activities. Sci Total Environ 2014;476-477:107-113.

# **Table and Figure Captions**

# **Table Captions**

**Table 1**: Extraction technique and quantification method for the measurement of PAEs in environmental matrices.

Table 2: Ions for selected ion monitoring (SIM) of PAEs by GC/MS-EI

**Table 3**: Ions for selected ion monitoring (SIM) or MRM transitions of PAEs by LC/MS in positive and negative modes.

**Table 4**: Ions for SIM of the corresponding silvl derivatives of phthalic esters by GC/MS-EI (Kim et al., 2007).

# Figure Captions

Figure 1: Hydrolysis reaction and the derivatization of PAEs by silylation (Kim et al., 2007).

Table 1: Extraction technique and quantification method for the measurement of PAEs in environmental matrices.

	Extraction/Pretr	eatment	Identification and quantification						
Target PAEs	Solvent (Eluent)	Technique	Internal standards /Surrogate	Column	Analyse	Yields (%)	Ref		
Water sample	es								
7PAEs <sup>a</sup>	DCM	LLE	-	DB-5	GC-FID GC-MS	-	[1]		
6PAEs <sup>b</sup>	DCM	LLE	DiPhP, DnPhP, DnBzP, Benzyl benzoate	DB-5MS	GC-MS	78-113	[2]		
15PAEs <sup>c</sup>	DCM	LLE	DiPhP, DnPhP, DnBzP, Benzyl benzoate	DB-35MS	GC-MS	62-112	[3]		
OMP, DEP, OnBP, DEHP	DCM	LLE	Butyl benzoate	Col-Elite 5	GC-FID	82-91	[4]		
5PAEs <sup>d</sup>	DCM	LLE	External calibration	DB-5MS	GC-MS	81-104	[5]		
PAEse	DCM/Hexane	LLE	Benzyl benzoate	XLB	GC-MS	72-108	[6]		
OnBP, DcHxP, DEHP	Ethyl acetate	LLE	DnBP-d4	DB-5MS	GC-MS	> 75	[7]		
PAEse	Hexane	LLE	DnPhP-d4	-	GC-MS	86-114	[8]		
OMP, DEP, BBzP	n-Tetradecane, can	HF- LLME	-	Ascentis-ODS	LC-UV	91-102	[9]		
PAEs <sup>f</sup>	1-Dodecane	LPME	Benzyl benzoate	DB-5MS	GC-MS	84-115	[10]		
OnBP, BBzP, DEHP, DnOP	Toluene	MMLLE	•	DB-5	GC-FID	54-110	[11]		
6PAEs <sup>b</sup>	Acetone	MSPE	External standard	RXi®-5MS	GC-MS	80-125	[12]		
OnBP, DEHP, BBzP	Acetone	SPE	DnBP-d4, BBzP-d4, DEHP-d4			82-106	[13]		
5PAEs <sup>d</sup>	Acetone	DSPE	Triphenyl phosphate	HP-5MS	GC-MS	71-117	[14]		
5 PAEs <sup>d</sup>	DCM/Acetone/MeOH	SPE	-	DB-5MS		71-98	[15]		
PAEs <sup>e</sup>	DCM/Hexane	SPE	DEP-d4, DnBP-d4, DnOP-d4	HP-5MS	GC-MS	61-108	[16]		
1PAEs <sup>g</sup>	Ethyl acetate	SPe	DAIP	HP-1	GC-MS	91-108	[17]		
BPAEs <sup>h</sup>	МеОН	SPE	DMP-d4, DEP-d4, DnBP-d4, BBzP-d4, DEHP-d4, DiNP-d4, DnOP-d4, DiDP-d4	Eclipse-plus- C18	UHPLC- ESI- MS/MS	65-135	[18]		
BPAEs <sup>h</sup>	МеОН	SPE	External calibration	C18	LC-ESI- MS/MS	-	[19]		
BBzP, DEHP	MeOH/DCM	SPE	DBP, DnOP	RP-18	LC-UV	99-104	[20]		
OMP, DAIP, OnBP, BBzP, OcHxP, DEHP	C <sub>6</sub> H <sub>5</sub> Cl	DLLME	-	DB-5MS	GC-MS	68-89	[21]		
OnBP	Solvent-free	SPME	Benzyl benzoate	DB-5MS	GC-FID	-	[22]		
PAEse	Solvent-free	SPME	External calibration	DB-35	GC-ECD	0-116	[23]		
PAEs <sup>e</sup>	Solvent-free	SMPE	External calibration	DB-35	GC-ECD GC-MS	-	[24]		
PAEs, MPEs <sup>i</sup>		SPME	MEP-d4, MBP-d4, DEP-d4, DBP-d4	HP-5MS	GC-MS		[25]		
1PAEs <sup>i</sup>		SPME	DMP-d4, DEP-d4, DnPrP-d4, DnBP-d4, DnHxP-d4, BBzP-d4, DEHP-d4, DBzP-d4	HP-5MS-UI	GC-MS		[26]		
PAEs <sup>k</sup>	DCM/ Hexane	SPME	3,5-Di- <i>tert</i> -butyl- 4-hydroxyanisol	DB-5	GC-FID	78-116	[27]		
DnBP	Without pre-treatment		Benzyl benzoate	C18	LC-UV	-	[28]		
	and drinking water (ta	p, bottled wat							
PAEse	DCM	LLE	DnOP-d4	Rtx-5MS	GC-MS	70-94	[29]		
PAEs <sup>1</sup>	DCM	LLE		TG-5MS	GC-MS	-	[30]		
PAEs <sup>e</sup>	DCM, hexane	LLE, SPE		DB1, DB-5	GC/FID		[31]		
BBzP, DEHP	Acetone	SPE	Internal calibration	DB1	GC-MS		[32]		
5PAEs <sup>m</sup>	Ethyl acetate	SPE	DEHP-d4	Rxi-5MS	GC-MS	-	[33]		

			D140 14 DD0 14				
8PAEs <sup>n</sup>	-	SPME	DMP -d4; DEP-d4, DnBP d4 ; DEHP d4 ; DnOP-d4	DB-5MS	GC-MS	-	[34]
Wastewater sa	amples			*			
6PAEs <sup>e</sup>	Hexane/DCM	LLE	External calibration	HT8	GC-ECD	68-84	[35]
6PAEs <sup>e</sup>	Hexane/DCM	LLE	External calibration	HT8	GC-ECD	68-84	[36]
5PAEs°	DCM	LLE	n-Butyl benzoate	Zorbax Eclipse XDB C18	LC-UV	57-97	[37]
6PAEs <sup>e</sup>	MeOH/Diethylether	SPE	Internal calibration	ZB-5MS	GC-MS	95-106	[38]
6PAEs, 4 MPEs <sup>i</sup>	-	SPME	MEP-d4; MBP-d4; DEP- d4; DBP-d4	HP-5MS	GC-MS	-	[25]
DEP, DEHP	Hexane, DCM, MeOH	SSPE	External calibration	Hypersil Green ENV	LC-MS	69-71	[39]
Seawater sam	ples		1 1 21 21 21 21 21 21 21 21 21 21 21 21				
DnBP, DHxP, DcHxP, DEHP	Ethyl acetate	LLE	DnBP-d4, DEHP-d4	DB5-MS	GC-MS	> 75	[7]
DEP, MEP	Hexane	LLE	-	HP-5	GC- FID/GC- MS	-	[40]
15PAEs <sup>c</sup>	Acetone	DSPE	Triphenyl phosphate	HP-5MS	GC-MS	71-117	[14]
DEP, DnPrP DcHcanACN	, DiBP, SPE		Zorbax Eclipse XDB C8	LC-UV 80-	104 [4	1]	
10MPEs <sup>p</sup>	Ethyl acecane, ACN	SPE	MEP- <sup>13</sup> C4, MnBP- <sup>13</sup> C4, MEHP- <sup>13</sup> C4, MiNP- <sup>13</sup> C4	Synergi RP- MAX C12	LC-MS	50-72	[42]
DEHP	Methanol	SPE	•	C18	LC-UV	70	[43]
DEP, DnBP, BBzP		EE-SPME	•	HP-1	GC-MS	74-93	[44]
Sediment							
5PAEs <sup>q</sup>	DCM/Acetone	ASE	-	Pinnacle <sup>TM</sup> II Phenyl	LC-6AD	83-92	[45]
6PAEs <sup>e</sup>	Ethyl acetate	ASE	DBzP, Benzyl benzoate	DB-5MS	GC-MS	77-102	[46]
10MPEs <sup>p</sup>	AcOH/MeOH	ASE/SPE	MEP- <sup>13</sup> C4, MnBP- <sup>13</sup> C4, MEHP- <sup>13</sup> C4, MiNP- <sup>13</sup> C4	Synergi RP- MAX C12	LC-MS	83-99	[42]
15PAEs <sup>c</sup>	•	MAE	-	DB-5MS	GC-MS	84-109	[15]
DnBP, DEHP BBzP	Cyclohexane/Ethyl acetate	Soxhlet	DnBP-d4, BBzP-d4, DEHP-d4,	DB-XLB	GC-MS	71-102	[13]
16PAEs <sup>b</sup>	DCM	Soxhlet	DiPhP, DnPhP, DnBzP, Benzyl benzoate	DB-5MS	GC-MS	71-108	[2]
DMP, DEP, DnBP, DEHP	DCM	Soxhlet	Butyl benzoate		GC	89-90	[4]
16PAEs <sup>b</sup>	DCM	Soxhlet	DiPhP, DnPhP, DnBzP, benzyl benzoate	DB-5MS	GC/MS	77-109	[47]
6PAEs <sup>e</sup>	Hexane/DCM	USE	DMP-d4, DnBP-d4,	C8	LC/ESI- MS	71-106	[48]
			DnOP-d4	DB-5	GC/MS		
Sludge sample	es			TM			
5PAEs°	DCM/Acetone	ASE	-	Pinnacle <sup>TM</sup> II Phenyl	LC-6AD	83-92	[45]
DEHP	Hexane	Sonication -assisted	tert-butylphenol	HP-5MS	GC-MS	105±8	[49]
DnBP, BBzP, DEHP	Cyclohexane/Ethyl acetate	Soxhlet	DnBP-d4, BBzP-d4, DEHP-d4	DB-XLB	GC-MS	71-102	[13]
16PAEs <sup>b</sup>	DCM	Soxhlet	DMP-d4, DEP-d4, DEHP-d4	HP-5MS	GC-MS	74-100	[50]
6PAEs <sup>e</sup>	DCM	Volatilisati on/condens ation	External calibration	НТ8	GC-ECD	68-84	[36]
Soil samples							
12PAEs <sup>r</sup>	ACN	ASE	2-Methylanthracene	LiChroCART RP-18	LC-UV	82-92	[51]
DEHP	DCM	ASE	DEHP-d4	ZB-5MS	GC-MS	90	[52]
5PAEs <sup>o</sup>	DCM/Acetone	ASE	-	Pinnacle <sup>TM</sup> II Phenyl	LC-6AD	83-92	[44]
DiNP, DEHP	n-Hexane	ASE	DEHP-d4	Rxi-5ms	GC-MS	99±11	[53]
6PAEs <sup>e</sup>	Acetone/Hexane	Centrifiga	DnBP-d4	DB-5	GC-MS	80-113	[54]

		tion					
7PAEs <sup>w</sup>	DCM	SLE	DnBP-d4, BBzP-d4, DEHP-d4, DnOP-d4	DB5-MS	GC-MS	-	[55]
16PAEs <sup>b</sup>	DCM	Soxhlet	DiPhP, DnPhP, DnBzP	DB-5MS	GC-MS	76-111	[56,57]
DnBP, DEHP	DCM/Acetone	USE	-	DB-5MS	GC-FID	≥ 98	[58]
Air							
DEHP, BBzP	DCM	Soxhlet	-	DB-5MS	GC-MS	-	[21]
DiBP, DEHP, DNP	DCM	Soxhlet (QFFs, PUFs)	DiPhP, DnPhP, DnBzP, Benzyl benzoate	HP-5	GC-MS	> 71	[59]
6PAEs <sup>e</sup>	DCM	Soxhlet	DEHP-d4	HP-5MS	GC-MS	75	[60]
16PAEs <sup>b</sup>	DCM	Soxhlet	DiPhP, DnPhP, DnBzP, Benzyl benzoate	DB-5MS	GC-MS	72-121	[61]
17PAEs <sup>s</sup>	DCM	Soxhlet	-	HP-5MS	GC-MS	73-94	[62]
6PAEs <sup>t</sup>	DCM** Hexane/Diethylether*	Soxhlet	DBzP	HP-5MS	GC-MS	86-118** 80-140*	[63]
14PAEs <sup>u</sup>	Hexane/DCM/MeOH	Soxhlet	DnBP-d4, DEHP-d4	HP-5MS	GC-MS	72-105* 82-105**	[64]
6PAEs <sup>t</sup>	Acetone	SPE air sampling	<sup>13</sup> C-DnPeP	DB-5MS	GC-MS <sup>2</sup>	>90-100	[65]
DnBP, DEHP	Acetone/Hexane/MeO H/Carbon disulfide	Sep-Pak PS Air cartridge	External calibration	HP-5MS	GC-MS	94-102	[66]
6PAEs <sup>e</sup>	DCM	USE	Benzyl benzoate	HP-5MS	GC-MS	78-116	[67]
6PAEs <sup>e</sup>	DCM/Acetone	USE	-	DB-5	GC	92-115	[58]
15PAEs <sup>c</sup>	DCM/Acetone	USE	External calibration	DB-5MS	GC-MS	84-107	[5]
15PAEs <sup>c</sup>	Hexane	USE	DEP-d4, DHxP-d4, DEHP-d4	SLB-5MS	GC-MS	-	[68]
BBzP, DEHP	Adsorption tubes (glass, 300mg Tenax TA)		-	DB-1701	TD-GC- MS	-	[69]
7PAEs <sup>v</sup>	Adsorption tubes (Tenax TA)		External calibration	ZB-5	TD-GC- MS	-	[70]
Marine aeros	ols						
DEHP	DCM/MeOH	LLE	C13 n-alkane	DB-5MS	GC-MS		[71]

\*Gas-phase; \*\* Particulate phase

- a. 7PAEs: DMP, DEP, DiPrP, DnBP, DEHP, DnOP, DiOP
- b. 16PAEs: DMP, DEP, DiBP, DnBP, DMGP, DMPP, DEEP, DnAIP, DnHxP, BBzP, HEHP, DBEP, DcHxP, DEHP, DnNP, DnOP
- c. 15PAEs: DMP, DEP, DiBP, DnBP, DMEP, BMPP, DEEP, DnPeP, DHxP, BBzP, DBEP, DcHxP, DEHP, DnOP, DNP
- d. 15PAEs: DMP, DEP, DPrP, DiBP, DnBP, DAIP, DHxP, BBzP, DEHP, DnOP, BMEP, BMPP, DEEP, DBEP, DcHxP
- e. 6PAEs: DMP, DEP, DnBP, BBzP, DEHP, DnOP
- f. 7PAEs: DMP, DEP, DAIP, DnBP, BBzP, DcHxP, DEHP
- g. 11PAEs: DMP, DEP, DPrP, DnBP, DAIP, BBzP, DcHxP, DEHP, DnOP, BMPrP, DMPrP
- h. 8PAEs: DMP, DEP, DnBP, BBzP, DEHP, DnOP, DiNP, DiDP
- i. 6PAEs: DMP, DEP, DnBP, BBzP, DEHP, DOP and 4MPEs: MMP, MEP, MBP, MEHP
- j. 11PAEs: DMP, DEP, DiPrP, DnPrP, DnBP, DnHxP, BBzP, DcHxP, DEHP, DnOP, DBzP
- k. 6PAEs: DMP, DEP, DiPrP, DiBP, DnBP, DEHP
- I. 5PAEs: DEP, DiBP, DnBP, BBzP, DEHP
- m. 5PAEs: DMP, DEP, DiBP, DnBP, DEHP
- n. 8PAEs: DMP, DEP, DiBP, DnBP, BBzP, DHxP, DEHP, DnOP
- o. 5PAEs: DMP, DEP, DnBP, DPhP, DEHP
- p. 10MPEs: MMP, MEP, MnBP, MBzP, MEHP, MnOP, MiHxP, MiHpP, MiNP, MiDP
- q. 5PAEs: DMP, DnBP, DEHP, DiNP, DiDP
- r. 12PAEs: DMP, DEP, DiPrP, DnBP, BBzP, DnPeP, DHxP, DHpP, DEHP, DnOP, DNP, DDP
- s. 17PAEs: DMP, DEP, DiBP, DnBP, DMEP, BMPP, DEEP, DnPeP, DHxP, BBzP, DBEP, DcHxP, DEHP, DnNP, DiNP, DPhP, DnOP
- t. 6PAEs: DMP, DEP, DiBP, DnBP, BBzP, DEHP
- u. 14PAEs: DMP, DEP, DAIP, DiBP, DnBP, DnPeP, BBzP, BOP, DHxP, DiOP, DnOP, DEHP, DiNP, DiDP
- v. 7PAEs: DMP, DEP, DiBP, DnBP, BBzP, DEHP, DnOP
- w. 7PAEs: DnBP, DnPeP, BBzP, DEHP, DnOP, DnNP, DiNP

References:  ${}^{[1]}$ Espadaler et al., 1997;  ${}^{[2]}$ Zeng et al., 2008;  ${}^{[3]}$ Liu et al., 2013;  ${}^{[4]}$ Fatoki et al., 2010;  ${}^{[5]}$ Das et al., 2014;  ${}^{[6]}$ Net et al., 2014;  ${}^{[7]}$ Kim et al., 2007;  ${}^{[8]}$ Gao et al., 2014;  ${}^{[9]}$ Chao et al., 2013;  ${}^{[10]}$ Farahani et a., 2008;  ${}^{[11]}$ Bergström et al., 2007;  ${}^{[12]}$ Luo et al., 2012;  ${}^{[13]}$ Fromme et al., 2002;  ${}^{[14]}$ Wu et al., 2013;  ${}^{[15]}$ Zheng et al., 2014;  ${}^{[16]}$ He et al., 2013;  ${}^{[17]}$ Furtmann, 1994;  ${}^{[18]}$ Liou et al., 2014;  ${}^{[19]}$ Yang et al., 2014;  ${}^{[20]}$ Jara et al., 2000;  ${}^{[21]}$ Farahani et al., 2007;  ${}^{[25]}$ Devier et al., 2006a;  ${}^{[23]}$ Prokůpková et al., 2002;  ${}^{[24]}$ Holadová et al., 2007;  ${}^{[25]}$ Alzaga et al., 2003;  ${}^{[26]}$ Dévier et al., 2013;  ${}^{[27]}$ Batlle and Nerín, 2004;  ${}^{[28]}$ Li et al., 2006b;  ${}^{[29]}$ Amiridou and Voutsa, 2011;  ${}^{[30]}$ Dumitrascu, 2013;  ${}^{[31]}$ EPA, 1995;  ${}^{[32]}$ Félix-Cañedo et al., 2013;  ${}^{[33]}$ Bach et al., 2013;  ${}^{[34]}$ Cao, 2008;  ${}^{[35]}$ Teil et al., 2007;  ${}^{[36]}$ Dargnat et al., 2009;  ${}^{[37]}$ Adewuyi, 2012;  ${}^{[38]}$ Ballesteros et al., 2006;  ${}^{[39]}$ Castillo and Barcelo,1999; [40] Peng et al., 2013;  ${}^{[41]}$  Cai et al., 2003;  ${}^{[42]}$ Blair et al., 2009;  ${}^{[43]}$ Bell and Barsh, 2010;  ${}^{[44]}$ Mousa et al., 2013;  ${}^{[45]}$ Reid et al., 2009;  ${}^{[46]}$ Huang et al., 2008;  ${}^{[47]}$ Sun et al., 2013;  ${}^{[52]}$ Rhind et al., 203;  ${}^{[53]}$ Cousins et al., 2014;  ${}^{[54]}$ Wang et al., 2014;  ${}^{[54]}$ Wang et al., 2013;  ${}^{[55]}$ Vikelsée et al., 2005;  ${}^{[61]}$ Zeng et al., 2010;  ${}^{[62]}$ Wang et al., 2014;  ${}^{[63]}$ Xie et al., 2007;  ${}^{[64]}$ Wang et al., 2014;  ${}^{[69]}$ Choi et al., 2010;  ${}^{[70]}$ Aragon et al., 2013;  ${}^{[70]}$ Bergé, 2012;  ${}^{[70]}$ Litz et al., 2006;  ${}^{[73]}$ Tienpont, 2004;  ${}^{[74]}$ Schiedek, 1995;  ${}^{[75]}$ Guo et al., 2013;  ${}^{[76]}$ Bergé, 2012;  ${}^{[77]}$ Litz et al., 2003;  ${}^{[78]}$ Schreiber et al., 2011;  ${}^{[79]}$ Khedr, 2013;  ${$ 

Table 2: Ions for selected ion monitoring (SIM) of PAEs by GC/MS-EI.

Analyte	Quantifier ion (abundance)	Qualifier ions (abundance)	Reference	Analyte	Quantifier ion (abundance)	Qualifier ions (abundance)	References
DMP	163 (100)	194, 135, 77	[12]	DEHP	167 (36)	279 (9.8), 149 (100)	[7]
		194(15), 135(15)	[29]		149 (100)	279, 167, 113	[12]
		194, 133	[38]			279 (8.8), 167 (34)	[13,29,32,34]
		194, 77	[34]			279	[10,38]
		194	[10,25,73]			167, 57	[30]
		77	[33,72,75]			167	[26,33,25]
			[26]		129	112	[72]
DEP	149 (100)	222, 177, 121	[12]	DPhP	225	197, 153, 77	[12]
		222 (1.6), 177 (23)	[76,77]	DBzP	149	108	[26]
		177, 76	[34]	BBzP	149 (100)	312(1), 206(22)	[77]
						238, 206, 91	[12]
		177 (28)	[10,25,26,29, 38,72,73,75]			238 (5), 206 (25)	[76]
		177, 65	[30]			206, 91	[34,73]
			[33]	1		206	[10,13]
BMEP	59	251, 193, 149	[12]		1	205 (21.5), 91	[29]
						(71.5)	
BEEP	45	149, 121, 72	[12]	1		205	[38]
BBEP	149	249, 193, 57	[12]			91, 65	[30]
DnPrP	149 (100)	209 (5.9), 191 (6.9)	[77]			91	[26,72,75]
DiPrP	149		[26]	DiHpP	149	265	[73]
DnBP 149 (100)	149 (100)	278 (1.0), 223 (7.4), 205, 121		DnOP	149 (100)	279, 261, 179	[12]
		223 (5.5), 205 (4.4)	[13,25,29,76]			279 (6.6), 207 (4.4)	[77]
		223, 104	[74]			279, 150	[34,38,72]
		223	[10,73]			279 (18.0)	[29,75]
		205	[75]			167	[26]
		150	[72]	DiNP	293	149, 71, 57	[12]
		147, 73	[30]			149	[73]
			[26,33]	DiDcP	307	149	[73]
DiBP	149 (100)	223, 205, 167	[12]		149 (100)	307 (6.4)	[77]
	, ,	223 (7.4), 205 (1.9)	[77]	DUP	149 (100)	321 (5.4)	[77]
		223, 57	[34]	DMIP	163	194, 133	[74]
		223	[73]	DMP-d4	167		[26,34]
		57, 41	[30]	DEP-d4	153	181	[25]
	,		[33]				[26,34]
DPeP	149	237, 219, 167	[12]	DiPrP-d4	153		[26]
		237	[73]	DnBP-d4	153 (100)	209, 227	[13,25]
BMPP	149	251, 167, 121	[12]			227 (6.3)	[7,26,34,73]
DAIP	149	189	[10,73]	DnHxP-d4	153		[26]
DnHxP	149 (100)	251 (11), 233 (3.3)	[7]	DEHP-d4	153 (100)	171 (31), 283 (14)	[13]
		251, 104, 76	[12]			171 (41)	[7,33]
		251, 43	[34]				[26,34]
			[26]	DBzP-d4	153		[26]
DcHxP	149 (100)	269, 167, 83	[12]	BBzP-d	153	210	[13]
		249 (17), 167 (32)	[7,73]				[26]
		167 (32), 249 (5.5)	[77]	DnOP-d4	153 (100)	283 (17)	[29,73]
		167	[10,26]				[34]

References: see indication in Table 1.

**Table 3**: Ions for selected ion monitoring (SIM) or MRM transitions of PAEs by LC/MS in positive and negative modes.

Analyte	Quantifier ion Q1	Qualifier ion Q3	Reference		
	Positive	e mode			
DMP	195	163, 133	[78]		
DEP	149	177, 223	[43]		
	223	149, 177	[78]		
BMEP	283	207, 59			
BEEP	311	221, 149			
DnPrP	251	149, 191			
DiPrP	251	149, 191	]		
DnBP	279	149, 205			
	149		[80]		
DiBP	279	149, 205	[78]		
DnPeP	307	219, 149			
DiPeP	307	219, 149			
BMPP	335	167, 251			
DAIP	247	189, 149	]		
BBEP	367	101, 249	1		
DnHxP	335	149, 233	1		
DcHP	331	167, 249			
DEHP	149	167, 391	[43,80]		
	391	167, 279	[78]		
	413.8	414.8	[79]		
DPhP	319	225, 77	[78]		
BBzP	313	149, 205			
DiHpP	363	149, 233			
DnOP	391	261, 149			
DiNP	419	275, 149			
DiDcP	447	149, 289			
	Negativ	e mode			
DEHP	277		[73]		

References: see indication in Table 1.

**Table 4**: Ions for SIM of the corresponding silyl derivatives of phthalic esters by GC/MS-EI (Kim et al., 2007).

Analyte	Quantifier ion (abundance)	Qualifier ion (abundance)
DBP-SE	131 (100)	103 (23), 145 (72)
DHP-SE	159 (100)	103 (42), 115 (5.0)
DCHP-SE	157 (97)	129 (100), 172 (23)
DEHP-SE	187 (80)	103 (100), 202 (0.1)
DBP-d4	295 (17)	147 (100), 310 (2.0)
DEHP-d4	153 (100)	227 (6.3)

Figure 1: Hydrolysis reaction and the derivatization of PAEs by silylation (Kim et al., 2007).

# RAMBOLL

# **MEMO**

# Bis (2-Ethylhexyl) Phthalate or BEHP Investigation

Job

1690000126

Client

U. S. Steel Fairfield

Date To January 17, 2018 Scott Unruh, Brian Lasko, and Eric Williams

From

Jackie Backus

Copy to

Robin Richards, Ramboll

# 1. Background

#### 1.1 Permit Related

The current U. S. Steel Fairfield, Alabama Facility ("USS Fairfield") NPDES Permit was issued in March 2017 with an effective date of April 1, 2017. The Permit contains the following monitoring requirements and numerical limits for Bis (2-Ethylhexyl) Phthalate ("BEHP") for DSN026.

- Daily Maximum: 0.00181 mg/L or 1.81 μg/L limit
- Monthly Average: Report only requirement
- · Monitoring Frequency: Monthly
- Sample Type: Grab

Per the Permit Rationale, BEHP data collected under the previous permit cycle exhibited a reasonable potential to exceed the human health criteria for certain receiving water classifications. This evaluation was performed with composite sample data collected under the previous permit cycle. The previous Permit contained monitor only requirements for BEHP with monthly composite sampling. Due to concerns with BEHP contamination from composite sampling equipment (e.g. tubing), the sample type was changed to grab in the renewed Permit. However, even with the switch in sample type, detectable levels of BEHP were observed in the USS Fairfield DSN026 samples. Subsequently exploratory sampling plans and material reviews have been carried out in order to investigate these detections. The plans and results are described in Sections 2 and 3 of this memo.

Ramboll Environ 4350 North Fairfax Drive Suite 300 Arlington, VA 22203 USA

T +1.703.516.2300 F +1.703.516.2345 www.ramboll-environ.com



#### 1.3 BEHP Analysis Concerns

The most common use of BEHP is as a plasticizer; it is added to plastics to make them flexible. BEHP is used in a variety of consumer materials especially those with PVC components. Many of the materials common to analytical labs and environmental sampling equipment (e.g. disposable pipets, rinse bottles, certain sample bottles and caps, certain gloves, composite sample tubing) are often made with BEHP.

As a result, incidental BEHP contamination from collection and lab equipment is an ongoing issue with BEHP analysis (for many facilities, not just USS Fairfield) especially as lower detection limits are required. For ubiquitous lab contaminates such as Bis (2-ethylhexyl) phthalate, when the sample result is <5X the blank result it's common to conclude that the sample result is due to (or influenced by) contamination. Although less common, blank subtraction has also been used to minimize the impacts of incidental contamination.

A further complicating factor for USS Fairfield is the required method sensitivity. For most methods the reporting limit (or quantification limit) is 3-5X the method detection limit. However, in the case of the BEHP analyse for USS Fairfield, the reporting limit is only 1.4X the method detection limit. The lower reporting limit is necessary in so that the method is sufficiently sensitive; meaning the reporting limit is below the permit limit. These lower detection levels increase the chances for results to be impacted by incidental contamination.

#### 2. Materials Review

USS Fairfield investigated chemicals used on site as possible sources of BEHP. Safety Data Sheets were reviewed for BEHP and any other phthalate components. No USS Fairfield source of BEHP to DSN026 was identified.

- · No process chemicals were found to contain BEHP or other phthalates.
- About 20 materials do contain phthalates. These are typically adhesives, coating, or paints that have minimal potential to impact the DSN026 discharge.

## 3. Sampling Investigations

Two rounds of investigative sampling were performed by USS Fairfield. The first preliminary investigation occurred in May 2015. Under this plan, samples were collected from a variety of internal sample locations using the normal USS sampling technique. Samples were sent to two different analytical labs for analysis. These results were used to help develop the next round of investigative sampling.

The second round also included various internal sample locations and analysis by more than one lab. However, changes were made to the sample collection and preservation methods and



added QC samples (e.g. field duplicates, equipment blanks) were also collected. For contextual information, corresponding grab TSS samples were also collected.

The attached figure shows the detailed water flow diagram for the facility. Using a simplified approach, there are 2 inputs of wastewater to DSN026: DSN013 discharge and FEC Pond discharge. These are commingled prior to the DSN026 monitoring point. The FEC Pond discharge is comprised of stormwater and groundwater while DSN013 discharge is comprised of process wastewater from current operations and some stormwater. Prior to the DSN013 monitoring point, the process wastewater and stormwater are routed through the upper and lower dolomite ponds. These ponds are used for solids settling, aeration, pH monitoring, and (if needed) oil removal. Both rounds of sampling included sampling at some of these locations as part of source investigation efforts.

#### 3.1 First Round of Sampling

In May 2017, the first round of investigatory sampling occurred. Grab samples were collected using either one of two techniques: 1) sample pole with the glass BEHP sample jar attached to the pole, or 2) direct grab/pour into the glass BEHP sample jar.

Samples sent to one lab (ESC) were preserved with sodium thiosulfate and samples sent to the other lab (ALS) did not contain a chemical preservative. Sodium thiosulfate is a common preservative used for EPA Method 625 samples if oxidizing compounds (e.g. chlorine) are expected to be present. It is ESC standard practice to include sodium thiosulfate in bottles used for Method 625 analytes, while ALS standard practice is to not include sodium thiosulfate unless there is a demonstrated need (e.g. measurable residual chlorine).

Table 1 shows the detailed results of the first round of sampling. No USS Fairfield sources of BEHP were indicated by the first round of sampling. With the exception of one sample, all results were non-detect. The one detection was an estimated ("J" flagged result between the method detection limit and reporting limit) result of 0.725 J  $\mu$ g/L for the "pH probe" sample location. The "pH probe" sample location is located in near the pH probe in the 1<sup>st</sup> (or upper) dolomite pond. If there were a USS Fairfield source of BEHP to the dolomite ponds, one would anticipate detections not only at the "pH probe" (1<sup>st</sup> pond) but also at the DSN013 equivalent locations that were tested.

Since limited QC samples were collected during the first round, no conclusions as to incidental contamination from either sampling equipment or lab analysis (e.g. sample prep) can be made.

## 3.2 Second Round of Sampling

Starting in late August 2017 and continuing through early November, the second round of investigatory sampling occurred. As previously indicated, sample collection, preservation, and included QC samples were modified for this round of sampling.

#### WATER



Based on discussions with USS Fairfield personnel, there is no need for the sodium thiosulfate preservative and so for the second investigation, no chemical preservatives were used.

In addition, the following added samples and changes were implemented for the second round of sampling.

- Each event included a trip blank sample. Sample bottles with clean lab water are sent with the sample cooler to the facility. These bottles remain closed and are returned to the lab for analysis.
- Each sample location included equipment blank samples. The collection equipment (pole and empty sample bottle) is first assembled. Then clean lab water is used to rinse the empty sample bottle. The final portion of the rinse water is collected in a separate empty sample bottle and sent for analysis.
- Sample and field duplicate collection. Directly following rinsing of the assembled collection
  equipment (pole and empty sample bottle), the sample is collected. In this case the empty
  sample bottle on the pole acts as transfer vessel. The pole bottle is first "rinsed" with an
  aliquot of DSN026 effluent, emptied and then refilled with DSN026 effluent. The effluent is
  then poured into a sample bottle for analysis as the "sample". Each sample location included
  field duplicate samples. Directly following sample collection, the rinsed pole bottle is refilled
  with DSN026 effluent and poured into a second sample for analysis as the "field duplicate."
- · Matrix spike samples were included for some events and sample locations.
- Events were planned in order to capture both "wet" (effluent known to include stormwater) and "dry" (no recent precipitation) conditions.

Results of the second round of sampling, grouped by sample location, are detailed in Table 2. Examination of the data for sample and/or field blank detections indicates that these detections are either:


- Not consistent. Meaning that only one of the sample pair (sample or field duplicate) showed a detection, or
- 2. Associated with a blank (equipment or method blank) of a similar magnitude.

Other key observations from the round 2 data are:

- No trends for BEHP detections and the presence/absence of stormwater were observed.
- · No trends for BEHP detections and TSS concentrations were observed.

Round 2 DSN026 data was also compared to the results of normal grab sampling. Table 3 shows a side by side comparison. For round 2 sampling, the magnitude of detections were all below the permit limit. When comparing on an average basis, round 2 data are also generally lower than normal sample results. This is shown visibly in the following figure.





It is theorized that this could be related to the following two changes enacting during round 2 sampling:

- No use of sodium thiosulfate preservative and
- Rinsing of the sample equipment prior to sample collection.

#### 4. Conclusions and Recommendations

## 4.1 Conclusions

There is no USS Fairfield source of BEHP to the discharge. Review of safety data sheets shows no production chemicals that contain BEHP or other phthalates. Materials that included

#### WATER



phthalates are typically adhesives, coating, or paints that have minimal potential to impact the DSN026 discharge.

The round 1 and round 2 sampling data support the conclusion that DSN026 detections of BEHP are due to incidental contamination related to sampling equipment or lab analysis (e.g. sample prep). In particular, the round 2 data where added field and lab QC samples/data are available clearly demonstrates the following:

 No consistent (both event to event and for sample/field duplicate pairs) detections of BEHP were observed for either DSN026 or its source waters that are not associated with either equipment or method blank detection of a similar magnitude.

Due to the ubiquitous nature of BEHP and literature documented analytical issues related to incidental contamination, this conclusion is not unexpected.

#### 4.2 Permit Recommendations

USS Fairfield should request removal of the DSN026 associated BEHP limits and monitoring requirements based on the following:

- The original evaluation that determined the need for limits was based on composite sample data which was likely influenced by incidental contamination.
  - The sampling investigations described in Section 3 demonstrate the difficulty in eliminating incidental contamination even for grab samples. The incidental contamination potential for composite samples is even greater given the use of flexible tubing as part of the composite equipment.
- The data used to show the need for limits was influenced by incidental contamination; therefore the need for limits may be overestimated or incorrect.
  - Recent investigations (materials review and sampling) show no USS Fairfield source of BEHP to the DSN026 discharge.

#### 4.3 Sampling Recommendations

Any future monitoring of BEHP should incorporate the following recommendations in order to minimize the possibility of contamination and provide contextual information for interpretation sample results:

- Eliminate the use of the sodium thiosulfate preservative for BEHP samples. Based on the nature of the DSN026 effluent, it is not necessary. Samples will still meet preservation requirements by continuing to cool the samples (≤ 6°C) without any chemical preservation.
- 2. Continue collection of field duplicate and equipment blank samples for each event.

#### TABLE 1. ROUND 1 SAMPLE RESULTS

#### Notes:

"<" indicates a non-detect result at the listed method detection limit.

"J" indicates estimated results between the method detection limit and reporting limit.

"Q" indicates the associated batch QC was outside the established quality control range for precision. Detailed QA/QC data were not available for review, however listed surrogate recoveries were acceptable.

BEHP (µg/L) Results for Wastewater Samples

Sample Date and Analytical Lab	Sodium Thiosulfate Preservative?	Field Blank	pH Probe - collected near pH probe in 1st (upper) dolomite pond	Dolomite Up - collected prior to defoamer addition point for DSN013	Defoam Water / Defoamer Spray - collected at defoamer addition point for DSN013	Dolomite Down - collected downstream of defoamer addition point for DSN013	Dolomite - equivalent to DSN013 but not official sample point	FEC Pond
5/01/2017 ESC	Yes		0.725 J, Q				*	
5/04/2017 ESC	Yes			< 0.709 Q	< 0.709 Q	< 0.709 Q		
5/10/2017 ESC	Yes				< 1.00	< 1.00	< 1.00	
5/11/2017 ALS	No	< 0.40			< 0.40	Broken Bottle	< 0.40	< 0.40
5/16/2017 ALS	No					< 0.40	< 0.40	
5/16/2017 ESC	Yes	< 1.00 Q				< 1.00 Q	< 1.00 Q	

BEHP (µg/L) Results for Water Samples

Sample Date and Analytical Lab	Sodium Thiosulfate Preservative?	Thiosulfate Field		City Water	Bottled Water	
5/10/2017 ESC	Yes		< 1.00	< 1.00	< 1.00	
5/11/2017 ALS	No	< 0.40	< 0.40	Broken Bottle	< 0.40	
5/16/2017 ALS	No		< 0.40			
5/16/2017 ESC	Yes	< 1.00 Q	< 1.00 Q			

#### TABLE 2. ROUND 2 SAMPLE RESULTS

#### Notes:

Bold blue font indicates a detection.

"<" indicates a non-detect result at the listed method detection limit.

"J" indicates estimated results between the method detection limit and reporting limit.

"B" indicates BEHP was also detected in the associated method blank

"Q" indicates that recovery for one of the surrogates was below acceptable limits. Recoveries for the other 2 surrogate were acceptable.

Trip blanks were utilized for each ESC batch of samples. All trip blank results were non-detect (<0.709 ug/L) at the method detection limit.

A field blank (lab water poured from one bottle to another while at the sample location) was also collected for the 8/23/17 event and analyzed by ESC. The result was non-detect (<0.709 ug/L) at the method detection limit.

Matrix spikes were performed using DSN026 samples on 8/23 (ALS), 9/26 (ESC), 10/17 (ESC), and 11/6 (ESC). All recoveries were within the acceptable range.

Unless noted, other reviewed lab QC (lab control spikes and surrogate recoveries) results were within limits for all events.

Sample		Sodium Thiosulfate	odium Thiosulfate pH Probe	BEHP (µg/L)	BEHP (µg/L)	Grab TSS	Comments	
Date	Lab	Preservative?	BEHP (µg/L) Sample	BEHP (µg/L) Field Duplicate	Equipment Blank	Method Blank	(mg/L)	
09/26/17	ESC	No	< 1.00	< 1.00	< 1.00	< 0.709	5.5	
10/17/17	ESC	No	2.09	< 1.00	< 1.00	< 0.709	3.6	Detection questionable since not detected in both the sample and field duplicate.
10/24/17	ESC	No	< 0.709	< 0.709	< 0.709	< 0.709	6.4	
11/06/17	ALS	No	< 0.40	< 0.40	< 0.40	< 0.40	2.7	
11/06/17	ESC	No	1.05 B	< 0.709	< 0.709	0.965 J		Sample detection questionable since 1) method blank detection is of similar magnitude as the sample result and 2) not detected in both the sample and field duplicate.

Sample	1	Sodium Thiosulfate	Founment !	Grab TSS	C			
Date	Lab	Preservative?	BEHP (µg/L) Sample	BEHP (µg/L) Field Duplicate	Blank	Method Blank	(mg/L)	Comments
08/23/17	ALS	No	< 0.40	< 0.40	< 0.44	< 0.40	3.3	
08/23/17	ESC	No	< 0.709	< 0.709	1.10	< 0.709	2.7	Based on equipment blank detection and non-detects in the sample and duplicate, it appears possible equipment contamination was removed by the equipment blank rinses.
09/26/17	ESC	No	< 0.709	< 0.709	< 1.00	< 0.709	3.0	
10/17/17	ESC	No	< 0.709	< 0.709	< 1.00	< 0.709	2.2	
10/24/17	ESC	No	< 0.709	< 0.709	< 0.709	< 0.709	2.8	
11/06/17	ALS	No	< 0.40	< 0.40	< 0.40	< 0.40	2.3	
11/06/17	ESC	No	1.11 B	1.14 B	< 0.709	0.965 J	2.5	Sample and duplicate detections questionable since the method blank detection is of a similar magnitude as the sample and duplicate.

TABLE 2. ROUND 2 SAMPLE RESULTS

Sample Sodium	FEC	Pond	BEHP (µg/L)	BEHP (µg/L)	Grab			
Date	Lab	Thiosulfate Preservative?	BEHP (µg/L) Sample	BEHP (µg/L) Field Duplicate	Equipment Blank	Method Blank	TSS (mg/L)	Comments
08/23/17	ALS	No	< 0.40	< 0.40	< 0.43	< 0.40	7.2	
08/23/17	ESC	No	< 0.709	< 0.709	< 0.709	< 0.709	24.1	
09/26/17	ESC	No	1.24 B	1.14 B	0.966 B, J	1.08	9.1	Sample and duplicate detections questionable since the equipment blank and method blank detections are of a similar magnitude as the sample and duplicate.
10/17/17	ESC	No	< 0.709	< 0.709	1.06 B	< 0.709 for sample/dup 0.870 J for EQ blank	14.3	Method blank detection associated with the equipment blank is of similar magnitude as the equipment blank result.
10/24/17	ESC	No	< 0.709	< 0.709	< 0.709	< 0.709	12.3	
11/06/17	ALS	No	< 0.40	0.61 J	< 0.40 Q	< 0.40	5.1	Detection questionable since not detected in both the sample and field duplicate.
11/06/17	ESC	No	< 0.709	< 0.709	< 0.709	< 0.709	4.7	

Sample	Sample Sodium Thiosulfate	DSN026		BEHP (µg/L)	BEHP (µg/L)	Grab	Comments	
Date	Lab	Preservative?	BEHP (µg/L) Sample	BEHP (μg/L) Field Duplicate	Equipment Blank	Method Blank	TSS (mg/L)	Comments
08/23/17	ALS	No	< 0.40	< 0.40	< 0.43	< 0.40	2.9	
08/23/17	ESC	No	< 0.709	< 0.709	< 0.709	< 0.709	2.7	
09/26/17	ESC	No	1.34 B	< 0.709	< 0.709	1.08	6.0	Sample detection questionable since 1) method blank detection is of similar magnitude as the sample result and 2) not detected in both the sample and field duplicate.
10/17/17	ESC	No	0.859 B, J	0.968 B, J	0.838 B, J	0.870 J	3.4	Sample and duplicate detections questionable since the equipment blank and method blank detections are of a similar magnitude as the sample and duplicate.
10/24/17	ESC	No	< 0.709	< 0.709	< 0.709	< 0.709	2.6	
11/06/17	ALS	No	< 0.40	< 0.40	< 0.40	< 0.40	2.3	
11/06/17	ESC	No	1.02 B	1.36 B	0.979 B, J	0.965 J	10.9	Sample and duplicate detections questionable since the equipment blank and method blank detections are of a similar magnitude as the sample and duplicate.

TABLE 3. DSN026 RESULTS SINCE SWITCHING TO GRAB SAMPLING

Sample		Sodium Thiosulfate	BEHP (µg/L)				
Date	Lab	Preservative?	Sample	Field Duplicate	Average	Comments	
04/11/17	ESC	Yes	7.13 B		7.13 B	Method blank (0.735 µg/L) w/in 1/10 of sample result.	
05/02/17	ESC	Yes	< 1.00		< 1.00	No blank information included in lab report.	
06/06/17	ESC	Yes	1.91		1.91	No blank information included in lab report.	
07/25/17	ESC	. Yes	3.51		3.51	No blank information included in lab report.	
08/08/17	ESC	Yes	2.55 B		2.55 B	Method blank (1.03 µg/L) w/in 1/5 of sample result.	
08/23/17	ALS	No-Part of Round 2	< 0.40	< 0.40	< 0.55	Associated equipment blank and associated method blank non-detect.	
	ESC	No-Part of Round 2	< 0.709	< 0.709	- 0.55	Associated equipment blank and associated method blank non-detect.	
09/26/17	ESC	No-Part of Round 2	1.34 B	< 0.709	1.02 B	Method blank for sample (1.08 μg/L) w/in 1/5 of sample result; Method blank for duplicate was non-detect.	
10/17/17	ESC	No-Part of Round 2	0.859 J, B	0.968 J, B	0.914 J, B	Method blank (0.870 μg/L) and Equipment blank (0.878 μg/L) same magnitude as sample and duplicate.	
10/24/17	ESC	No-Part of Round 2	< 0.709	< 0.709	< 0.709	Associated equipment blank and associated method blank non-detect.	
	ALS	No-Part of Round 2	< 0.40	< 0.40		Associated equipment blank and associated method blank non-detect.	
11/06/17	ESC	No-Part of Round 2	1.02 B	1.36 B	0.80 B	Method blank (0.965 μg/L) and Equipment blank (0.979 μg/L) same magnitude as sample and duplicate.	
11/07/17	ESC	Yes	3.13		3.13	No blank information included in lab report.	
12/05/17	ESC	No	< 1.05		< 1.05	Associated method blank non-detect.	

#### Notes:

Bold red font indicates a detection above the permit limit (1.81  $\mu$ g/L). Bold blank font indicates a detection below the permit limit (1.81  $\mu$ g/L).

"<" indicates a non-detect result at the listed method detection limit.

<sup>&</sup>quot;J" indicates estimated results between the method detection limit and reporting limit.

<sup>&</sup>quot;B" indicates BEHP was also detected in the associated method blank

# Jackson, Scott A

Subject:

RE: Draft Modified NPDES Permit AL0083763 - Additional Review Time Request

From: Brockington, Shawonda (S) <SBrockington@dow.com>

Sent: Friday, January 31, 2020 4:21 PM

To: Jackson, Scott A <scott.jackson@adem.alabama.gov>

Subject: RE: Draft Modified NPDES Permit AL0083763 - Additional Review Time Request

Scott,

A copy of the attached letter has been placed in the mail.

Should there be any questions, please let me know.

Best regards,

Shawonda Brockington

Site EHS&S Leader – DC Alabama, Inc. A wholly owned subsidiary of The Dow Chemical 1940 Ohio Ferro Rd. • Mt. Meigs, Al. 36057 Office: 334.270.3609 | Cell: 504.427.7724

Fax: 334.215.8969 | Email: sbrockington@dow.com





WORLDWIDE PARTNER



January 31, 2020

The Dow Chemical Company
1940 Ohio Ferro Road
Mt. Meigs, AL 36057

Scott Jackson Alabama Department of Environmental Management Water Division – Industrial / Municipal Branch P.O. Box 301463 Montgomery, AL 36130-1463

Subject: DC Alabama, Inc. NPDES Permit AL0083763 – Comments on Draft Permit Modification / Reporting Requirements

Dear Scott;

Part IV C.1.c.(2) of DC Alabama's NPDES permit (AL0083763) specifies that "Biomonitoring test results obtained during each monitoring period shall be summarized and reported using the appropriate Discharge Monitoring Report (DMR) form approved by the Department. In accordance with Section 2. of this part, an effluent toxicity report containing the information in Section 2. shall be included with the DMR. Two copies of the test results must be submitted to the Department no later than 28 days after the month in which the tests were performed."

The last sentence in the paragraph is confusing since the DC Alabama NPDES permit requires that toxicity testing be conducted once per quarter at specified outfalls. The requirement should state that "test results must be submitted to the Department no later than 28 days after the end of the monitoring period in which the tests were performed." This change makes the wording in this part of the permit consistent with reporting requirements specified in Part I C.1.b. of the permit.

Part IV C.2. of the NPDES permit specifies the toxicity testing information to be submitted with each discharge monitoring report and states that "The Department may at any time suspend or reinstate this requirement or may increase or decrease the frequency of submittals." This implies that the Department has the discretion to suspend the requirement to submit the information listed in Part IV C.2. of the NPDES permit. If this is the case, DC Alabama requests that ADEM suspend the requirement to submit the toxicity testing information listed in this part of its NPDES permit and in the modified permit currently being considered by ADEM.

Thank you for your consideration of these comments. If you have questions or need additional information, please call me at (334)270-3609.

Sincerely,

Shawonda Brockington Site EHS&S Site Leader

Shawonda Brockington

DC Alabama, Inc.



# Jackson, Scott A

Subject:

RE: DC Alabama - NPDES Permit Modification

From: Sisk, Lynn/MGM < Lynn.Sisk@jacobs.com>

**Sent:** Tuesday, July 14, 2020 1:13 PM

To: Ramsey, S Scott < SRamsey@adem.alabama.gov>

Cc: Powers, Martin/SEA < Martin.Powers@jacobs.com >; Cesarz, Scott/DET < Scott.Cesarz@jacobs.com >; Gale,

Matthew/CIN < Matthew.Gale@jacobs.com >; Martin, J.P./MGM < J.P.Martin@jacobs.com >

Subject: DC Alabama - NPDES Permit Modification

Scott,

I hope that you and your family are doing well. I am following up on our previous conversation (pre-pandemic) regarding the discharge of uncontaminated groundwater from DC Alabama's new process stormwater retention basin underdrain system. To refresh your memory and provide some background for the following discussion, I will summarize the permit modification process to date.

- DC Alabama submitted a request for a modification of its individual NPDES permit (AL0083763) in May 2019 to include the discharge of treated process stormwater at Outfall 004 to the Tallapoosa River.
- ADEM reviewed the modification request and prepared a DRAFT Modified Permit in July 2019 for DC Alabama's review.
- Following DC Alabama's review of the draft modified NPDES permit and additional review of available water quality data, ADEM prepared a revised draft modified NPDES permit in December 2019 to add monitoring requirements for Bis (2-Ethylhexyl) Phthalate. By this time, construction of the new stormwater retention basin was well underway.
- Following the completion of DC Alabama's review of the revised draft modified NPDES permit in January 2020 but prior to issuance of a Final Modified NDPES permit by ADEM, it became evident that an underdrain system would be needed for the new stormwater basin to prevent shallow groundwater from damaging the concrete floor of the basin.
- On February 14, 2020, I contacted you to discuss possible options for managing the water from the underdrain and to determine if the discharge of this water to the stormwater drainage channel adjacent to the stormwater retention basin would need coverage in the NPDES permit. You stated that ADEM would need to review the results of a laboratory sampling analysis to determine if the water from the underdrain system was "uncontaminated" before a determination of how, or if, the discharge of the underdrain water should be addressed in the NPDES permit.
- Issuance of a Final Modified NPDES permit for the DC Alabama facility was put on hold until a sample of the underdrain water could be analyzed and the results reviewed by the Water Division of ADEM.

The attached spreadsheet contains the results of the laboratory analyses conducted on a sample collected from the underdrain system on February 27, 2020. The results confirm that the shallow groundwater collected by the underdrain system can be considered "uncontaminated" groundwater. The discharge of this water will be intermittent and based on shallow groundwater levels which fluctuate in response to rainfall. The rate of discharge during discharge events is estimated to be approximately 20 gallons per minute (28,800 gallons per day).

Let me know if you have questions about the data or need additional information. I am available to discuss the sample results and the next step in issuance of the Final Modified NPDES permit for the DC Alabama facility at your convenience.

Lynn Sisk, P.E. Jacobs Technologist | BIAF 334.215.9060 334.467.6284 mobile 334.273.7504 fax Lynn.Sisk@jacobs.com

www.jacobs.com

NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.

SW-13\_20200227\_N\_WS 2/27/2020

METAL         SW6010C         D         ALUMINUM         mg/l         0.50         0.903         0.500           METAL         SW6010C         D         ANTIMONY         mg/l         0.05 U         0.05         0.004         0.050           METAL         SW6010C         D         ARSENIC         mg/l         0.01 U         0.01         0.003         0.010           METAL         SW6010C         D         BARIUM         mg/l         0.12 U         0.02         0.001         0.020           METAL         SW6010C         D         BERYLLIUM         mg/l         0.055 U         0.01         0.000         0.005           METAL         SW6010C         D         BORON         mg/l         0.025 J         0.01         0.000         0.005           METAL         SW6010C         D         CALCIUM         mg/l         0.024 J         1.00         0.00         0.01         0.00         0.01         0.00         0.01         0.00         0.01         0.00         0.00         0.01         0.00		I						_N_WS 2/2	
METAL   SWEDICC   D   ANTHONY	Analysis	ANALYTIC_METHOD	Fraction	Analyte	Unit	Result	RDL.	MDL	QL
METAL SWEDUC   D ASSENIC   mg/l 0.01.0   0.063   0.020	METAL	SW6010C	D	ALUMINUM	mg/l	0.5 U	0.50	0.093	0.500
METAL   SW6510C	METAL	SW6010C	D	ANTIMONY	mg/l	0.05 U	0.05	0.004	0.050
METAL   SW6016C	METAL	SW6010C	D	ARSENIC	mg/l	0.01 U	0.01	0.003	0.010
METAL   SW6010C   D   BERYLLUM   mg/l   0.005 J   0.021   0.020   0.002   0.002   0.000   0.			D	BARTUM	ma/l	0.12	0.02	0.001	0.020
METAL   SW6010C   D									
METAL SW6010C   D   CAZCIUM   mg/l   25   100   0.024   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   1.090   0.004   0.008   0.001   0.008   0.00				-					
METAL SWISDIGC   D									
METAL SWEGIGE   D   CHECHRIM   mg/l   0.01 U   0.01   0.002   0.010			D		mg/l	0.0004 J	0.01		0.005
METAL   SWE010C	METAL	SW6010C	D	CALCIUM	mg/l	26	1.00	0.024	1.000
MCTAL   SW6010C   D   CORALT   mg/l   0.008   0.01   0.009   0.010	METAL	SW6010C	D	CHROMIUM	mg/l	0.01 U	0.01	0.002	0.010
METAL   SW6010C	-		D			0.0086 1	0.01	0.000	0.010
METAL   SWE010C									
METAL   SW6010C									
METAL   SW6010C   D   MAGNESIUM   mg/l   7.2   1.00   0.055   1.000   METAL   SW6010C   D   MAGNAESE   mg/l   5.5 8   0.01   0.000   0.000   0.000   METAL   SW6010C   D   MERCIRY   ug/l   0.25 U   0.25   0.200   0.250   0.000   METAL   SW6010C   D   MCLYBDENUM   mg/l   0.013 U   0.011   0.010   0.001   0.010   0.011   0.01			ł						
METAL   SW001DC   D   MANCAMESE   mg/l   0.25 U 0.25 0.100 0.025	METAL	SW6010C	D	LEAD	mg/l	0.01 U	0.01	0.002	0.010
METAL   SW747DA   D   MERCURY   Ug/f   0.25 U 0.25   0.00 0.290	METAL	SW6010C	D	MAGNESIUM	mg/l	7.2	1.00	0.056	1.000
METAL   SW747DA   D   MERCURY   Ug/f   0.25 U 0.25   0.00 0.290	METAL	SW6010C	D	MANGANESE	mg/l	5.9 B	0.01	0.000	0.010
METAL   SW6010C	METAL	SW7470A	D			0.25 U	0.25	0.100	0.250
METAL   SW6010C		<del></del>	<del>-</del> -			<del></del>			
METAL   SW6010C			+ -						
METAL   SW6010C									
METAL   SW6010C	METAL		D		mg/l				
METAL   SWE010C	METAL	SW6010C	D	5ELENIUM	mg/l	0.04 U	0.04	0.003	0.040
METAL   SWE010C	METAL	SW6010C	D	Silica as SiO2	mg/l	13	0.43	0.005	0.430
METAL   SW6010C							0.01		
METAL   SW6010C				<del></del>					
METAL         SW6010C         D         VANADIUM         mg/I         0.01 U         0.001         0.000         0.010           METAL         SW6010C         D         ZINC         mg/I         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ALUMINUM         mg/I         0.5 U         0.50         0.093         0.500           METAL         SW6010C         T         ANTIMONY         mg/I         0.05 U         0.01         0.000         0.002         0.001         0.000									
METAL   SW6010C									
METAL         SW6010C         T         ALUMINUM         mg/l         0.5U         0.50         0.933         0.500           METAL         SW6010C         T         ANTIMONY         mg/l         0.01         0.05         0.004         0.050           METAL         SW6010C         T         ARSENIC         mg/l         0.01         0.001         0.003         0.010           METAL         SW6010C         T         BARIUM         mg/l         0.013         0.02         0.001         0.000         0.005           METAL         SW6010C         T         BARIUM         mg/l         0.051         0.001         0.000         0.005           METAL         SW6010C         T         CADMIUM         mg/l         0.004         0.01         0.000         0.005           METAL         SW6010C         T         CALCIUM         mg/l         26         1.00         0.024         1.000           METAL         SW6010C         T         CHROMUM         mg/l         206         1.00         0.024         1.000           METAL         SW6010C         T         COPPER         mg/l         0.01         0.000         0.010           METAL	METAL		D	_	mg/l		0.01		0.010
METAL         SW6010C         T         ANTINONY         mg/l         0.05 U         0.05         0.004         0.050           METAL         SW6010C         T         ARSENIC         mg/l         0.01 U         0.01         0.003         0.010           METAL         SW6010C         T         BARIUM         mg/l         0.03 U         0.01         0.000         0.001           METAL         SW6010C         T         BERYLLUM         mg/l         0.026 U         0.01         0.000         0.005           METAL         SW6010C         T         CADMIUM         mg/l         0.004 J         0.01         0.000         0.000           METAL         SW6010C         T         CALCIUM         mg/l         0.01 U         0.002         0.010           METAL         SW6010C         T         CORALT         mg/l         0.010 U         0.002         0.010           METAL         SW6010C         T         CORALT         mg/l         0.008 J         0.01         0.002         0.010           METAL         SW6010C         T         ICRA         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C	METAL	SW6010C	D	ZINC	mg/i	0.03 U	0.03	0.004	0.030
METAL         SW6010C         T         ANTINONY         mg/l         0.05 U         0.05         0.004         0.050           METAL         SW6010C         T         ARSENIC         mg/l         0.01 U         0.01         0.003         0.010           METAL         SW6010C         T         BARIUM         mg/l         0.03 U         0.01         0.000         0.001           METAL         SW6010C         T         BERYLLUM         mg/l         0.026 U         0.01         0.000         0.005           METAL         SW6010C         T         CADMIUM         mg/l         0.004 J         0.01         0.000         0.000           METAL         SW6010C         T         CALCIUM         mg/l         0.01 U         0.002         0.010           METAL         SW6010C         T         CORALT         mg/l         0.010 U         0.002         0.010           METAL         SW6010C         T         CORALT         mg/l         0.008 J         0.01         0.002         0.010           METAL         SW6010C         T         ICRA         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C	METAL	SW6010C	Т	ALUMINUM	ma/l	0.5 U	0.50	0.093	0.500
METAL   SW6010C									
METAL         SW6010C         T         BARIUM         mg/l         0.13         0.02         0.001         0.020           METAL         SW6010C         T         BERYLLIUM         mg/l         0.005 U         0.01         0.000         0.001         0.000         0.001         0.000         0.001         0.000         0.001         0.000         0.001         0.000         0.012         0.20         0.012         0.20         0.012         0.20         0.012         0.20         0.012         0.20         0.012         0.20         0.012         0.00         0.012         0.00         0.012         0.00         0.012         0.00         0.012         0.00         0.012         0.00         0.012         0.00         0.012         0.00         0.012         0.00         0.012         0.00<									
METAL   SW6010C				<u></u>					
METAL         SW6010C         T         BORON         mg/l         0.026 J         0.20         0.012         0.200           METAL         SW6010C         T         CAMHUM         mg/l         0.004 J         0.01         0.00         0.005           METAL         SW6010C         T         CALCIUM         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         CHROMIUM         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         COPPER         mg/l         0.01 U         0.01         0.008         0.010           METAL         SW6010C         T         COPPER         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         LEAD         mg/l         4.7         0.40         0.027         0.400           METAL         SW6010C         T         MAGNESLIM         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         MAGNESLIM         mg/l         0.0035         1.00         0.01         0.010           META	METAL	SW6010C					0.02		
METAL         SW6010C         T         CADMIUM         mg/l         0.0004 J         0.01         0.000         0.005           METAL         SW6010C         T         CALCIUM         mg/l         26 I         1.00         0.24 I         1.000           METAL         SW6010C         T         CHROMIUM         mg/l         0.01 U         0.01 0         0.000         0.010           METAL         SW6010C         T         COBALT         mg/l         0.01 U         0.01 0         0.000         0.010           METAL         SW6010C         T         COPPER         mg/l         0.01 U         0.01 0         0.000         0.010           METAL         SW6010C         T         IRON         mg/l         0.01 U         0.01 0         0.002         0.010           METAL         SW6010C         T         MARGNESIUM         mg/l         0.01 U         0.01 0         0.055         1.000           METAL         SW6010C         T         MARGNESE         mg/l         6.0 0.01 0         0.001         0.010         0.010         0.010         0.010         0.010         0.010         0.010         0.010         0.010         0.010         0.010         0.010	METAL	SW6010C	T	BERYLLIUM	mg/l	0.005 U	0.01	0.000	0.005
METAL         SW6010C         T         CADMIUM         mg/l         0.0004 J         0.01         0.000         0.005           METAL         SW6010C         T         CALCIUM         mg/l         26         1.00         0.024         1.000           METAL         SW6010C         T         CHROMIUM         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         COPPER         mg/l         0.01 U         0.01         0.008         0.010           METAL         SW6010C         T         COPPER         mg/l         0.01 U         0.01         0.008         0.010           METAL         SW6010C         T         IRON         mg/l         4.7 U         0.0         0.027         0.400           METAL         SW6010C         T         ILEAD         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         MANGANESE         mg/l         6.01 U         0.005         1.000           METAL         SW6010C         T         MCKEL         mg/l         0.01 U         0.01         0.010           METAL         SW6010C         T <td>METAL</td> <td>SW6010C</td> <td>T</td> <td>BORON</td> <td>mg/l</td> <td>0.026 J</td> <td>0.20</td> <td>0.012</td> <td>0.200</td>	METAL	SW6010C	T	BORON	mg/l	0.026 J	0.20	0.012	0.200
METAL         SW6010C         T         CALCIUM         mg/l         26         1.00         0.024         1.000           METAL         SW6010C         T         CHROMIUM         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         COPPER         mg/l         0.01 U         0.01         0.008         0.010           METAL         SW6010C         T         IRON         mg/l         4.7         0.40         0.027         0.400           METAL         SW6010C         T         IRON         mg/l         4.7         0.40         0.027         0.400           METAL         SW6010C         T         MAGNESIUM         mg/l         6.7         1.00         0.056         1.000           METAL         SW6010C         T         MAGNESIUM         mg/l         6         0.01         0.000         0.010           METAL         SW6010C         T         MOLYBDENUM         mg/l         0.001         0.010         0.010           METAL         SW6010C         T         MOLYBDENUM         mg/l         0.01         0.001         0.010           METAL         SW6010C         T								0.000	0.005
METAL         SW6010C         T         CHROMIUM         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         COBALT         mg/l         0.0085 J         0.00         0.000         0.010           METAL         SW6010C         T         COPER         mg/l         0.01 U         0.01         0.008         0.010           METAL         SW6010C         T         IRON         mg/l         4.7         0.40         0.027         0.400           METAL         SW6010C         T         MAGNESIUM         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         MAGNESIUM         mg/l         6         0.01         0.006         0.010           METAL         SW6010C         T         MANGANESE         mg/l         6         0.01         0.001         0.010           METAL         SW6010C         T         MICKEL         mg/l         0.01 U         0.01         0.001         0.010           METAL         SW6010C         T         SELENIUM         mg/l         0.04 U         0.03         0.040           METAL         SW6010C<		<del></del>	+						
METAL         SW6010C         T         COBALT         mg/l         0.0085 J         0.01         0.000         0.010           METAL         SW6010C         T         COPPER         mg/l         0.01 U         0.01         0.008         0.010           METAL         SW6010C         T         IRON         mg/l         4.7         0.40         0.027         0.400           METAL         SW6010C         T         ILEAD         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         MANGANESE         mg/l         6         0.01         0.000         0.010           METAL         SW6010C         T         MOLYBDENUM         mg/l         0.003 J         0.01         0.001         0.010           METAL         SW6010C         T         NICKEL         mg/l         0.01 U         0.01         0.001         0.010           METAL         SW6010C         T         NICKEL         mg/l         0.01 U         0.01         0.001         0.001           METAL         SW6010C         T         SILCANUM         mg/l         0.04 U         0.03         0.04         0.03         0.04         0.03<		<del></del>	+						
METAL         SW6010C         T         COPPER         mg/l         0.01 U         0.01 U         0.008         0.010           METAL         SW6010C         T         IRON         mg/l         4.7         0.40         0.027         0.400           METAL         SW6010C         T         ILEAD         mg/l         0.01 U         0.01         0.002         0.010           METAL         SW6010C         T         MAGNESIUM         mg/l         6         0.01         0.000         0.010           METAL         SW6010C         T         MANGANESE         mg/l         6         0.01         0.001         0.010           METAL         SW6010C         T         MCKEL         mg/l         0.010         0.011         0.011         0.011         0.011         0.010         0.011         0.011         0.011         0.010         0.011         0.011         0.011         0.010         0.011         0.010         0.011         0.010         0.011         0.010         0.011         0.011         0.011         0.011         0.011         0.011         0.011         0.011         0.011         0.011         0.011         0.011         0.011         0.011         0.011			+						
METAL         SW6010C         T         IRON         mg/l         4.7         0.40         0.027         0.400           METAL         SW6010C         T         LEAD         mg/l         0.01         0.01         0.002         0.010           METAL         SW6010C         T         MAGNESIUM         mg/l         7.2         1.00         0.056         1.000           METAL         SW6010C         T         MAGNESIUM         mg/l         6         0.01         0.001         0.010           METAL         SW6010C         T         MCKEL         mg/l         0.010         0.011         0.001         0.010           METAL         SW6010C         T         POTASSIUM         mg/l         3.7         1.00         0.037         1.00           METAL         SW6010C         T         SILVER         mg/l         0.04 U         0.03         0.040           METAL         SW6010C         T         SILVER         mg/l         0.0021 J         0.01         0.01         0.01           METAL         SW6010C         T         THALILUM         mg/l         0.01 U         0.01         0.01         0.01           METAL         SW6010C	METAL	SW6010C	T	COBALT	mg/l	0.0085 J	0.01	0.000	0.010
METAL         SW6010C         T         LEAD         mg/l         0.01 U         0.01 U         0.002         0.010           METAL         SW6010C         T         MAGNESIUM         mg/l         7.2         1.00         0.056         1.000           METAL         SW6010C         T         MANGANESE         mg/l         6         0.01         0.000         0.010           METAL         SW6010C         T         MOLYBDENIM         mg/l         0.036 J         0.01         0.001         0.010           METAL         SW6010C         T         NICKEL         mg/l         0.01 U         0.01         0.001         0.010           METAL         SW6010C         T         POTASSIUM         mg/l         3.7         1.00         0.037         1.000           METAL         SW6010C         T         SELENIUM         mg/l         0.04 U         0.04         0.004         0.004           METAL         SW6010C         T         SILVER         mg/l         0.021 J         0.01         0.01         0.01         0.01           METAL         SW6010C         T         T SILUTUM         mg/l         0.01 J         0.03         0.04         0.03 <td< td=""><td>METAL</td><td>SW6010C</td><td>Т</td><td>COPPER</td><td>mg/l</td><td>0.01 U</td><td>0.01</td><td>0.008</td><td>0.010</td></td<>	METAL	SW6010C	Т	COPPER	mg/l	0.01 U	0.01	0.008	0.010
METAL         SW6010C         T         LEAD         mg/l         0.01 U         0.01 U         0.002         0.010           METAL         SW6010C         T         MAGNESIUM         mg/l         7.2         1.00         0.056         1.000           METAL         SW6010C         T         MANGANESE         mg/l         6         0.01         0.000         0.010           METAL         SW6010C         T         MOLYBDENIM         mg/l         0.036 J         0.01         0.001         0.010           METAL         SW6010C         T         NICKEL         mg/l         0.01 U         0.01         0.001         0.010           METAL         SW6010C         T         POTASSIUM         mg/l         3.7         1.00         0.037         1.000           METAL         SW6010C         T         SELENIUM         mg/l         0.04 U         0.04         0.004         0.004           METAL         SW6010C         T         SILVER         mg/l         0.021 J         0.01         0.01         0.01         0.01           METAL         SW6010C         T         T SILUTUM         mg/l         0.01 J         0.03         0.04         0.03 <td< td=""><td></td><td>SW6010C</td><td>Т</td><td>IRON</td><td>ma/l</td><td>4.7</td><td>0.40</td><td>0.027</td><td>0.400</td></td<>		SW6010C	Т	IRON	ma/l	4.7	0.40	0.027	0.400
METAL         SW6010C         T         MAGNESIUM         mg/l         7.2         1.00         0.056         1.000           METAL         SW6010C         T         MANGANESE         mg/l         6         0.01         0.000         0.010           METAL         SW6010C         T         MOLYBDENUM         mg/l         0.001 U         0.01         0.001         0.010           METAL         SW6010C         T         POTASSIUM         mg/l         0.01 U         0.02 U         0.02 U         0.04 U </td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>									
METAL         SW6010C         T         MANGANESE         mg/l         6         0.01         0.000         0.010           METAL         SW6010C         T         MOLYBDENUM         mg/l         0.0036 J         0.01         0.001         0.010           METAL         SW6010C         T         NICKEL         mg/l         0.01 U         0.01         0.011           METAL         SW6010C         T         POTASSIUM         mg/l         3.7         1.00         0.037         1.000           METAL         SW6010C         T         SELENIUM         mg/l         0.04 U         0.04         0.037         1.000           METAL         SW6010C         T         SIIIca as SiO2         mg/l         14         0.43         0.005         0.430           METAL         SW6010C         T         SILVER         mg/l         0.0021 J         0.01         0.001         0.010           METAL         SW6010C         T         THALLIUM         mg/l         0.016 J^A         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.010 J^A         0.030         0.004         0.030           METAL			<del>{</del>						
METAL         SW6010C         T         MOLYBDENUM         mg/l         0.0363         0.01         0.010         0.010           METAL         SW6010C         T         NICKEL         mg/l         0.01 U         0.01         0.001         0.010           METAL         SW6010C         T         POTASSIUM         mg/l         3.7         1.00         0.037         1.000           METAL         SW6010C         T         SIICERIUM         mg/l         0.04 U         0.04         0.003         0.040           METAL         SW6010C         T         SIICER         mg/l         1.00         0.03         0.040           METAL         SW6010C         T         SILVER         mg/l         0.021 I         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.01         0.00         0.021         1.000         MeTAL         SW6010C         T         TAHALIJUM         mg/l         0.01 U         0.00         0.01         0.00         MeTAL         SW6010C         T         TAHALIJUM         mg/l         0.01 U         0.00			+					-	
METAL         SW6010C         T         NICKEL         mg/l         0.01 U         0.01 U         0.001 U         0.003 U         0.003 U         0.003 U         0.003 U         0.003 U         0.004 U         0.005 U							-		
METAL         SW6010C         T         POTASSIUM         mg/l         3.7         1.00         0.037         1.000           METAL         SW6010C         T         SELENIUM         mg/l         0.04 U         0.04         0.003         0.040           METAL         SW6010C         T         SIIk VER         mg/l         14         0.43         0.005         0.430           METAL         SW6010C         T         SILVER         mg/l         0.0021         0.01         0.001         0.011           METAL         SW6010C         T         THALLIUM         mg/l         0.016 J^A         0.03         0.004         0.030           METAL         SW6010C         T         THALLIUM         mg/l         0.01 U         0.01         0.000         0.011           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.25 U         0.01         0.000         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03         0.004         0.030           METAL         SW6010C	METAL	SW6010C	T	MOLYBDENUM	mg/l	0.0036 J	0.01	0.001	0.010
METAL         SW6010C         T         SELENIUM         mg/l         0.04 U         0.04         0.003         0.040           METAL         SW6010C         T         Silica as SiO2         mg/l         14         0.43         0.005         0.430           METAL         SW6010C         T         SILVER         mg/l         0.0021 J         0.01         0.001         0.001           METAL         SW6010C         T         T Sodium         mg/l         0.016 J^A         0.03         0.004         0.030           METAL         SW6010C         T         T HALLIUM         mg/l         0.01 U         0.01         0.000         0.004         0.030           METAL         SW6010C         T         T VANADIUM         mg/l         0.01 U         0.01         0.000         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.01 U         0.01         0.00         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030	METAL	SW6010C	T	NICKEL	mg/l	0.01 U	0.01	0.001	0.010
METAL         SW6010C         T         SELENIUM         mg/l         0.04 U         0.04         0.003         0.040           METAL         SW6010C         T         Silica as SiO2         mg/l         14         0.43         0.005         0.430           METAL         SW6010C         T         SILVER         mg/l         0.0021 J         0.01         0.001         0.001           METAL         SW6010C         T         T Sodium         mg/l         0.016 J^A         0.03         0.004         0.030           METAL         SW6010C         T         T HALLIUM         mg/l         0.01 U         0.01         0.000         0.004         0.030           METAL         SW6010C         T         T VANADIUM         mg/l         0.01 U         0.01         0.000         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.01 U         0.01         0.00         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030	METAL	<u> </u>	Т	POTASSIUM	mg/l	3.7	1.00	0.037	1.000
METAL         SW6010C         T         Silica as SiO2         mg/l         14         0.43         0.005         0.430           METAL         SW6010C         T         SILVER         mg/l         0.0021 J         0.01         0.001         0.010           METAL         SW6010C         T         THALLIUM         mg/l         29 B         1.00         0.021         1.000           METAL         SW6010C         T         THALLIUM         mg/l         0.01 U         0.01         0.000         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL <td></td> <td><u> </u></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>		<u> </u>							
METAL         SW6010C         T         SILVER         mg/l         0.0021         0.01         0.001         0.010           METAL         SW6010C         T         Sodium         mg/l         29 B         1.00         0.021         1.000           METAL         SW6010C         T         THALLIUM         mg/l         0.016 J^         0.03         0.004         0.030           METAL         SW6010C         T         VANADIUM         mg/l         0.01 U         0.01         0.000         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         MERCURY         ug/l         1.00         0.25         0.100         0.00         0.00						<del></del>			
METAL         SW6010C         T         Sodium         mg/l         29 B         1.00         0.021         1.000           METAL         SW6010C         T         THALLIUM         mg/l         0.016 J^         0.03         0.004         0.030           METAL         SW6010C         T         VANADIUM         mg/l         0.01 U         0.01         0.000         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW6010C         T         ZINC         mg/l         0.25 U         0.25 U         0.00         0.000         0.000         0.000         0.000         0.000         0.000         0.000         0.25 U         0.100         0.25 U         0.100         0.120 U         1.000         0.160									
METAL         SW6010C         T         THALLIUM         mg/l         0.016 J^         0.03         0.004         0.030           METAL         SW6010C         T         VANADIUM         mg/l         0.01 U         0.01         0.000         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW7470A         T         MERCURY         ug/l         0.25 U         0.25         0.100         0.250           PCB         SW8082         T         Aroclor 1016         ug/l         1 U*         1.00         0.540         1.000           PCB         SW8082         T         Aroclor 1221         ug/l         1 U*         1.00         0.440         1.000           PCB         SW8082         T         Aroclor 1232         ug/l         1 U*         1.00         0.120         1.000           PCB         SW8082         T         Aroclor 1242         ug/l         1 U*         1.00         0.200         1.000           PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00         0.340         1.000           <	$\overline{}$	<del> </del>							
METAL         SW6010C         T         VANADIUM         mg/l         0.01 U         0.01         0.000         0.010           METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW7470A         T         MERCURY         ug/l         0.25 U         0.25         0.100         0.250           PCB         SW8082         T         Aroclor 1016         ug/l         1 U*         1.00         0.540         1.000           PCB         SW8082         T         Aroclor 1221         ug/l         1 U*         1.00         0.440         1.000           PCB         SW8082         T         Aroclor 1232         ug/l         1 U*         1.00         0.120         1.000           PCB         SW8082         T         Aroclor 1242         ug/l         1 U*         1.00         0.160         1.000           PCB         SW8082         T         Aroclor 1248         ug/l         1 U*         1.00         0.240         1.000           PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00         0.340         1.000	METAL		+		<del></del>	<del></del>			
METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03 U         0.03 O         0.04 O         0.030 O           METAL         SW7470A         T         MERCURY         ug/l         0.25 U         0.25 U         0.25 O         0.100 O         0.250           PCB         SW8082         T         Aroclor 1016         ug/l         1 U*         1.00 O         0.540 I         1.000           PCB         SW8082         T         Aroclor 1221         ug/l         1 U*         1.00 O         0.440 I         1.000           PCB         SW8082         T         Aroclor 1232         ug/l         1 U*         1.00 O         0.120 I         1.000           PCB         SW8082         T         Aroclor 1242         ug/l         1 U*         1.00 O         0.160 I         1.000           PCB         SW8082         T         Aroclor 1248         ug/l         1 U*         1.00 O         0.200 I         1.000           PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00 O         0.340 I         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U	METAL	SW6010C	Т	THALLIUM	mg/l	0.016 J^	0.03	0.004	0.030
METAL         SW6010C         T         ZINC         mg/l         0.03 U         0.03         0.004         0.030           METAL         SW7470A         T         MERCURY         ug/l         0.25 U         0.00 U         0.25 U         0.00 U         0.25 U         0.26 U         1.000         0.200         1.000         1.000         0.26 U         1.000         0.26 U         1.000         0.24 U         1.000         0.24 U         1.000         0.24 U         1.000         0.24 U <t< td=""><td>METAL</td><td>SW6010C</td><td>Т</td><td>VANADIUM</td><td>mg/l</td><td>0.01 U</td><td>0.01</td><td>0.000</td><td>0.010</td></t<>	METAL	SW6010C	Т	VANADIUM	mg/l	0.01 U	0.01	0.000	0.010
METAL         SW7470A         T         MERCURY         ug/l         0.25 U         0.25 U         0.25 O.100         0.250           PCB         SW8082         T         Aroclor 1016         ug/l         1 U*         1.00         0.540         1.000           PCB         SW8082         T         Aroclor 1221         ug/l         1 U*         1.00         0.440         1.000           PCB         SW8082         T         Aroclor 1232         ug/l         1 U*         1.00         0.120         1.000           PCB         SW8082         T         Aroclor 1242         ug/l         1 U*         1.00         0.160         1.000           PCB         SW8082         T         Aroclor 1248         ug/l         1 U*         1.00         0.200         1.000           PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00         0.140         1.000           PCB         SW8082         T         Aroclor 1260         ug/l         1 U*         1.00         0.340         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000 <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>0.004</td> <td>0.030</td>								0.004	0.030
PCB         SW8082         T         Aroclor 1016         ug/l         1 U*         1.00         0.540         1.000           PCB         SW8082         T         Aroclor 1221         ug/l         1 U*         1.00         0.440         1.000           PCB         SW8082         T         Aroclor 1232         ug/l         1 U*         1.00         0.120         1.000           PCB         SW8082         T         Aroclor 1242         ug/l         1 U*         1.00         0.160         1.000           PCB         SW8082         T         Aroclor 1248         ug/l         1 U*         1.00         0.200         1.000           PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00         0.140         1.000           PCB         SW8082         T         Aroclor 1260         ug/l         1 U*         1.00         0.340         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000           SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2,2 U         2,20         0.360         2,200									
PCB         SW8082         T         Aroclor 1221         ug/l         1 U*         1.00         0.440         1.000           PCB         SW8082         T         Aroclor 1232         ug/l         1 U*         1.00         0.120         1.000           PCB         SW8082         T         Aroclor 1242         ug/l         1 U*         1.00         0.160         1.000           PCB         SW8082         T         Aroclor 1248         ug/l         1 U*         1.00         0.200         1.000           PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00         0.140         1.000           PCB         SW8082         T         Aroclor 1260         ug/l         1 U*         1.00         0.340         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000           SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2,2 U         2,20         0.320         2,200           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2,7 U         2.70         0.280         2,700					<del> </del>				
PCB         SW8082         T         Aroctor 1232         ug/l         1 U*         1.00         0.120         1.000           PCB         SW8082         T         Aroctor 1242         ug/l         1 U*         1.00         0.160         1.000           PCB         SW8082         T         Aroctor 1248         ug/l         1 U*         1.00         0.200         1.000           PCB         SW8082         T         Aroctor 1254         ug/l         1 U*         1.00         0.140         1.000           PCB         SW8082         T         Aroctor 1260         ug/l         1 U*         1.00         0.340         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000           SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.320         2.200           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700									
PCB         SW8082         T         Aroclor 1242         ug/l         1 U*         1.00         0.160         1.000           PCB         SW8082         T         Aroclor 1248         ug/l         1 U*         1.00         0.200         1.000           PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00         0.140         1.000           PCB         SW8082         T         Aroclor 1260         ug/l         1 U*         1.00         0.340         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000           SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.320         2.200           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700	PCB	SW8082	T	Aroclor 1221	ug/l		1.00		
PCB         SW8082         T         Aroclor 1242         ug/l         1 U*         1.00         0.160         1.000           PCB         SW8082         T         Aroclor 1248         ug/l         1 U*         1.00         0.200         1.000           PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00         0.140         1.000           PCB         SW8082         T         Aroclor 1260         ug/l         1 U*         1.00         0.340         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000           SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.320         2.200           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700	PCB	SW8082	T	Aroclor 1232	ug/l	1 U*	1.00	0.120	1.000
PCB         SW8082         T         Aroclor 1248         ug/l         1 U*         1.00         0.200         1.000           PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00         0.140         1.000           PCB         SW8082         T         Aroclor 1260         ug/l         1 U*         1.00         0.340         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000           SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2,2 U         2.20         0.320         2.200           SVOC         SW8270D         T         2,4,6-TRICHLOROPHENOL         ug/l         2,7 U         2.70         0.280         2.700           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2,7 U         2.70         0.280         2.700				Arodor 1242	ua/l	1 U*	1.00	0.160	1.000
PCB         SW8082         T         Aroclor 1254         ug/l         1 U*         1.00         0.140         1.000           PCB         SW8082         T         Aroclor 1260         ug/l         1 U*         1.00         0.340         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000           SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.320         2.200           SVOC         SW8270D         T         2,4,6-TRICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700					<u> </u>				<b></b> -
PCB         SW8082         T         Aroclor 1260         ug/l         1 U*         1.00         0.340         1.000           SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000           SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.320         2.200           SVOC         SW8270D         T         2,4,6-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.360         2.200           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700			<del></del>						<b></b>
SVOC         SW8260C         T         ISOPROPYLBENZENE (CUMENE)         ug/l         1 U         1.00         0.240         1.000           SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.320         2.200           SVOC         SW8270D         T         2,4,6-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.360         2.200           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700					<del>                                     </del>	<del> </del>			
SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2,2 U         2.20         0.320         2.200           SVOC         SW8270D         T         2,4,6-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.360         2.200           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700	PCB	SW8082	<u> </u>	Aroclor 1260	ug/l		1.00		1.000
SVOC         SW8270D         T         2,4,5-TRICHLOROPHENOL         ug/l         2,2 U         2.20         0.320         2.200           SVOC         SW8270D         T         2,4,6-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.360         2.200           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700	SVOC	SW8260C	T	ISOPROPYLBENZENE (CUMENE)	ug/l	1 U	1.00	0.240	1.000
SVOC         SW8270D         T         2,4,6-TRICHLOROPHENOL         ug/l         2.2 U         2.20         0.360         2.200           SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700								<del></del>	
SVOC         SW8270D         T         2,4-DICHLOROPHENOL         ug/l         2.7 U         2.70         0.280         2.700	-								
			4						
SVOC   SW8270D				<u> </u>					
	SVOC	SW8270D	<u>T</u>	2,4-DIMETHYLPHENOL	ug/l	2.7 U	2.70	0.200	2.700

SVOC	SW8270D	Т	2,4-DINITROPHENOL	ug/l	5.4 U	5.40	0.430	5.400
SVOC	SW8270D	Т	2,4-DINITROTOLUENE	ug/l	1.6 U	1.60	0.350	1.600
SVOC	SW8270D	Т	2,6-DINITROTOLUENE	ug/l	1.1 U	1.10	0.320	1.100
SVOC	SW8270D	Т	2-CHLORONAPHTHALENE	ug/l	1.6 U	1.60	0.210	1.600
SVOC	SW8270D	Т	2-CHLOROPHENOL	ug/l	2.2 U	2.20	0.240	2.200
SVOC	SW8270D	Т	2-METHYLPHENOL (O-CRESOL)	ug/l	1.6 U	1.60	0.210	1.600
SVOC	SW8270D	Т	2-NITROANILINE	ug/i	2.7 U	2.70	0.380	2.700
SVOC	SW8270D	Т	2-NITROPHENOL	ug/l	1.1 U	1.10	0.240	1.100
svoc	SW8270D	Т	3,3'-DICHLOROBENZIDINE	ug/l	5.4 U	5.40	0.350	5.400
svoc	SW8270D	Т	3-Methylphenol & 4-Methylphenol	ug/l	1.1 U	1.10	0.170	1.100
svoc	SW8270D	Т	3-NITROANILINE	ug/l	2.7 U	2.70	0.140	2.700
svoc	SW8270D	Т	4,6-DINITRO-2-METHYLPHENOL	ug/l	2,2 U	2.20	0.170	2.200
svoc	SW8270D	Т	4-BROMOPHENYL PHENYL ETHER	ug/l	1.6 U	1.60	0.270	1.600
svoc	SW8270D	Т	4-CHLORO-3-METHYLPHENOL	ug/l	1. <b>1</b> U	1.10	0.270	1.100
SVOC	SW8270D	T	4-CHLOROANILINE	ug/l	1.1 U	1.10	0.120	1.100
svoc	SW8270D	Т	4-CHLOROPHENYL PHENYL ETHER	ug/l	1.6 U	1.60	0.250	1.600
svoc	SW8270D	T	4-NITROANILINE	ug/l	2.7 U	2.70	0.250	2.700
svoc	SW8270D	Ť	4-NITROPHENOL	ug/l	2.7 U	2.70	0.360	2.700
svoc	SW8270D	T	ACETOPHENONE	ug/l	1.6 U	1.60	0.740	1.600
SVOC	SW8270D	T	ATRAZINE	ug/l	5.4 U*	5.40	1.200	5.400
SVOC	SW8270D	<del>i</del>	Benzaldehyde	ug/l	5.4 U*	5.40	1.300	5.400
SVOC	SW8270D	Ť	BENZYL BUTYL PHTHALATE	ug/l	2.7 U*	2.70	0.920	2.700
SVOC	SW8270D	T	BIPHENYL (DIPHENYL)	ug/l	1.6 U	1.60	0.790	1.600
SVOC	SW8270D	<del>                                     </del>	BIS(2-CHLOROETHOXY) METHANE	ug/l	1.6 U	1,60	0.210	1,600
SVOC	SW8270D	T	BIS(2-CHLOROETHYL) ETHER	ug/l	1.6 U	1.60	0.200	1.600
SVOC	SW8270D	T	BIS(2-CHLOROISOPROPYL) ETHER	ug/l	1.1 U	1.10	0.200	1.100
SVOC	SW8270D	<del>i</del>	BIS(2-ETHYLHEXYL) PHTHALATE	ug/l	2.7 U*	2,70	0.640	2.700
svoc	SW8270D	<del>l i</del>	Caprolactam	ug/l	1.1 U	1.10	0.430	1.100
SVOC	SW8270D	Ť	CARBAZOLE	ug/l	5.4 U	5.40	0.380	5.400
SVOC	SW8270D	<del> </del>	DIBENZOFURAN	ug/l	1.6 U	1.60	0.170	1.600
svoc	SW8270D	<del>                                     </del>	DIETHYL PHTHALATE	ug/l	5.4 U	5,40	4.600	5.400
SVOC	SW8270D	<del>i i</del>	DIMETHYL PHTHALATE	ug/l	2.7 U	2.70	0.200	2.700
SVOC	SW8270D	Ė	DI-N-BUTYL PHTHALATE	ug/l	19 *	5.40	2,000	5.400
SVOC	SW8270D	<del>i</del>	DI-N-OCTYLPHTHALATE	ug/l	5.4 U*	5,40	0.170	5.400
SVOC	SW8270D	<del> </del>	HEXACHLOROBENZENE	ug/l	1.6 U	1.60	0.270	1.600
SVOC	SW8270D	<del>i</del>	HEXACHLOROBUTADIENE	ug/l	2.2 U	2,20	0.210	2.200
SVOC	SW8270D	<del></del>	HEXACHLOROCYCLOPENTADIENE	ug/l	1.6 U	1,60	0.160	1.600
SVOC	SW8270D	Ť	HEXACHLOROETHANE	ug/l	2.2 U	2.20	0.180	2.200
SVOC	SW8270D	Ť	ISOPHORONE	ug/l	1.6 U	1.60	0.160	1.600
svoc	SW8270D	T	NITROBENZENE	ug/l	1.6 U	1.60	0.220	1.600
SVOC	SW8270D	<del>                                     </del>	N-NITROSODI-N-PROPYLAMINE	ug/l	2.7 U	2.70	0.260	2.700
SVOC	SW8270D	Ť	N-NITROSODIPHENYLAMINE	ug/l	1.6 U	1.60	0.360	1.600
svoc	SW8270D	+ +	PENTACHLOROPHENOL	ug/l	2.7 U	2.70	1.000	2.700
svoc	SW8270D	<del>                                     </del>	PHENOL	ug/l	1.6 U	1.60	0.150	1.600
SVOC	SW8270DSIM	<del>'</del> -	2-METHYLNAPHTHALENE	ug/l	0.073	0.05	0.016	0.050
SVOC	SW8270DSIM	T	ACENAPHTHENE	ug/l	0.075 U 20.0	0.05	0.019	0.050
SVOC	SW8270DSIM	Ť	ACENAPHTHYLENE	ug/l	0.05 U	0,05	0.015	0.050
SVOC	SW8270DSIM	<del>                                     </del>	ANTHRACENE	ug/l	0.05 U	0.05	0.013	0.050
SVOC	SW8270DSIM	<del>                                     </del>	BENZO(A)ANTHRACENE	ug/l	0.05 UF2	0.05	0.011	0.050
SVOC	SW8270DSIM	Ť	BENZO(A)PYRENE	ug/l	0.05 U	0.05	0.004	0.050
svoc	SW8270DSIM	<del>                                     </del>	BENZO(B)FLUORANTHENE	ug/l	0.0S UF2	0.05	0.004	0.050
SVOC	SW8270DSIM	Ť	BENZO(G,H,I)PERYLENE	ug/l	0.05 U	0.05	0.007	0.050
SVOC	SW8270DSIM	T	BENZO(K)FLUORANTHENE	ug/l	0.05 U	0.05	0.008	0.050
SVOC	SW8270DSIM	T	CHRYSENE	ug/l	0.05 UF2	0.05	0.010	0.050
SVOC	SW8270DSIM	<del>                                     </del>	DIBENZ(A,H)ANTHRACENE	ug/l	0.05 U	0.05	0.004	0.050
SVOC	SW8270DSIM	<del>'</del>	FLUORANTHENE	ug/l	0.05 U	0.05	0.013	0.050
SVOC	SW8270DSIM	<del>  '</del>	FLUORENE	ug/l	0.05 U	0.05	0.013	0.050
SVOC	SW8270DSIM	† †	INDENO(1,2,3-C,D)PYRENE	ug/l	0.05 U	0.05	0.013	0.050
		<del>  '</del>	NAPHTHALENE	ug/l	0.039 JB	0.05	0.014	0.050
SVOC	SW8270DSIM	T	PHENANTHRENE	ug/i ug/l	0.039 JB 0.013 J	0.05	0.018	0.050
	SW8270DSIM				0.013 J 0.017 JF2F	0.05	0.012	0.050
SVOC	SW8270DSIM	T	PYRENE	ug/l	1 U	1.00	0.012	1.000
VOC	SW8260C	T	1,1,1-TRICHLOROETHANE	ug/l			•	
VOC	SW8260C	T	1,1,2,2-TETRACHLOROETHANE	ug/l	1 U	1.00	0.200	1.000
VOC	SW8260C	T	1,1,2-TRICHLORO-1,2,2-TRIFLUOROETHANE	ug/l_	10	1.00	0.210	1.000
VOC	SW8260C	T	1,1,2-TRICHLOROETHANE	ug/l	1 U	1.00	0.210	1.000
VQC	SW8260C	T	1,1-DICHLOROETHANE	ug/l	1 Ų	1.00	0.170	1.000

voc	SW8260C	Т	1,1-DICHLOROETHENE	ug/l	1 U	1.00	0.190	1.000
VOC	SW8260C	Т	1,2,3-Trichlorobenzene	ug/l	1 U	1.00	0.570	1.000
voc	SW8260C	Т	1,2,4-TRICHLOROBENZENE	ug/l	1 U	1.00	0.180	1.000
voc	SW8260C	Ť	1,2-DIBROMO-3-CHLOROPROPANE	ug/l	1 U	1.00	0.810	1.000
voc	SW8260C	Т	1,2-DIBROMOETHANE (ETHYLENE DIBROMIDE)	ug/l	1 U	1.00	0.110	1.000
voc	SW8260C	Т	1,2-DICHLOROBENZENE	ug/l	1 U	1.00	0.150	1.000
voc	SW8260C	Т	1,2-DICHLOROETHANE	ug/l	1 U	1.00	0.120	1.000
voc	SW8260C	T	1,2-DICHLOROPROPANE	ug/l	1 Ü	1.00	0.140	1.000
voc	SW8260C	Т	1,3-DICHLOROBENZENE	ug/l	1 U	1.00	0.210	1.000
voc	SW8260C	Т	1,4-DICHLOROBENZENE	ug/l	1 U	1.00	0.180	1.000
voc	SW8260C	Т	2-HEXANONE	ug/l	2 UF1	2.00	0.270	2.000
voc	SW8260C	Т	ACETONE	ug/l	5 U	5.00	0.450	5.000
voc	SW8260C	Т	BENZENE	ug/l	1 U	1.00	0.180	1.000
voc	SW8260C	Т	BROMODICHLOROMETHANE	ug/l	1 Ü	1.00	0.150	1.000
voc	SW8260C	Т	BROMOFORM	ug/l	1 U	1.00	0.150	1.000
voc	SW8260C	Т	BROMOMETHANE	ug/l	2 U	2.00	0.250	2.000
voc	SW8260C	Т	CARBON DISULFIDE	ug/l	2 U	2.00	0.220	2.000
voc	SW8260C	Т Т	CARBON TETRACHLORIDE	ug/l	1 U	1.00	0.180	1.000
voc	SW8260C	Т	CHLOROBENZENE	ug/l	10	1.00	0.190	1.000
voc	SW8260C	Т	Chlorobromomethane	ug/l	1 U	1.00	0.160	1.000
voc	SW8260C	1	CHLOROETHANE	ug/l	2 U*	2.00	0.240	2.000
voc	SW8260C	Т	CHLOROFORM	ug/l	1 U	1.00	0.150	1.000
voc	SW8260C	Т	CHLOROMETHANE	ug/l	2 U*	2.00	0.210	2.000
voc	SW8260C	Т	CIS-1,2-DICHLOROETHYLENE	ug/l	1 U	1.00	0.160	1.000
voc	SW8260C	T	CIS-1,3-DICHLOROPROPENE	ug/l	1 U	1.00	0.160	1.000
voc	SW8260C	Т	CYCLOHEXANE	ug/l	1 U	1.00	0.220	1.000
voc	SW8260C	Т	DIBROMOCHLOROMETHANE	ug/l	10	1.00	0.120	1.000
voc	SW8260C	Т	DICHLORODIFLUOROMETHANE	ug/l	1 U*	1.00	0.860	1.000
voc	SW8260C	Т	ETHYLBENZENE	ug/l	10	1.00	0.210	1.000
voc	SW8260C	T	METHYL ACETATE	ug/l	5 U	5.00	0.550	5.000
voc	SW8260C	Т	METHYL ETHYL KETONE (2-BUTANONE)	ug/l	2 U	2.00	0.760	2.000
voc	SW8260C	Т	METHYL ISOBUTYL KETONE (4-METHYL-2-PENTANONE)	ug/l	2 U	2.00	0.350	2.000
voc	SW8260C	Т	METHYLCYCLOHEXANE	ug/l	1 U	1.00	0.210	1.000
voc	SW8260C	Т	METHYLENE CHLORIDE	ug/l	5 U	5.00	0.180	5.000
voc	SW8260C	Т	STYRENE	ug/l	1 U	1.00	0.180	1.000
voc	SW8260C	Т	TERT-BUTYL METHYL ETHER	ug/l	1 U	1.00	0.110	1.000
voc	SW8260C	Т	TETRACHLOROETHYLENE(PCE)	ug/l	1υ	1.00	0.330	1.000
voc	SW8260C	Т	TOLUENE	ug/l	1υ	1.00	0.200	1.000
voc	SW8260C	Т	TRANS-1,2-DICHLOROETHENE	ug/l	10	1.00	0.190	1.000
voc	SW8260C	Т	TRANS-1,3-DICHLOROPROPENE	ug/l	1 U	1.00	0.140	1.000
voc	SW8260C	Т	TRICHLOROETHYLENE (TCE)	ug/l	1 U	1.00	0.140	1.000
voc	SW8260C	Т	TRICHLOROFLUOROMETHANE	ug/l	1 U	1.00	0.240	1.000
voc	SW8260C	<u> </u>	VINYL CHLORIDE	ug/l	2 U	2.00	0.250	2.000
voc	SW8260C	<del>                                     </del>	XYLENES, TOTAL	ug/l	2 U	2.00	0.370	2.000
voc	SW8270DSIM	T	1-METHYLNAPHTHALENE	ug/l	0.041 JF1	0.05	0.016	0.050

# Notes:

 $\mu$ g/L = micrograms per liter

mg/L - milligrams per liter

- ^ = Instrument related QC is outside acceptance limits
- \* (SVOC) = LCS or LCSD is outside acceptance limits
- \* (VOC) = Relative Percent Difference (RPD) of the lab control sample and lab control sample duplicate exceeds the control limits

B= Compound was found in the blank and sample

F1 = Matrix spike (MS) and /or matrix spike duplicate (MSD) Recovery is outside acceptance limits

F2 = MS/MSD RPD exceeds control limits due to sample size difference

J = the reported concentration is estimated

MDL = Method Detection Limit

N = normal field sample

PCB = polychlorinated biphenyl

 ${\sf QL} = {\sf Quantification\ Limit}$ 

RDL = Reporting Detection Limit

SVOC = semivolatile organic compound

U = not detected at reported concentration

VOC = volatile organic compound

# Jackson, Scott A

From:

Sisk, Lynn/MGM < Lynn. Sisk@jacobs.com>

Sent:

Friday, August 28, 2020 11:35 AM

To:

Jackson, Scott A

Cc:

Powers, Martin/SEA; Mehigh, Kurt/DET; Cesarz, Scott/DET; Martin, J.P./MGM;

Brockington, Shawonda (S)

Subject:

Updated NPDES forms for DC Alabama NPDES permit modification request

Follow Up Flag: Flag Status: Follow up Flagged

Scott,

As you probably recall, DC Alabama, Inc. in Mt. Meigs has been preparing a NPDES permit modification request for several months and has completed revisions to EPA Form 1 and ADEM Form 187. The revisions include the following changes:

- The addition of stormwater to Outfall 004
- The addition of uncontaminated groundwater to Outfall 001
- A new process flow diagram to reflect the changes listed above
- Addition of the new DC Alabama Site Leader, Meredith Bruick
- New corporate officers

I will drop the signed forms off at the front desk at ADEM's main office on Coliseum Blvd. this afternoon.

Thanks. Let me know if you have questions as you review the information. Have a good weekend.

Lynn Sisk, P.E. Jacobs Technologist | BIAF 334.215.9060 334.467.6284 mobile 334.273.7504 fax Lynn.Sisk@jacobs.com

www.jacobs.com

NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.

#### **CH2M HILL**

4121 Carmichael Rd. Suite 400 Montgomery, AL 36106

# **CH2MHILL**

Scott Jackson Water Division Industrial Permitting RECEIVED
AUG 28 2000
ADEM FRONT

# ALABAMA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT (ADEM) NPDES INDIVIDUAL PERMIT APPLICATION SUPPLEMENTARY INFORMATION FOR INDUSTRIAL FACILITIES

Instructions: This form should be used to submit the required supplementary information for an application for an NPDES individual permit for industrial facilities. The completed application should be submitted to ADEM in duplicate. If insufficient space is available to address any item, please continue on an attached sheet of paper. Please mark "N/A" in the appropriate box when an item is not applicable to the applicant. Please type or print legibly in blue or black ink. Mail the completed application to:

		ADEM-Water Division Industrial Section P O Box 301463 Montgomery, AL 36130-1463		AUG 2 8 2020
	PU	RPOSE OF THIS APPLICATION	ON	IND / MUN BRANC
	Initial Permit Application for New Facility*	☐ Initial Permit Application		The state of the s
	Modification of Existing Permit Revocation & Reissuance of Existing Permit	<ul> <li>Reissuance of Existing F</li> <li>* An application for participation is submitted to allow permittee to el</li> </ul>	n the ADEM's Electronic	Environmental (E2) Reporting must b
SE	CTION A - GENERAL INFORMATION	and the union permittee to ex-	cenomeany anomin repor	is as required.
1.	Facility Name: DC Alabama, Inc.			
2.	NPDES Permit Number: AL_0083763	(not applicable if initial permit	application)	
3.	SID Permit Number (if applicable): IU			
4.	NPDES General Permit Number (if applicable):	ALG		
5.	Facility Location (Front Gate): Latitude: 32.3959	42 Longitud	e:86.072600	
7.	Responsible Official (as described on the last pa	age of this application):		
	Name: Meredith Bruick	Title: Site Leade	r	
	Address: 1940 Ohio Ferro Road			
	City: Mount Meigs	State: Alabama		Zip: <u>36057</u>
	Phone Number: <u>334-270-3737</u>	Email Address: MRBruick	@dow.com	
8.	Designated Discharge Monitoring Report (DMR)	Contact:		
	Name: Shawonda Brockington	Title: Site EHS D	elivery Leader	
	Phone Number: <u>334-270-3609</u>	Email Address: SBrocking	ton@dow.com	
9.	Type of Business Entity:			
	□ Corporation    □ General Partnership    □     □ Other (Please Specify)	Limited Partnership  Lim	ited Liability Compar	ny Sole Proprietorship
10.	Complete this section if the Applicant's business	entity is a Corporation		
	a) Location of Incorporation:			
	Address: 1940 Ohio Ferro Road			
	City: Mount Meigs County: Mo	ntgomery State: A	labama	Zip: 36057
	b) Parent Corporation of Applicant:			
	Name: The Dow Chemical Corporation			
	Address: 2040 Dow Center			
	City: Midland	State: Michigan		Zin: 48647

Name: Not Applicable								
Address:	- <del></del>							
City:	Sta	te:	Zip:					
d) Corporate Officers:								
Name: Scott Niswonger, Presider	nt							
Address: P.O. Box 68								
City: Mount Meigs	Sta	te: Alabama	Zip: <u>36057</u>					
Name: John Tiemey, Secretary								
Address: P.O. Box 68								
City: Mount Meigs	Star	te:_Alabama	Zip; <u>36057</u>					
e) Agent designated by the c	corporation for purposes of se	ervice:						
Name: Meredith Bruick	Name: Meredith Bruick							
Address: P.O. Box 68								
City: Mount Meigs	Stat	te: Alabama	Zip: _36057					
If the Applicant's business entity is a Partnership, please list the general partners.								
Name: Not Applicable								
Address:								
	City: State: Zip: City: State: Zip:							
If the Applicant's business entity is a Proprietorship, please enter the proprietor's information.  Name: Not Applicable								
Address:			7:					
<ol> <li>Identify all Administrative Compiler any, against the Applicant, it</li> </ol>	City: State: Zip: Zip: Identify all Administrative Complaints, Notices of Violation, Directives, Administrative Orders, or Litigation concerning water pollu if any, against the Applicant, its parent corporation or subsidiary corporations within the State of Alabama within the past five y (attach additional sheets if necessary):							
Facility Name	Permit Number	Type of Action	Date of Action					
DC Alabama, Inc.	ALG120051	Consent Order	10/30/2018					
DC Alabama, Inc.	ALG120051	Notice of Violation	3/12/2018					
		•						

## SECTION B - BUSINESS ACTIVITY

If your facility conducts or will be conducting any of the processes listed below (regardless of whether they generate wastewater, waste sludge, or hazardous waste), place a check beside the category of business activity (check all that apply):

	Indust	rial C	ategories	
	Aluminum Forming		Metal Molding	and Casting
	Asbestos Manufacturing		Metal Products	
	Battery Manufacturing		Nonferrous Me	tals Forming
	Can Making		Nonferrous Me	tals Manufacturing
	Canned and Preserved Fruit and Vegetables		Oil and Gas Ex	traction
	Canned and Preserved Seafood		Organic Chemi	cals Manufacturing
	Cement Manufacturing		Paint and Ink F	ormulating
	Centralized Waste Treatment		Paving and Ro	ofing Manufacturing
	Carbon Black		Pesticides Man	ufacturing
	Coal Mining		Petroleum Refi	ning
	Coil Coating		Phosphate Mar	nufacturing
	Copper Forming		Photographic	
	Electric and Electronic Components Manufacturing		Pharmaceutica	I
	Electroplating		Plastic & Synth	etic Materials
	Explosives Manufacturing		Plastics Proces	ssing Manufacturing
	Feedlots		Porcelain Enan	nel
	Ferroalloy Manufacturing		Pulp, Paper, an	nd Fiberboard Manufacturing
	Fertilizer Manufacturing		Rubber	
	Foundries (Metal Molding and Casting)		Soap and Dete	rgent Manufacturing
	Glass Manufacturing		Steam and Elec	ctric
	Grain Mills		Sugar Processi	ng
	Gum and Wood Chemicals Manufacturing		Textile Mills	
	Inorganic Chemicals		Timber Product	s
	Iron and Steel		Transportation	Equipment Cleaning
	Leather Tanning and Finishing		Waste Combus	tion
	Metal Finishing	X	Other (specify)	SIC 3313, Electrometallurical, except steel
	Meat Products			
acility w ese facil	Meat Products  with processes inclusive in these business areas may be littles are termed "categorical users".	oe cov		
CTION	C - WASTEWATER DISCHARGE INFORMATION			
Do y	ou share an outfall with another facility? X Yes	No	(If no, continue to	o C.2)
	each shared outfall, provide the following:			
Fore	nlicant's			Miles and the second and the stand
A	pplicant's Name of Other Permittee/Facility		NPDES Pormit No	Where is sample collected
A	outfall No.	AI	NPDES Permit No. .0082431	by Applicant?  After final treatment

2.	<ol><li>Do you have, or plan to have, automatic sampling equipment or co</li></ol>	ntinuous wastewater flow metering equipment at this facility?
	Current: Flow Metering	Yes No No
	Sampling Equipment	Yes No N/A
	Planned: Flow Metering	Yes No NA
	Sampling Equipment	Yes □ No ☑ N/A
	If so, please attach a schematic diagram of the sewer system indicathe equipment below:	ating the present or future location of this equipment and describe
	Flow rate through the treatment system is logged using a flow totalizer. A discharge. See the attached flow diagram.	24-hour composite sampler is installed after final treatment and prior to
3.	Are any process changes or expansions planned during the next th	ree years that could alter wastewater volumes or characteristics?
	✓ Yes    ✓ No (If no, continue to C.4)	
	Briefly describe these changes and their anticipated effects on the	wastewater volume and characteristics:
	After the slurry pond is dewatered and closed in place, the process waste	water discharge will cease. The only discharges from the facility at that
	time will be stormwater and non-contact cooling water.	valor discribings will occase. The only discribinges from the lability at that
,	4. List the trade page and chamical composition of all bioxides and	
4.	The same of the sa	
	Trade Name	Chemical Composition
	Acutrace 3014	See attached biocide sheet. (Applicable to DSN003 only)
	Acubrome Liquid	See attached biocide sheet. (Applicable to DSN003 only)
	Sodium Hypochlorite	See attached biocide sheet. (Applicable to DSN003 only)
	<ol> <li>96-hour median tolerance limit data for organisms representat ultimately reach,</li> <li>quantities to be used,</li> <li>frequencies of use,</li> <li>proposed discharge concentrations, and</li> <li>EPA registration number, if applicable</li> </ol>	ve of the biota of the waterway into which the discharge will
SE	SECTION D - WATER SUPPLY	
Wa	Water Sources (check as many as are applicable):	
	Private Well	☐ Surface Water
	Municipal Water Utility (Specify City):	Other (Specify):
	IF MORE THAN ONE WELL OR SURFACE INTAKE, PROVIDE I	DATA FOR FACH ON AN ATTACHMENT
	City: 0.002 MGD* Well: 0.72 MGD* Well Depth:	533 Ft. Latitude: 32.39105 Longitude: -86.07525
	Surface Intake Volume:MGD*	n Relation to Bottom:Ft.
	Intake Elevation:Ft. Latitude: Lo	ngitude:
	Name of Surface Water Source:	
	* MGD - Million Gallons per Day	

ADEM Form 187 m6 04/2020 Page 4 of 8

20011	ng Water Intake Structure Information
	plete D.1 and D.2 if your water supply is provided by an outside source and not by an onsite water intake structure? (e.g., ler industry, municipality, etc…)
1.	Does the provider of your source water operate a surface water intake? ■ Yes ☐ No (If yes, continue, if no, go to Section E.)
	a) Name of Provider: Montgomery Water Works and Sanitary Sewer Board b) Location of Provider: Montgomery, AL (Tallapoosa River)
	a) Name of Provider: Montgomery, AL (Taliapoosa River)  b) Location of Provider: Montgomery, AL (Taliapoosa River)  c) Latitude: 32.4401 Longitude: -86.1955
2.	Is the provider a public water system (defined as a system which provides water to the public for human consumption or which provides only <u>treated</u> water, not raw water)?   Yes  No (If yes, go to Section E, if no, continue.)
	to be completed if you have a cooling water intake structure or the provider of your water supply uses an intake structure loes not treat the raw water.
3	Is any water withdrawn from the source water used for cooling?   Yes   No
4	Using the average monthly measurements over any 12-month period, approximately what percentage of water withdrawn is used exclusively for cooling purposes?%
5	Does the cooling water consist of treated effluent that would otherwise be discharged?
6	a. Is the cooling water used in a once-through cooling system?
	b. Is the cooling water used in a closed cycle cooling system? ☐ Yes ☐ No
7	When was the intake installed?
8	What is the maximum intake volume?(maximum pumping capacity in gallons per day)
9	What is the average intake volume? (average intake pump rate in gallons per day average in any 30-day period)
1	0. What is the actual intake flow (AIF) as defined in 40 CFR §125.92(a)?MGD
1	1. How is the intake operated? (e.g., continuously, intermittently, batch)
1	2. What is the mesh size of the screen on your intake?
1	3. What is the intake screen flow-through area?
1	4. What is the through-screen design intake flow velocity?ft/sec
1	5. What is the through-screen actual velocity (in ft/sec)?ft/sec
1	6. What is the mechanism for cleaning the screen? (e.g., does it rotate for cleaning)
1	7. Do you have any additional fish detraction technology on your intake?   Yes No
1	8. Have there been any studies to determine the impact of the intake on aquatic organisms?   Yes No (If yes, please provide.)
19	9. Attach a site map showing the location of the water intake in relation to the facility, shoreline, water depth, etc.
	2. Only 5 6 6 7 7 8 9 11 11 11 11 11 11 11 11 11 11 11 11 1

ADEM Form 187 m6 04/2020 Page 5 of 8

CECTION	E MACTE	CTODACE	AND DICDOCAL	INFORMATION
SECTION	E - WASIE	STURAGE	AND DISPUSAL	INFURMATION

Provide a description of the location of all sites involved in the storage of solids or liquids that could be accidentally discharged to a water
of the state, either directly or indirectly via such avenues as storm water drainage, municipal wastewater systems, etc., which are located
at the facility for which the NPDES application is being made. Where possible, the location should be noted on a map and included with
this application:

Description of Waste Description of Storage Lo				ocation				
	Silica fume generated during the production of silica metal 35 acre silica fume slurry pond (Lat. 32.396)				34478)			
SEC	TION	F - COASTAL ZONE INFORMATION						
	Is the	e discharge(s) located within the 10-foot elevation contour	and within the limits of Mobile or Baldwin County? [	Yes	⊠ No			
	If yes	s, complete items F.1 – F.12:						
	1	Does the project require new construction?		Yes	<u>No</u>			
	1. 2.	Will the project be a source of new air emissions?						
	3.	Does the project involve dredging and/or filling of a wetla		_				
	Э.	If Yes, has the Corps of Engineers (COE) permit been re						
	4.	Does the project involve wetlands and/or submersed gra	assbeds?					
	5.	Are oyster reefs located near the project site?			П			
		If Yes, include a map showing project and discharge local		_	_			
	6.	Does the project involve the site development, construct ADEM Admin. Code r. 335-8-102(bb)?						
	7.	Does the project involve mitigation of shoreline or coasta	al area erosion?					
	8.	Does the project involve construction on beaches or dun	e areas?					
	9.	Will the project interfere with public access to coastal wa	iters?					
	10.	Does the project lie within the 100-year floodplain?						
	11.	Does the project involve the registration, sale, use, or ap	pplication of pesticides?					
	12.	Does the project propose or require construction of a ne pump more than 50 gallons per day (GPD)?	w well or to alter an existing groundwater well to					
		If yes, has the applicable permit for groundwater recover	y or for groundwater well installation been					

#### SECTION G - ANTI-DEGRADATION EVALUATION

In accordance with 40 CFR §131.12 and the ADEM Admin. Code r. 335-6-10-.04 for anti-degradation, the following information must be provided, if applicable. It is the applicant's responsibility to demonstrate the social and economic importance of the proposed activity. If further information is required to make this demonstration, attach additional sheets to the application.

- Is this a new or increased discharge that began after April 3, 1991?
   Yes ☐ No If yes, complete G.2 below. If no, go to Section H.
- 2. Has an Anti-Degradation Analysis been previously conducted and submitted to the Department for the new or increased discharge referenced in G.1? 

  Yes 
  No

If yes, do not complete this section. If no, and the discharge is to a Tier II waterbody as defined in ADEM Admin. Code r. 335-6-10-.12(4), complete G.2.A – G.2.F below and ADEM Forms 311 and 313 (attached). ADEM Form 313 must be provided for each alternative considered technically viable.

ADEM Form 187 m6 04/2020 Page 6 of 8

	What environmental or public health problem will the discharger be correcting?
	How much will the discharger be increasing employment (at its existing facility or as the result of locating a new facility)?
The same of the sa	How much reduction in employment will the discharger be avoiding?
	How much additional state or local taxes will the discharger be paying?
	What public service to the community will the discharger be providing?
	What economic or social benefit will the discharger be providing to the community?

#### SE

All A http://www.adem.alabama.gov/programs/water/waterforms.cnt . The EPA application forms must be submitted in duplicate as follows:

- 1. All applicants must submit Form 1.
- 2. Applicants for existing industrial facilities (including manufacturing facilities, commercial facilities, mining activities, and silvicultural activities) which discharge process wastewater must submit Form 2C.
- 3. Applicants for new industrial facilities which propose to discharge process wastewater must submit Form 2D.
- 4. Applicants for new and existing industrial facilities which discharge only non-process wastewater (i.e., non-contact cooling water and/or sanitary wastewater) must submit Form 2E.
- Applicants for new and existing facilities whose discharge is composed entirely of storm water associated with industrial activity must submit Form 2F, unless exempted by § 122.26(c)(1)(ii). If the discharge is composed of storm water and nonstorm water, the applicant must also submit Forms 2C, 2D, and/or 2E, as appropriate (in addition to Form 2F).

#### SECTION I - ENGINEERING REPORT/BMP PLAN REQUIREMENTS

SECTION	1	DECEN	/INIC	MAIA"	FEDG
SECTION.	-	REGEN	CIPIL.	WWA	IERS

Outfall No.	Receiving Water(s)	303(d) Se	egment?	Included in TMDL?*		
001	Tributary to Miller Creek (stormwater, uncontaminated groundwater)	☐ Yes	⊠No	☐ Yes	⊠No	
002	Tributary to Miller Creek (process water)	Yes	No	☐ Yes	⊠No	
003	Tributary to Miller Creek (non-contact cooling water)	Yes	⊠No	Yes	⊠No	
004	Tallapoosa River (process water and stormwater)	☐ Yes	⊠No	Yes	⊠No	
		☐ Yes	□No	Yes	□No	

\*If a TMDL Compliance Schedule is requested, the following should be attached as supporting documentation:

- (1) Justification for the requested Compliance Schedule (e.g. time for design and installation of control equipment, etc.);
- (2) Monitoring results for the pollutant(s) of concern which have not previously been submitted to the Department (sample collection dates, analytical results (mass and concentration), methods utilized, MDL/ML, etc. should be submitted as available);
- (3) Requested interim limitations, if applicable;
- (4) Date of final compliance with the TMDL limitations; and,
- (5) Any other additional information available to support requested compliance schedule.

#### SECTION K - APPLICATION CERTIFICATION

The information contained in this form must be certified by a responsible official as defined in ADEM Administrative Code r. 335-6-6-.09 "signatories to permit applications and reports" (see below).

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations."

Signature of Responsible Official:	Mhi	Date Signed:_	8	28	2020
Name: Meredith Bruick	Title: Site Leade	er			
If the Responsible Official signing this application	n is <u>not</u> identified in Section A.7, provide th	he following informa	tion:		
Mailing Address:					
City:	State:		Zi	p:	
Phone Number:	Email Address:				

#### 335-6-6-.09 SIGNATORIES TO PERMIT APPLICATIONS AND REPORTS.

- (1) The application for an NPDES permit shall be signed by a responsible official, as indicated below:
  - (a) In the case of a corporation, by a principal executive officer of at least the level of vice president, or a manager assigned or delegated in accordance with corporate procedures, with such delegation submitted in writing if required by the Department, who is responsible for manufacturing, production, or operating facilities and is authorized to make management decisions which govern the operation of the regulated facility;
  - (b) In the case of a partnership, by a general partner;
  - (c) In the case of a sole proprietorship, by the proprietor; or
  - (d) In the case of a municipal, state, federal, or other public entity, by either a principal executive officer, or ranking elected official.

ADEM Form 187 m6 04/2020 Page 8 of 8

EPA Identification Number		ition Number	NPDES Permit Number		Fa	cility Name	Form Approved 03/05/19			
			AL008376	53	DC A	labama, Inc.	OMB No. 2040-0004			
Form 1	.9	EPA	U.S. Environmental Protection Agency Application for NPDES Permit to Discharge Wastewater							
NPDES	-				GENERAL	INFORMATIO	ON			
SECTIO	N 1. AC	TIVITIES REQUIRI	NG AN NPDES PE	RMIT (40 CF	R 122.21(f) an	d (f)(1))				
	1.1		Required to Subm							
	1.1.1		w or existing publi		1.1.2	Is the facility a	new or existing treatment works			
	1.1.1	treatment works?		1.1.2	treating dome					
			es, STOP. Do NOT complete	✓ No		If yes, STOP. I				
		Form 1. Complete	e Form ZA.			complete Form Form 2S.	1. Complete			
	1.2	Applicants Requ	ired to Submit Fo	rm 1		TOTAL ZO.				
	1.2.1		ncentrated anima		1.2.2	Is the facility an	existing manufacturing,			
E		operation or a co	oncentrated aquat			commercial, mi	ning, or silvicultural facility that is			
S		production facil					harging process wastewater?			
PDE			omplete Form 1 od Form 2B.	✓ No			Complete Form No			
Z	1.2.3		w manufacturing, o	commercial,	1.2.4	-	new or existing manufacturing,			
ng a		mining, or silvicul	tural facility that ha			commercial, mining, or silvicultural facility that				
Ē		commenced to discharge?  ☐ Yes → Complete Form 1	_	C No		-	ly nonprocess wastewater?			
8			omplete Form 1	✓ No			Complete Form  No 1 and Form 2E.			
Activities Requiring an NPDES Permit	1.2.5		w or existing facil	ity whose		internation control 42 per s				
ctiv			posed entirely of st							
⋖			industrial activity posed of both stor							
		non-stormwater		illiffator and						
			mplete Form 1	☐ No						
		1	d Form 2F							
			less exempted by CFR							
		12	2.26(b)(14)(x) or							
		A STATE OF THE PARTY OF THE PAR	(15).							
SECTIO	A STATE OF THE PARTY OF THE PAR	ME, MAILING ADD	RESS, AND LOCA	TION (40 CF	R 122.21(f)(2)		elim ta the wat Mainte at all			
	2.1	Facility Name			<b>.</b>					
		DC Alabama, Inc.								
6	2.2	EPA Identification	on Number							
cati										
d Lo		AL0083763								
an,	2.3	Facility Contact								
ress		Name (first and la	,	Title			Phone number			
Add		Shawonda Brockir	ngton	EHS Site Lea	der		(334) 270-3609			
D D		Email address								
Mail	1.3	SBrockington@do			(Management of the Control of the Co					
Name, Mailing Address, and Location	2.4	Facility Mailing	Address							
Nan		Street or P.O. box								
		1940 Ohio Ferro R	oad			-				
		City or town		State	ECL	TWE R	ZIP code			
		Mount Meigs		AL (	565		36057			


Alig 2 8 2020 U

EPA Identification		ation Number	NPDES Permit Nu AL0083763		Facility Name DC Alabama, Inc.	Form Approved 03/05/ OMB No. 2040-00		
, D	2.5	Facility Location						
Addres		Street, route number, or other specific identifier 1940 Ohio Ferro Road						
Name, Mailing Address, and Location Continued		County name Montgomery	Co	ounty code (if k	nown)			
Name, and Lo		City or town Mount Meigs	Sta AL	ate		ZIP code 36057		
SECTIO	N 3. SIC	AND NAICS CODE	S (40 CFR 122.21(	f)(3))				
	3.1	SIC Cod	e(s) De	scription (opt	ional)			
		3313	Elec	ctrometallurgi	cal Products, except steel			
Codes					70 1140			
SIC and NAICS Codes	3.2	NAICS Co	de(s) De	escription (opt	ional)			
SIC and						T. HANSIL		
						0.00		
SECTIO	4.1	Name of Operator		.21(1)(4))				
					A TOTAL PARTY MANAGEMENT			
-	4.2	DC Alabama, Inc.	to disa tensa di di alaa		1.5 1.0 1.11			
Operator Information	4.2	Is the name you listed in Item 4.1 also the owner?  Yes No						
r	4.3	Operator Status						
Operato		☐ Public—federa ☐ Private	Oth	olic—state er (specify)	Othe	r public (specify)		
	4.4	Phone Number of	Operator					
		(334) 270-3737						
nation	4.5	Operator Address Street or P.O. Box 1940 Ohio Ferro Ro			194-70			
Operator Information Continued	l bi	City or town Mount Meigs		ate		ZIP code 36057		
Operat		Email address of o				1,		
SECTIO	N 5. INC	DIAN LAND (40 CFR	122.21(f)(5))	Sakaley.				
	5.1		ed on Indian Land?					
Indian		☐ Yes ☑ N	0					


EPA Form 3510-1 (revised 3-19) Page 2

EP.	EPA Identification Number NPDES Permit N AL008376		DC Alabama, Inc.			Form Approved 03/05/1 OMB No. 2040-000			
SECTIO	SECTION 6. EXISTING ENVIRONMENTAL PERMITS (					TO SERVICE STATE OF THE SERVICE STATE STATE OF THE SERVICE STATE STATE STATE OF THE SERVICE STATE S			
	6.1						resno	onding permit number for each)	
Existing Environmental Permits	0.1	NPDES (discharges to surface water) AL0083763, ALR10BEN2				dous wastes)		UIC (underground injection of fluids)	
ing Environ Permits		PSD (air ei		☐ Nonatta	ainmen	t program (CAA)		NESHAPs (CAA)	
			mping (MPRSA)	☐ Dredge	or fill	CWA Section 404)	Ø	Other (specify) MSOP 209-0026	
SECTIO	N 7. MA	P (40 CFR 122.2	1(f)(7))			<b>国际区型建筑</b>			
Мар	7.1	specific require		p containing	all req	uired information to this	s appli	ication? (See instructions for	
		☑ Yes □	No ☐ CAFO—Not	t Applicable (	See re	quirements in Form 2E	3.)		
SECTIO	N 8. NA	URE OF BUSIN	ESS (40 CFR 122.21)	f)(8))		THE WARREN	James Company		
Nature of Business	8.1	The facility prod (fume), which is process include	s used as a strengthen es melting raw materia	ed in chemic ner and filler l als (quartz roc	by the ck, coa	concrete and refractor I, charcoal, and wood	y indu hips)	lity also produces micro silica istries. The manufacturing in an electric arc furnace to being packaged for shipping.	
SECTIO	The second second		NTAKE STRUCTURE	S (40 CFR 1	22.21(	f)(9))	Wolf		
	9.1 Does your facility use cooling water?								
res er		☑ Yes □	No → SKIP to Item	10.1.					
Cooling Water Intake Structures	THE DES permitting authority to determine what specific information needs to be submitted and when.)							R 122.21(r). Consult with your	
SECTIO	N 10 VA	RIANCE REQUE	ESTS (40 CFR 122.21	(f)(10))	A PARTY		27/67	White State of the	
	10.1	Do you intend to	o request or renew on	e or more of		etermine what informa	tion ne	R 122.21(m)? (Check all that eeds to be submitted and	
e Requ		Fundami Section 3	entally different factors 301(n))	s (CWA		Water quality related 302(b)(2))	efflue	nt limitations (CWA Section	
Variance Requests		Section 3	ventional pollutants (C 301(c) and (g))	CWA		Thermal discharges (	CWA	Section 316(a))	
		✓ Not appl	icable						

EPA Identification Number			ei	AL0083763			DC Alabama, Inc.		OMB No. 2040-0004	
SECTIO	N 11 C	JECKI IS	CT AND							
SECTION	11.1	In Coli For ea	umn 1 bel ach sectio	n, specify in Colum	ons of Form 1 tha	at you ha	ve co	mpleted and are su	bmitting with your application. It the permitting authority. Note	
		that not all applicants are required to provide attachments.  Column 1				Column 2				
		<b>V</b>	Section 1: Activities Requiring an NPDES Permit			Permit		w/ attachments		
		V	Section 2: Name, Mailing Address, and Location			cation		w/ attachments		
		<b>7</b>	Section	3: SIC Codes				w/ attachments		
		<b>V</b>	Section 4: Operator Information					w/ attachments		
		Ø	Section	5: Indian Land				w/ attachments		
ent		<b>V</b>	Section	6: Existing Enviro	nmental Permits			w/ attachments		
Checklist and Certification Statement		Ø	Section	7: Map			<b>√</b>	w/ topographic map	w/ additional attachments	
tion S		Ø	Section	8: Nature of Busin	ess			w/ attachments		
rtifica		Ø	Section	9: Cooling Water	ntake Structures			w/ attachments		
nd Ce		V	Section	10: Variance Requ	uests			w/ attachments		
dist ar		<b>7</b>	Section	11: Checklist and	Certification State	ement		w/ attachments		
heck	11.2	Certification Statement								
รั	I certify under penalty of law that this document and all a in accordance with a system designed to assure that qui information submitted. Based on my inquiry of the perso directly responsible for gathering the information, the infibelief, true, accurate, and complete. I am aware that the including the possibility of fine and imprisonment for kno							sonnel properly gai ons who manage the submitted is, to the nificant penalties fo	ther and evaluate the e system, or those persons best of my knowledge and	
		Name (print or type first and last name)				Official title				
		Meredi	ith Bruick				Site Le	eader		
		Signature				Date signed 8 - 27 - 2020				







May 6, 2019

The Dow Chemical Company 1940 Ohio Ferro Road Mt. Meigs, AL 36057

Alabama Department of Environmental Management (ADEM) Water Division - Industrial Section P.O. Box 301463 Montgomery, AL 36130-1463

R# 19-48869

Minor NPDES Permit Modification - Dow Corning Alabama Inc., Permit No. ALG0083763

Dear Mr. Ramsey,

DC Alabama, Inc. is requesting that NPDES permit number AL0083763 be modified to include the discharge of stormwater at outfall DSN004 to the Tallapoosa River. This change reflects the collection and treatment of stormwater runoff from the facility's industrial process area (approximately 10 acres) and routing of the treated stormwater to outfall DSN004 (Tallapoosa River).

Please find attached EPA Form 1, ADEM Form 187, a revised flow diagram, EPA Form 2C, and EPA Form 2F. The payment receipt in the amount of \$3,120 was made via the ADEM online payment system and is also enclosed for a Minor NPDES Permit Modification per ADEM Fee Schedule D – Water Permits.

If you have questions about any of the attachments or need additional information, please contact Shawonda Brockington at (334) 270-3609.

W- Derman

Sincerely,

Tim Dermon

DC Alabama Site Leader

Attachments

# ALABAMA DEPARTMENT OF ENVIRONMENTAL MANAGEMENT (ADEM) NPDES INDIVIDUAL PERMIT APPLICATION SUPPLEMENTARY INFORMATION FOR INDUSTRIAL FACILITIES

Instructions: This form should be used to submit the required supplementary information for an application for an NPDES individual permit for industrial facilities. The completed application should be submitted to ADEM in duplicate. If insufficient space is available to address any item, please continue on an attached sheet of paper. Please mark "N/A" in the appropriate box when an item is not applicable to the applicant application to:

application to: ADEM-Water Division Industrial Section P O Box 301463 Montgomery, AL 36130-1463 **PURPOSE OF THIS APPLICATION** ☐ Initial Permit Application for New Facility\* ☐ Initial Permit Application for Existing Facility\* Modification of Existing Permit ☐ Reissuance of Existing Permit Revocation & Reissuance of Existing Permit An application for participation in the ADEM's Electronic Environmental (E2) Reporting must be submitted to allow permittee to electronically submit reports as required. SECTION A - GENERAL INFORMATION DC Alabama, Inc. 1. Facility Name: DC Alabama, Inc. Is the operator identified in A.1.a, the owner of the facility? Yes □ No If no, provide name and address of the operator and submit information indicating the operator's scope of responsibility for the facility. NPDES Permit Number: AL 0 0 8 3 7 6 3 (not applicable if initial permit application) SID Permit Number (if applicable): 1U \_\_\_ - \_\_ - \_\_ - \_\_ \_ \_ \_\_\_ 3. Facility Physical Location: (Attach a map with location marked; street, route no. or other specific identifier) Street: 1940 Ohio Ferro Road \_<sub>County:</sub>\_Montgomery <sub>\_State:</sub> Alabama <sub>Zip:</sub> 36057 City: Mount Meigs Longitude: (-86) (04) (21.36) Facility Location (Front Gate): Latitude: (32) (23) (45.39) Facility Mailing Address: 1940 Ohio Ferro Road County: Montgomery <sub>State:</sub> Alabama Zip: 36057 City: Mount Meigs Responsible Official (as described on the last page of this application): Name and Title: Tim Dermon, Site Leader Address: 1940 Ohio Ferro Road <sub>\_State:</sub> Alabama <sub>Zip:</sub> 36057 City: Mount Meigs Phone Number: 334-270-3737 Email Address: tim.dermon@dow.com Designated Facility Contact: Name and Title: Shawonda Brockington, Site EHS Delivery Leader Phone Number: 334-270-3609 Email Address: sbrockington@dow.com

9.	Designated Discharge Monitoring Report (DMR) Contact:
	Name and Title: Shawonda Brockington, Site EHS Delivery Leader
	Phone Number: 334-270-3609 Email Address: sbrockington@dow.com
10.	Type of Business Entity:
	■ Corporation 🔲 General Partnership 🔲 Limited Partnership 🔲 Limited Liability Company 🔲 Sole Proprietorship
	Other (Please Specify)
11.	Complete this section if the Applicant's business entity is a Corporation
	a) <u>Location of Incorporation</u> :
	Address: 1940 Ohio Ferro Road
	City: Mount Meigs County: Montgomery State: Alabama Zip: 36057
	b) Parent Corporation of Applicant:
	Name: The Dow Chemical Corporation
	Address: 2040 Dow Center
	City: Midland State: Michigan Zip: 48647
	c) Subsidiary Corporation(s) of Applicant:
	Not Applicable
	Address:
	City:
	d) Corporate Officers:
	Name: David H. Ott, President
	Address: P.O. Box 68
	City: Mount Meigs State: Alabama Zip: 36057
	Name: Johnathan P. Wendt, Secretary
	Address: P.O. Box 68
	City: Mount Meigs State: Alabama Zip: 36057
	a) Agent designated by the corporation for purposes of service:
	Name: Tim Dermon
	Address: P.O. Box 68
	City: Mount Meigs State: Alabama Zip: 36057
12.	If the Applicant's business entity is a Partnership, please list the general partners.
	Name: Not Applicable Name:
	Address: Address:
	City:State:Zip: City:State:Zip:

Name: Not Applicable Address:					
					Zip:
Permit numbers for Applicant's pre Permits presently held by the Appli	eviously iss	ued NPDES P	ermits and identification	of any oth	ner State of Alabama Environmenta
Permit Name		<u>Pe</u>	ermit Number		Held By
NPDES General Permit		ALG120	051	DC A	labama, Inc.
NPDES Individual Perm	it	AL00837	763	DC A	labama, Inc.
Major Source Operating	Permit	209-002	6	DC A	labama, Inc.
NPDES General Permit		ALR10B	EN2	DC A	labama, Inc.
DC Alabama, Inc.  DC Alabama, Inc.	ALG'	nit Number 120051 120051	Consent Orde  Notice of Viola	r	Date of Action 10/30/2018 03/12/2018
SECTION B – BUSINESS ACTIVITY  1. Indicate applicable Standard Industrimportance:  a. 3313  b  c  d  e  f	ial Classifi	cation (SIC) Co	des for all processes. If	more than	one applies, list in order of

☐ Aluminu		Industri	ial C	ategories	
Asbesto Battery Can Ma Canned Canned Canned Cement Centralii Carbon Coal Min Coil Coa Copper Electric Explosiv Feedlots Ferroalle Foundri Glass M Grain M Gum an Inorgani Iron and Leather Metal Fi Meat Professe facilities are seed as a brief des The facility put which is used	and Preserved Fru and Preserved Sea Manufacturing Zed Waste Treatmed Black ning atting Forming and Electronic Completing Wes Manufacturing of Manufacturing of Manufacturing of Manufacturing of Metal Molding allanufacturing ills di Wood Chemicals in Steel Tanning and Finish nishing oducts of Electronic Manufacturing and Finish oducts of Electronic Manufacturing and	it and Vegetables afood ent  inponents Manufacturing and Casting)  Manufacturing ang ese business areas may be users" and should skip to ations at this facility including atal used in chemical and er and filler by the concest (quartz rock, coal, character as ingots. The ingotand are considered Categorian and are considered Categorian and are considered Categorian.	e coving prima la lurrete rocal orica	Metal Molding and Casting Metal Products Nonferrous Metals Forming Nonferrous Metals Manufactur Oil and Gas Extraction Organic Chemicals Manufactur Paint and Ink Formulating Paving and Roofing Manufactur Pesticides Manufacturing Petroleum Refining Phosphate Manufacturing Photographic Pharmaceutical Plastic & Synthetic Materials Plastics Processing Manufactur Porcelain Enamel Pulp, Paper, and Fiberboard M Rubber Soap and Detergent Manufactur Steam and Electric Sugar Processing Textile Mills Timber Products Transportation Equipment Cleat Waste Combustion Other (specify)	ring  ring  lanufacturing  lanufacturing  aning  on (EPA) categorical standards.  ach additional sheets if necessar  lso produces micro silica (fum  ne manufacturing process  tric arc furnace to produce  kaged for shipping.  C.2 of this section.
For Non-Categ	(Figure 1), enter				w schematic should include :
For Non-Categ	(Figure 1), enter s as well as monit	oring and discharge poi	nts).		w schematic should include stimates for each discharge.]
For Non-Categ	s as well as monit	oring and discharge point  Last 12 Months (gals/day)  Highest Month Avg. Flow 288,000 - projected	nts).	[New facilities should provide ending the facilities should provide ending the facilities of Last 5 (gals/day)  Monthly Avg. Flow  504,000 - projected	w schematic should include stimates for each discharge.]  Discharge Type (batch, continuous, intermittent)

2. If your facility conducts or will be conducting any of the processes listed below (regardless of whether they generate wastewater,

if batch	discharge occurs or will oc	cur, indicate: [r	new facilities may	estimate.]			
a.	Number of batch discharg	es:	pe	er day		•	
b.	Average discharge per ba	tch:		(GPD)			
C.	Time of batch discharges	(days o	at	(hours	of day)		
		(days o	•	•	or day)		
d.	Flow rate:		gallons/m	inute			
е.	Percent of total discharge	:					
	Non-Process Discl		(gal:	? Months s/day) nth Avg. Flow	(g	ow Year of Last 5 als/day) ly Avg. Flow	
	Non-contact cooli	ng water	No discharge		No discharg	e	
wastew privately For eac	plete this Section only if rater to a water of the Stary-owned treatment works, of Yes  Categorical Users: Provide the of your processes or presponds to each process.	te. If Categoric check "Yes" in the e the wastewater coposed proces	cal wastewater is of the appropriate sp ter discharge flows sses. Using the p	discharged exclusion below and property of the control of the cont	sively via an indire roceed directly to p whichever is applicated rematic (Figure 1, 1	ct discharge to a public or	ırıt
2a.					Tvp	e of Discharge Flow	
	Regulated Process	Applicable C	ategory /	Applicable Subpa	•	continuous, intermittent)	
			<del></del> -	- 100			
2b.	Process Description	(gals/day),	2 Months (lbs/day), etc. onth Average*	(gals/day), (	Year of Last 5 lbs/day), etc. Average*	Discharge Type (batch, continuous, intermittent)	
			<u> </u>		-		
	* Reported values shou example, flow (MGD), prodischarge occurs or will occur on the occurs of the occurs or will occur on the occurs of the	oduction (pou	nds per day), etc.	•	ederal productio	n-based standard. For	
	•		p				
a.	Number of batch discharg						
b.	Average discharge per ba						
C.	Time of batch discharges	(days o	of week)	(hours	of day)	-	
d.	Flow rate:		gallons/m	ninute			
e.	Percent of total discharge	e:					

	Non categorical Process Description	(	it 12 Months gals/day) Month Avg. Flow	Highest Flow Y (gals/o Monthly Av	lay)	Discharge Type (batch, continuous, intermittent)
If batc	h discharge occurs or w	vill occur, indica	te: [new facilities ma	y estimate.]		
a.	Number of batch dis	charges:		per day		
b.	Average discharge p	er batch: _		(GPD)		
C.	Time of batch discha		ys of week)	at(hours of	day)	
d.	Flow rate:		gallons	/minute		
e.	Percent of total disch	narge:				
2d.						
		ess Discharges act cooling wat	(g:	12 Months als/day) lonth Avg. Flow	gals (gals	Year of Last 5 /day) Avg. Flow
3. I		with another fac provide the foll Name of Other P	•	No (If no, continue to NPDES Permit No. AL0082431	Where	is sample collected by Applicant? atment and before outfall
- 4. De	o you have, or plan to h	ave, automatic	sampling equipment Flow Metering Sampling Equipmen	Yes N	o ∏N/A	g equipment at this facility?
		Planned:	Flow Metering Sampling Equipmen	Yes N		
	so, please attach a sche e equipment below:	ematic diagram	of the sewer system	indicating the preser	nt or future location	of this equipment and describe
Flo fina	ow rate through the trea al treatment and prior to	tment system w discharge. Se	ill be logged using a e the attached flow o	flow totalizer. A 24- liagram.	hour composite sa	mpler will be installed after
	re any process changes ] Yes		planned during the n	ext three years that o	could alter wastewa	iter volumes or characteristics?
Br	riefly describe these cha	inges and their	anticipated effects o	n the wastewater vol	ume and character	istics:
	ter the slurry pond is de e facility at that time will					The only discharges from

2c.

Trade Name	Chemical Composition
Acutrace 3014	See attached biocide sheet
Acubrome Liquid	See attached biocide sheet
Sodium Hypochlorite	See attached biocide sheet
For each biocide and/or corrosion inhibitor used, please include the	following information:
<ol> <li>96-hour median tolerance limit data for organisms represer ultimately reach,</li> <li>quantities to be used,</li> <li>frequencies of use,</li> <li>proposed discharge concentrations, and</li> <li>EPA registration number, if applicable</li> </ol>	ntative of the biota of the waterway into which the discharge will
SECTION D – WATER SUPPLY Water Sources (check as many as are applicable):	
Private Well	☐ Surface Water
Municipal Water Utility (Specify City): Montgomery	Surface Water  Other (Specify):
•	
IF MORE THAN ONE WELL OR SURFACE INTAKE, PROVID	
City: 0.002 MGD* Well: 0.72 MGD* Well Dep	oth: 533Ft. Latitude: 32.39105 _ Longitude: -86.07525
Surface Intake Volume:MGD* Intake Elevati	ion in Relation to Bottom:Ft.
Intake Elevation:Ft. Latitude:	Longitude:
Name of Surface Water Source:	
* MGD – Million Gallons per Day	
Cooling Water Intake Structure Information	
Complete D.1 and D.2 if your water supply is provided by an ou another industry, municipality, etc)	itside source and not by an onsite water intake structure? (e.g.,
<ol> <li>Does the provider of your source water operate a surface water (If yes, continue, if no, go to Section E.)</li> </ol>	ater intake? Yes No No
a) Name of Provider: Montgomery Water Works and Sanitary Sewer B	b) Location of Provider: Montgomery, Alabama (Tallapoosa River)
c) Latitude: 32.4401 Longitude: -86.19	
	nich provides water to the public for human consumption or which o (If yes, go to Section E, if no, continue.)
Only to be completed if you have a cooling water intake structu and does not treat the raw water.	re or the provider of your water supply uses an intake structure
3. Is any water withdrawn from the source water used for cooling	ng? 🗌 Yes 🔲 No
Using the average monthly measurements over any 12-mon used exclusively for cooling purposes?%	th period, approximately what percentage of water withdrawn is
<ol> <li>Does the cooling water consist of treated effluent that would (If yes, go to Section E, if no, complete D.6 – D.17)</li> </ol>	otherwise be discharged? ☐ Yes ☐ No
6. a. Is the cooling water used in a once-through cooling syste	em? ☐ Yes ☐ No
b. Is the cooling water used in a closed cycle cooling system	m? ☐ Yes ☐ No

Page 7 of 11

6. List the trade name and chemical composition of all biocides and corrosion inhibitors used:

ADEM Form 187 10/17 m5

<ol><li>When was the intake installed?</li></ol>	struction/installation o	of intake compo	nents including scree	ens)	
What is the maximum intake volume?_ (maximum pumping capacity in gallons)		·	Ū	,	
9. What is the average intake volume?					
(average intake pump rate in gallons page	er day average in any	30-day period	)		
10. What is the actual intake flow (AIF) as	defined in 40 CFR §1	25.92(a)?	MGD		
11. How is the intake operated? (e.g., cont	tinuously, intermittentl	y, batch)			
12. What is the mesh size of the screen on	ı your intake?				
13. What is the intake screen flow-through	area?				
14. What is the through-screen design inta	ke flow velocity?	ft/sec	:		
15. What is the through-screen actual velocities	city (in ft/sec)?	ft/sec			
16. What is the mechanism for cleaning the	e screen? (e.g., does	it rotate for clea	aning)		
17.Do you have any additional fish detract	tion technology on you	ur intake?	Yes □ No		
18. Have there been any studies to determ provide.)	nine the impact of the	intake on aqua	tic organisms? ∐ Ye	es 🗌 No (If yes, plo	ease
19. Attach a site map showing the location	of the water intake in	relation to the	facility, shoreline, wa	iter depth, etc.	
rovide a description of the location of all sites f the state, either directly or indirectly via such t the facility for which the NPDES application	involved in the storag avenues as storm wa	e of solids or lic ater drainage, m	unicipal wastewater	systems, etc., which a	re located
Provide a description of the location of all sites f the state, either directly or indirectly via such t the facility for which the NPDES application	involved in the storag avenues as storm wa	e of solids or lic ater drainage, m	unicipal wastewater	systems, etc., which a sted on a map and incl	re locate
rovide a description of the location of all sites f the state, either directly or indirectly via such t the facility for which the NPDES application is application:  Description of Waste	involved in the storag avenues as storm wa is being made. Where	e of solids or lic ater drainage, me possible, the	unicipal wastewater location should be no Description of Sto	systems, etc., which a oted on a map and incl orage Location	re located uded with
rovide a description of the location of all sites f the state, either directly or indirectly via such the facility for which the NPDES application his application:  Description of Waste Silica fume generated during the produc	involved in the storag avenues as storm wa is being made. Where tion of silica metal	e of solids or licater drainage, me possible, the	unicipal wastewater location should be no Description of Sto fume slurry pond (Lat	systems, etc., which a bited on a map and included on a map and included orage Location  2. 32.396828°, Lon86.	re located luded with
rovide a description of the location of all sites f the state, either directly or indirectly via such the facility for which the NPDES application his application:  Description of Waste Silica fume generated during the production of the universe description of the location of the universe for the state of the state	involved in the storag avenues as storm wa is being made. Where stion of silica metal	e of solids or licater drainage, me possible, the	unicipal wastewater location should be no Description of Sto fume slurry pond (Lat	systems, etc., which a bited on a map and included on a map and included orage Location  2. 32.396828°, Lon86.	re located luded with
rovide a description of the location of all sites f the state, either directly or indirectly via such the facility for which the NPDES application his application:  Description of Waste Silica fume generated during the production of the unique of the location of the unique of	involved in the storag avenues as storm wa is being made. Where stion of silica metal ultimate disposal sites cility.	e of solids or lice ater drainage, me possible, the solid ater drainage and solid or lice at the solid or lice at	Description of Store  To should be not be no	systems, etc., which a oted on a map and included on a system of the	re located luded with
Provide a description of the location of all sites fithe state, either directly or indirectly via such the facility for which the NPDES application his application:  Description of Waste  Silica fume generated during the product of the understanding the product of the location of the understanding the factorist of the product of the product of the location of the product of the provide a description of the location of the product of the provide a description of the location of the product of the provide and the factorist of the product of the provided and the factorist of the product of the product of the provided and the factorist of the product of the prod	involved in the storag avenues as storm wa is being made. Where tion of silica metal ultimate disposal sites cility.  Quantity (lbs/c) 36,000	e of solids or lice ater drainage, me possible, the solid ater drainage and solid or lice at the solid or lice at	Description of Store  State of the state of	systems, etc., which a oted on a map and included on a second of the	re located luded with
rovide a description of the location of all sites fithe state, either directly or indirectly via such the facility for which the NPDES application is application:  Description of Waste Silica fume generated during the product rovide a description of the location of the unastewater treatment system located at the factorized from dewatering and treatment of Slurry Pond	involved in the storag avenues as storm wa is being made. Where stion of silica metal ultimate disposal sites cility.	e of solids or lice ater drainage, me possible, the solid ater drainage and solid or lice at the solid or lice at	Description of Store  State of the state of	systems, etc., which a oted on a map and included on a system of the	re located luded with
Provide a description of the location of all sites fithe state, either directly or indirectly via such the facility for which the NPDES application his application:  Description of Waste  Silica fume generated during the product  Provide a description of the location of the unastewater treatment system located at the factorization of Waste  Sludge from dewatering and treatment of Slurry Pond  Sludge from treatment of process area stormwater  Indicate which wastes identified above are	involved in the storag avenues as storm wa is being made. Where tion of silica metal altimate disposal sites cility.  Quantity (lbs/c 36,000 8,000	e of solids or lice ater drainage, me possible, the separate solid ater drainage, me possible, the separate solid ater drainage, me possible, the separate solid aterity s	Description of Store fume slurry pond (Late and waste by-produce Disp On site (waste facility and which	systems, etc., which a pited on a map and included on a section. 32.396828°, Lon86.  Cits (such as sludges)  Cosal Method*  within slurry pond)  within slurry pond)	re located uded with 084478°) from any
rovide a description of the location of all sites f the state, either directly or indirectly via such the facility for which the NPDES application his application:  Description of Waste Silica fume generated during the product rovide a description of the location of the urastewater treatment system located at the fact the fact of the location of th	involved in the storag avenues as storm wa is being made. Where tion of silica metal altimate disposal sites cility.  Quantity (lbs/c 36,000 8,000	e of solids or lice ater drainage, me possible, the separate solid ater drainage, me possible, the separate solid ater drainage, me possible, the separate solid aterity s	Description of Store fume slurry pond (Late and waste by-produce Disp On site (waste facility and which	systems, etc., which a oted on a map and included on a section. 32.396828°, Lon86.  Cts (such as sludges)	re located uded with 084478°) from any
rovide a description of the location of all sites f the state, either directly or indirectly via such the facility for which the NPDES application is application:  Description of Waste Silica fume generated during the product rovide a description of the location of the urastewater treatment system located at the fact the fact rowide from dewatering and treatment of Slurry Pond Sludge from treatment of process area stormwater and indicate which wastes identified above are my wastes are sent to an off-site centralize	involved in the storag avenues as storm wa is being made. Where tion of silica metal altimate disposal sites cility.  Quantity (lbs/c) 36,000  8,000  disposed of at an ord waste treatment face	e of solids or lice ater drainage, me possible, the separate solid ater drainage, me possible, the separate solid ater drainage, me possible, the separate solid aterity s	Description of Store fume slurry pond (Late and waste by-produce Disp On site (waste facility and which	systems, etc., which a oted on a map and included on a section. 32.396828°, Lon86.  Cts (such as sludges)	re located uded with 084478°) from any
rovide a description of the location of all sites f the state, either directly or indirectly via such the facility for which the NPDES application is application:  Description of Waste Silica fume generated during the product rovide a description of the location of the unastewater treatment system located at the fact that the fact rowide from dewatering and treatment of Slurry Pond Sludge from treatment of process area stormwater and wastes are sent to an off-site centralize is the discharge(s) located within the 10-for	involved in the storag avenues as storm wa is being made. Where stion of silica metal ultimate disposal sites cility.  Quantity (lbs/c 36,000 8,000 disposed of at an or id waste treatment fa	e of solids or lice ter drainage, me possible, the separate solid and separate solid or lice solid o	Description of Store fume slurry pond (Late and waste by-produce Disp On site (waste of the waste and the form	systems, etc., which a bred on a map and included on a second of a second of a second of a second of a second on a secon	re located uded with 084478°) from any
rovide a description of the location of all sites f the state, either directly or indirectly via such the facility for which the NPDES application is application:  Description of Waste Silica fume generated during the product rovide a description of the location of the urastewater treatment system located at the factor of the state of the system of the location of the state of the state of the system of the location of the urastewater treatment of the location of the urastewater treatment of the system located at the factor of the location of the urastewater from dewatering and treatment of Slurry Pond Sludge from treatment of process area stormwater of located which wastes identified above are ny wastes are sent to an off-site centralize SECTION F – COASTAL ZONE INFORMATION	involved in the storag avenues as storm wa is being made. Where stion of silica metal ultimate disposal sites cility.  Quantity (lbs/c 36,000 8,000 disposed of at an or id waste treatment fa	e of solids or lice ter drainage, me possible, the separate solid and separate solid or lice solid o	Description of Store fume slurry pond (Late and waste by-produce Disp On site (waste of the waste and the form	systems, etc., which a bred on a map and included on a second of second of second of second on a re disposed of onfacility.	re located uded with 084478°) from any site. If
Provide a description of the location of the unastewater treatment system located at the factoristic production of Waste  Description of Waste  Sludge from dewatering and treatment of Slurry Pond Sludge from treatment of process area stormwater  Indicate which wastes identified above are any wastes are sent to an off-site centralized SECTION F – COASTAL ZONE INFORMATION  Is the discharge(s) located within the 10-forms	involved in the storag avenues as storm wa is being made. Where stion of silica metal ultimate disposal sites cility.  Quantity (lbs/o 36,000 8,000 disposed of at an o d waste treatment fa	e of solids or lice of solids or lice drainage, me possible, the last of solid or lice of s	Description of Storement of Sto	systems, etc., which a bred on a map and included on a second of second of second of second on a re disposed of onfacility.	re located uded with 084478°) from any site. If

ADEM Form 187 10/17 m5 Page 8 of 11

	3.	Does the project involve dredging and/or filling of a wetland area or water way?		
	<b>J</b> .	If Yes, has the Corps of Engineers (COE) permit been received?		П
		COE Project No	Ч	Ц
	4.	Does the project involve wetlands and/or submersed grassbeds?		
		Are oyster reefs located near the project site?		
	5.	If Yes, include a map showing project and discharge location with respect to oyster reefs	Ы	ы
	6	Does the project involve the site development, construction and operation of an energy facility as defined in		
	6.	ADEM Admin. Code r, 335-8-102(bb)?		
	7.	Does the project involve mitigation of shoreline or coastal area erosion?		
	8.	Does the project involve construction on beaches or dune areas?		
	9.	Will the project interfere with public access to coastal waters?		
	10	Does the project lie within the 100-year floodplain?		
	11.	Does the project involve the registration, sale, use, or application of pesticides?		
	12	Does the project propose or require construction of a new well or to alter an existing groundwater well to pump more than 50 gallons per day (GPD)?		
		If yes, has the applicable permit for groundwater recovery or for groundwater well installation been		
		obtained?		
	2710	N.C. ANTI DECDARATION EVALUATION		
SE		N G - ANTI-DEGRADATION EVALUATION		
pro	vided	fance with 40 CFR §131.12 and the ADEM Admin. Code r. 335-6-1004 for anti-degradation, the following inform, if applicable. It is the applicant's responsibility to demonstrate the social and economic importance of the propertion is required to make this demonstration, attach additional sheets to the application.	mation posed a	must be ctivity. If
1.	s this	s a new or increased discharge that began after April 3, 1991?   Yes No , complete G.2 below. If no, go to Section H.		
	-		sod disa	harao
		an Anti-Degradation Analysis been previously conducted and submitted to the Department for the new or increasenced in G.1?   Yes  No	sea aisc	naige
	335-6	s, do not complete this section. If no, and the discharge is to a Tier II waterbody as defined in ADEM 5-1012(4), complete G.2.A – G.2.F below and ADEM Forms 311 and 313 (attached). ADEM Form 313 must alternative considered technically viable.	Admin. be prov	Code r. vided for
	Infor	nation required for new or increased discharges to high quality waters:		
	A.	What environmental or public health problem will the discharger be correcting?		
	В.	How much will the discharger be increasing employment (at its existing facility or as the result of locating a new	facility)	?
	C.	How much reduction in employment will the discharger be avoiding?		
	D.	How much additional state or local taxes will the discharger be paying?		
	E.	What public service to the community will the discharger be providing?		
	F.	What economic or social benefit will the discharger be providing to the community?		
				0.544
AD	EM F	om 187 10/17 m5	rage	e 9 of 11

ADEM Form 187 10/17 m5

#### SECTION H - EPA Application Forms

All Applicants must submit EPA permit application forms. More than one application form may be required from a facility depending on the number and types of discharges or outfalls found. The EPA application forms are found on the Department's website at <a href="http://www.adem.alabama.gov/programs/water/waterforms.cnt">http://www.adem.alabama.gov/programs/water/waterforms.cnt</a>. The EPA application forms must be submitted in duplicate as follows:

- 1. All applicants must submit Form 1.
- Applicants for existing industrial facilities (including manufacturing facilities, commercial facilities, mining activities, and silvicultural activities) which discharge process wastewater must submit Form 2C.
- 3. Applicants for new industrial facilities which propose to discharge process wastewater must submit Form 2D.
- Applicants for new and existing industrial facilities which discharge only non-process wastewater (i.e., non-contact cooling water and/or sanitary wastewater) must submit Form 2E.
- 5. Applicants for new and existing facilities whose discharge is composed entirely of storm water associated with industrial activity must submit Form 2F, unless exempted by § 122.26(c)(1)(ii). If the discharge is composed of storm water and non-storm water, the applicant must also submit Forms 2C, 2D, and/or 2E, as appropriate (in addition to Form 2F).

#### SECTION I - ENGINEERING REPORT/BMP PLAN REQUIREMENTS

See ADEM 335-6-6-.08(i) & (j)

#### SECTION J- RECEIVING WATERS

Outfall No.	Receiving Water(s)	303(d) Se	gment?	Included in TMDL?*	
001	Unnamed tributary to Miller Creek (stormwater)	☐ Yes	No	☐ Yes	No
002	Unnamed tributary to Miller Creek (process water)	☐ Yes	■No	Yes	■No
003	Unnamed tributary to Miller Creek (non-contact cooling water)	☐ Yes	■No	Yes	■No
004	Tallapoosa River (process water and stormwater)	Yes	No	Yes	No
		Yes	No	Yes	No

<sup>\*</sup>If a TMDL Compliance Schedule is requested, the following should be attached as supporting documentation:

- (1) Justification for the requested Compliance Schedule (e.g. time for design and installation of control equipment, etc.);
- (2) Monitoring results for the pollutant(s) of concern which have not previously been submitted to the Department (sample collection dates, analytical results (mass and concentration), methods utilized, MDL/ML, etc. should be submitted as available);
- (3) Requested interim limitations, if applicable;
- (4) Date of final compliance with the TMDL limitations; and,
- (5) Any other additional information available to support requested compliance schedule.

ADEM Form 187 10/17 m5 Page 10 of 11

#### SECTION K - APPLICATION CERTIFICATION

The information contained in this form must be certified by a responsible official as defined in ADEM Administrative Code r. 335-6-6-.09 "signatories to permit applications and reports" (see below).

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information including the possibility of fine and imprisonment for knowing violations."

Signature of Responsible Official.  Name and Title: Tim Dermon,		Date Signed: 5/6/2019	
If the Responsible Official signing this of	application is <u>not</u> identified in Section A.7, provide the	following information:	
Mailing Address:			
City:	State:	Zip:	
Phone Number:	Email Address:		

#### 335-6-6-.09 SIGNATORIES TO PERMIT APPLICATIONS AND REPORTS.


- (1) The application for an NPDES permit shall be signed by a responsible official, as indicated below:
  - (a) In the case of a corporation, by a principal executive officer of at least the level of vice president, or a manager assigned or delegated in
    accordance with corporate procedures, with such delegation submitted in writing if required by the Department, who is responsible for
    manufacturing, production, or operating facilities and is authorized to make management decisions which govern the operation of the
    regulated facility;
  - (b) In the case of a partnership, by a general partner;
  - (c) In the case of a sole proprietorship, by the proprietor; or
  - (d) In the case of a municipal, state, federal, or other public entity, by either a principal executive officer, or ranking elected official.

Biocide Information Individual NPDES Permit Modification DC Alabama Inc., Mt. Meigs, Alabama

Trade Name	Sodium Hypochlorite	Acutrace 3014	Acubrome Liquid
· <del>-</del>	Sodium Chloride, 5-20% (weight)	Sodium hydroxide, 10-15% (weight)	Sodium Bromide, 40%
	Sodium Hypochlorite, 10-20% (weight)	1-Hydroxyethylidene-1-diphosphonic acid, 4-8% (weight)	
Composition	Sodium Hydroxide, <1% (weight)	Sodium tolytriazole, 2-4% (weight)	
	Water, 60-85% (weight)	Sodium molybdate, 3-5% (weight)	
		Polymaleic acid, 4-8% (weight)	
	Daphnia Magna, 48h, EC50, 874 mg/L	Fathead Minnow, 96h, LC50, 976 mg/L	Fathead Minnow, 96h, LC50, >5,000 mg/L
96-hour median tolerance limit		Daphnia Magna, 48h, LC50, 1569 mg/L	Daphnia Magna, 48h, LC50, >5,000 mg/L
Quantity to be used	14 gallons/day	7 gallons/day	1 gallon/day
Frequency of use	Daily	Daily	Daily
Proposed discharge concentration	None discharged	None discharged	None discharged
EPA registration number (if applicable)	Not applicable	Not applicable	Not applicable

AX0601181110MGM

Figure 2
Plant Water Balance
DC Alabama, Inc., Mount Meigs, Alabama



EPA Form 3510-1 (8-90)

6


Mount Meigs

CONTINUE ON REVERSE

ΑL

IND. MUN BRANCH

CONTINUED FROM THE FRONT	
VII. SIC CODES (4-digit, in order of priority)	D OFFICE A
A. FIRST	B. SECOND
7 3313   Specify   Electrometallurgical Products, Except Steel	7
15 16 - 19 C. THIRD	15 16 - 19
C. THIRD	D. FOURTH
7	[7]
VIII. OPERATOR INFORMATION	15 16 - 19
VIII. OPERATOR INFORMATION  A. NAI	ME B. Is the name listed in Item
8 DC Alabama, Inc.	PES 🗆 NO
15 16	55 66
C. STATUS OF OPERATOR (Enter the appropriate	
F = FEDERAL M = PUBLIC (other than federal or state)	(specify) c (334) 270-3609
S = STATE P = PRIVATE O = OTHER (specify)	A (331/ 2/3 3333
	56 15 6 - 18 19 - 21 22 - 26
E. STREET OR P.O. BOX	
1940 Ohio Ferro Road	
E CITY OF TOWN	G. STATE   H. ZIP CODE   IX. INDIAN LAND
F. CITY OR TOWN	G. STATE H. ZIP CODE IX. INDIAN LAND I I I I I I I I I I I I I I I I I I I
B Mount Meigs	AL 36057 PES NO
15 16	40 41 42 47 - 51 52
X. EXISTING ENVIRONMENTAL PERMITS	
	PSD (Air Emissions from Proposed Sources)
CTI	
9 N AL0083763 9 P	
15 16 17 18 30 15 16 17	
B. UIC (Underground Injection of Fluids)	E. OTHER (specify)
9 U	209-0026 (specify)
15 16 17 18 30 15 16 17	Major Source Operating Air Permit
C. RCRA (Hazardous Wastes)	E. OTHER (specify)
CTI	(specify)
9 R 9	
15 16 17 18 30 15 16 17	30
XI. MAP	
	at least one mile beyond property boundaries. The map must show the outline of the facility, the tures, each of its hazardous waste treatment, storage, or disposal facilities, and each well where it
injects fluids underground. Include all springs, rivers, and other surface v	
XII. NATURE OF BUSINESS (provide a brief description)	
	mical and aluminum products. The facility also produces micro
	and filler by the concrete and refractory industries. The
manufacturing process includes melting raw mater	rials (quartz rock, coal, charcoal, and wood chips) in an
electric arc furnace to produce molten silicon	metal, which is cast as ingots. The ingots are crushed before
being packaged for shipping.	
VIII CERTIFICATION (see instructions)	
XIII. CERTIFICATION (see instructions)	
	amiliar with the information submitted in this application and all attachments and that, based on my
am aware that there are significant penalties for submitting false informa	mation contained in the application, I believe that the information is true, accurate, and complete. I tion, including the possibility of fine and imprisonment.
	SIGNATURE C. DATE SIGNED
Tim Dermon, Site Leader	
	Jem w. Dem 5/6/2019
<u> </u>	0101001
COMMENTS FOR OFFICIAL USE ONLY	
<u> </u>	
С	



Please print or type in the unshaded areas only.

PORM 2C



U.S. ENVIRONMENTAL PROTECTION AGENCY
APPLICATION FOR PERMIT TO DISCHARGE WASTEWATER
EXISTING MANUFACTURING, COMMERCIAL, MINING AND SILVICULTURE OPERATIONS
Consolidated Permits Program

ı	OUTFALL	LOCATION

For each outfall, list the latitude and longitude of its location to the nearest 15 seconds and the name of the receiving water. A. OUTFALL NUMBER **B. LATITUDE** C. LONGITUDE D. RECEIVING WATER (name) (list) 1. DEG. 2. MIN. 3, SEC, 1. DEG. 3. SEC. 2. MIN. 002 32.00 23.00 34.04 -86.00 4.00 11.63 Unnamed tributary to Miller Creek 32,00 004 24.00 33,14 -86.00 4.00 0.28 Tallapoosa River

#### II. FLOWS, SOURCES OF POLLUTION, AND TREATMENT TECHNOLOGIES

- A. Attach a line drawing showing the water flow through the facility. Indicate sources of intake water, operations contributing wastewater to the effluent, and treatment units labeled to correspond to the more detailed descriptions in Item B. Construct a water balance on the line drawing by showing average flows between intakes, operations, treatment units, and outfalls. If a water balance cannot be determined (e.g., for certain mining activities), provide a pictorial description of the nature and amount of any sources of water and any collection or treatment measures.
- B. For each outfall, provide a description of: (1) All operations contributing wastewater to the effluent, including process wastewater, sanitary wastewater, cooling water, and storm water runoff; (2) The average flow contributed by each operation; and (3) The treatment received by the wastewater. Continue on additional sheets if necessary.

1. OUT-	2. OPERATION(S)	CONTRIBUTING FLOW	3. TREATMENT							
FALL NO. (list)	a. OPERATION (list)	b. AVERAGE FLOW (include units)	a. DESCRIPTION	b. LIST CODE TABLE 2	S FROM C-1					
DSN002	Silica fume from baghouse	0.2 MGD	Evaporation	1-F						
/004			Polymer flocculation	1-G						
			Discharge to surface water	4-A						
			Potential additional treatment							
				-						
				+						
					<del></del>					
				<del>-   -  </del>						
	-									
			_							

OFFICIAL USE ONLY (effluent guidelines sub-categories)

EPA Form 3510-2C (8-90)



CONTINUE ON REVERSE

CONTINUED FF	OM THE FRO	ONT													
C. Except for st	torm runoff, le YES ( <i>complet</i>			of the	discharges d	described i	in Ite	ems II-A or B int	termittent or sea	isonal?					
						3. 1		QUENCY			4. FLC				
			NDED 4 TION(-)			a. DAYS P			- FLOW D		TOTAL V		$\neg$		
1. OUTFALL		CONT	PERATION(s) RIBUTING FLO	W		WEEK (specify	, I	b. MONTHS PER YEAR	a. FLOW RA	2. MAXIMUM	1. LONG	Specify with	h units)  2. MAXIN	AUM.	C. DURATION
NUMBER (list)	_		(list)			average,	,	(specify average)	AVERAGE	DAILY	AVER	AGE	DAIL		(in days)
1														- 1	
										ŀ				- 1	
										ļ					
											1				
					İ							1			
											•				
							ſ					- 1			
					}							ĺ			
III. PRODUCTIO	ON D					v .			. " •1						
A. Does an efflu		limitation	promulgated	d by El	PA under Se	ction 304	of the	e Clean Water	Act apply to you	r facility?		_			_
<u> </u>	YES (complete	e Item III-	-B)				V	NO (go to Sect	tion IV)						
B. Are the limita				eline e	xpressed in t	terms of p				ration)?					_
C. If you answe	YES (complete				ish sassass	-tt	<u>√</u>	NO (go to Sect	tion IV)						
applicable et	fluent guidelir	ne, and in	ndicate the af	fected	outfalls.	nts an act	uair	neasurement o	r your level of p	oroduction, exp	ressed i	n the ter	ms and	units	used in the
			1. A	/ERAG	E DAILY PR							2. AFFE	CTED O	UTFA	LLS
a. QUANTITY	PER DAY	b. UNITS	S OF MEASU	IRE	'	C. OPERA	ATIO	N, PRODUCT, (specify)	MATERIAL, ET	C.		(list e	outfall nu	mbers	)
	]			- 1											
	-														
										ı					
							-								
				ł											
IV. IMPROVEME	NTS									-					
А. Аге уои пом	required by	any Fed	deral, State o	or loca	l authority to	o meet ar	пујл	nplementation	schedule for th	e construction	, upgradi	ing or o	perations	s of v	vastewater
treatment equipermit condit	uipment or pra ions, administ	actices or trative or	r any other er enforcement	orders orders	nental progra , enforceme	ams which int complia	nay	y affect the disc schedule letter	charges describ	ed in this appli court orders, ar	cation? T	his inclu or loan c	des, but	is not	limited to,
	YES (complete	the follow	ving table)					NO (go to Item					.,		
1. IDENTIFICAT			2. AFI	FECTE	D OUTFALL	LS		3 80155 1	ESCRIPTION	OE BROJECT		4. FIN	AL COM	PLIAN	ICE DATE
AGREE	MENT, ETC.		a. NO.	b. 501	URCE OF DIS	CHARGE		J. DIVILLE	DESCRIPTION	01 71000001		a. REQ	UIRED	b. Pi	ROJECTED
Consent Orde	r 19-007-Cī	₩P	001	Stor	mwater Ru	noff	Sto	rmwater pon	d remediation	on - underw	ау	10/25			5/2019
			004	Slur	ry Pond a	1			stewater man			10/25			5/2019
				Stor	mwater			erway				,			, , , , ,
													-		
													1		
B. OPTIONAL:	You may atta	ach addit	tional sheets	descri	bing any ad	dditional w	vater	pollution cont	rol programs (d	or other enviro	nmental	projects	which i	may a	affect your
discharges) y construction.	ou now have	underwa	y or which yo	ou pian	. Indicate wh	hether eac	ch pr	ogram is now u	inderway or pla	nned, and indi	cate your	actual o	or planne	ed sch	edules for
	MARK "X" IF I	DESCRIP	TION OF A	DITIO	NAL CONTR	ROL PROC	GRA	MS IS ATTACH	łED						

EPA I.D. NUMBER (copy from Item 1 of Form 1)

#### CONTINUED FROM PAGE 2

V. INTAKE AND EFFLUENT CHARACTER			
INOTE. Tables V-A, V-D, and V	eding – Complete one set of tables for each /-C are included on separate sheets numbe	rea V-1 through V-9.	
D. Use the space below to list any of the from any outfall. For every pollutant you	pollutants listed in Table 2c-3 of the instruct u list, briefly describe the reasons you belie	ctions, which you know or have reason to live it to be present and report any analytical	believe is discharged or may be discharged I data in your possession.
1. POLLUTANT	2. SOURCE	1. POLLUTANT	2. SOURCE
			1
VI. POTENTIAL DISCHARGES NOT COVE			
Is any pollutant listed in Item V-C a substan	ce or a component of a substance which yo	ou currently use or manufacture as an inter-	mediate or final product or byproduct?
YES (list all such pollutants b	elow)	NO (go to Item VI-B)	
			i
			!
	•		<b>.</b>
			i
		_	

## CONTINUED FROM THE FRONT VII. BIOLOGICAL TOXICITY TESTING DATA Do you have any knowledge or reason to believe that any biological test for acute or chronic toxicity has been made on any of your discharges or on a receiving water in relation to your discharge within the last 3 years? YES (identify the test(s) and describe their purposes below) NO (go to Section VIII) Aquatic Toxicity by Method 1000.0 - Ceriodaphnia dubia Aquatic Toxicity by Method 1002.0 - Pimephales promelas Biological toxicity testing data were collected on April 18, 2018 at the stormwater retention pond, which was discharging treated slurry water at the time through General NPDES Permit (ALG120051) Outfall 001. The sample analyzed produced a growth or reproduction inhibition in 25% of Pimephales promelas at an effluent concentration of 7.90%. For Ceriodaphnia dubia, less than 25% of the test organisms exhibit growth or reproduction inhibition at an effluent concentration of 100%. VIII. CONTRACT ANALYSIS INFORMATION Were any of the analyses reported in Item V performed by a contract laboratory or consulting firm? YES (list the name, address, and telephone number of, and pallutants analyzed by, NO (go to Section IX) each such laboratory or firm below) C. TELEPHONE D. POLLUTANTS ANALYZED A. NAME B. ADDRESS (area code & no.) (list) VOLATILE ORGANIC COMPOUNDS (GC-MS); SEMIVOLATILE ORGANIC COMPOUNDS (GC-MS); TestAmerica Laboratories. Inc. 3355 McLemore Drive (850)474-1001 (TestAmerica Pensacola) Pensacola, FL 32514 DISSOLVED METALS (ICPMS); TOTAL METALS (ICPMS); DISSOLVED MERCURY (CVAA); TOTAL MERCURY; Oil and Grease; Total dissolved solids; Total suspended solids; Chemical oxygen demand; Phenols (total); Cvanide IX. CERTIFICATION I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

EPA Form 3510-2C (8-90)

C, SIGNATURE

A. NAME & OFFICIAL TITLE (type or print)

Tim Dermon, Site Leader

B, PHONE NO. (area code & no.)

(334) 270-3737

D. DATE SIGNED

PLEASE PRINT OR TYPE IN THE UNSHADED AREAS ONLY. You may report some or all of this information on separate sheets (use the seme format) instead of completing these pages. SEE INSTRUCTIONS.

EPA I.D. NUMBER (copy from Item 1 of Form 1)

V. INTAKE AND EFFLUENT CHARACTERISTICS (continued from page 3 of Form 2-C)

OUTFALL NO. DSN002 / DSN004

PART A -You must provide the results of at least one analysis for every pollutant in this table. Complete one table for each outfall. See instructions for additional details,

	-						3. UN	ITS	4. INTAKE			
				2. EFFLU	ENT_			(specify if			(optional)	
	a. MAXIMUM DA	ILY VALUE	b. MAXIMUM 30 (if availa		c. LONG TERM AVR (if available		d. NO. OF	a, CONCEN-		a. LONG AVERAGE		L NO 05
1. POLLUTANT	CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	ANALYSES	TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	b. NO. OF ANALYSES
a. Biochemical Oxygen Demand (BOD)	10	16.7	N/A	N/A	N/A	N/A	est	mg/L	lb/day			
b. Chemical Oxygen Demand (COD)	87.0	145.1	N/A	N/A	23.6	39.4	10	mg/L	lb/day			
c. Total Organic Carbon (TOC)	5.0	8.3	N/A	N/A	4.9	8.1	2	mg/L	lb/day			
d. Total Suspended Solids (TSS)	260	434	N/A	N/A	49.5	82.6	10	mg/L	lb/day			
e. Ammonia (as N)	0	0	N/A	N/A	N/A	N/A	1	mg/L	lb/day			
f. Flow	VALUE 0.80	)	VALUE N/J		VALUE 0.20		est	MGD MGD		VALUE	-	
g. Temperature (winter)	VALUE 22.3	7	VALUE N/I	λ.	VALUE 20.2		12	*c		VALUE		
h. Temperature (swnmer)	VALUE 22.7	7	VALUE N/F	7	VALUE 20.2	_	12	°C		VALUE		
i. pH	MINIMUM 7 . 4	MAXIMUM 8.2	MINIMUM N/A	MAXIMUM N/A			12	STANDARI	DUNITS			, ∀

PART B — Mark "X" in column 2-a for each pollutant you know or have reason to believe is present. Mark "X" in column 2-b for each pollutant you believe to be absent. If you mark column 2a for any pollutant which is limited either directly, or indirectly but expressly, in an effluent limitations guideline, you must provide the results of at least one analysis for that pollutant. For other pollutants for which you mark column 2a, you must provide quantitative data or an explanation of their presence in your discharge. Complete one table for each outfall. See the instructions for additional details and requirements.

<del></del>		RK "X"			2	EFFLUENT		4. UNITS			5. INTAKE (optional)			
1	Z. MA	KK A								4. UNI	S	5. INT	AKE (options	11)
1, POLLUTANT AND	8.	ъ.	a. MAXIMUM DA	VILY VALUE	b. MAXIMUM 30 DAY VALUE (if available)		c. LONG TERM AVRG. VALUE (if available)			- 00110511		a. LONG TERM / VALUE		
(if available)			(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	d. NO. OF ANALYSES	a. CONCEN- TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	b. NO. OF ANALYSES
a. Bromide (24959-67-9)		X												
b. Chlorine, Total Residual		X												
c, Color		X												
d. Fecal Coliform		X												
e, Fluoride (16984-48-8)		X			_									
f. Nitrate-Nitrite (as N)		X							_				_	

#### ITEM V-B CONTINUED FROM FRONT

	2. MA	2. MARK "X"				EFFLUENT				4. UNI	rs	5. INTAKE (optional)		
1. POLLUTANT AND		ь.	a. MAXIMUM DA	ILY VALUE	b. MAXIMUM 30 (if availa	DAY VALUE	c. LONG TERM A' (if availa	VRG. VALUE				a, LONG TI AVERAGE V	ERM ALUE	
CAS NO. (if available)	a, BELIEVED PRESENT	b. BELIEVED ABSENT	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	d. NO. OF ANALYSES	a. CONCEN- TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	b. NO. OF ANALYSES
g. Nitrogen, Total Organic (as N)		X						_						_
h, Oil and Grease	X		2.2	3.7	N/A	N/A	1.0	1.7	10	mg/L	lb/d			
i. Phosphorus (as P), Total (7723-14-0)		X		_				-		·				
j. Radioactivity		<del></del>												
(1) Alpha, Total		X				-							_	
(2) Beta, Total		X				_								
(3) Radium, Total		X	_					_			-			
(4) Radium 226, Total		X		-										
k. Sulfate (as SO <sub>2</sub> ) (14808-79-8)		X				-							-	
I, Sulfide (as S)		X												
m. Sulfite (as SO <sub>3</sub> ) (14265-45-3)		X	_			-		-						
n. Surfactants		X												
o. Aluminum, Total (7429-90-5)	X		5.1	8.5	N/A	N/A	0.617	1.0	12	mg/L	lb/d			
p. Barium, Total (7440-39-3)		X												
q. Boron, Total (7440-42-8)		X						_			_		· ·	
r. Cobalt, Total (7440-48-4)		X		<u> </u>	,				_					
s. Iron, Total (7439-89-6)		X											-	
t. Magnesium, Total (7439-95-4)		X												
u. Molybdenum, Total (7439-98-7)		×												
v. Manganese, Total (7439-96-5)		X												
w. Tin, Total (7440-31-5)		X						_	-					
x. Titanium, Total (7440-32-6)		X												

EPA I.D. NUMBER (copy from Item 1 of Form 1) OUTFALL NUMBER

CONTINUED FROM PAGE 3 OF FORM 2-C

DSN002 / DSN004

PART C - If you are a primary industry and this outfall contains process wastewater, refer to Table 2c-2 in the instructions to determine which of the GC/MS fractions you must test for, Mark "X" in column 2-a for all such GC/MS fractions that apply to your industry and for ALL toxic metals, cyanides, and total phenols. If you are not required to mark column 2-a (secondary industries, nonprocess wastewater outfalls, and nonrequired GC/MS fractions), mark "X" in column 2-b for each pollutant you know or have reason to believe is present. Mark "X" in column 2-b for each pollutant you wastewater outfalls, and nonrequired GC/MS provide the results of at least one analysis for that pollutant. If you mark column 2b for any pollutant, you must provide the results of at least one analysis for that pollutant if you know or have reason to believe it will be discharged in concentrations of 10 ppb or greater. If you mark column 2b for acrolein, acrylonitrile, 2,4 dinitrophenol, or 2-methyl-4, 6 dinitrophenol, you must provide the results of at least one analysis for each of these pollutants which you know or have reason to believe that you discharge in concentrations of 100 ppb or greater. Otherwise, for pollutants for which you mark column 2b, you must either submit at least one analysis or briefly describe the reasons the pollutant is expected to be discharged. Note that there are 7 pages to this part; please review each carefully. Complete one table (all 7 pages) for each outfall. See instructions for

addition	al details an	nd requireme	ents.										ages) for each only		
	2	2. MARK "X"					FFLUENT				4. UN	ITS	5. INTAKE (optional)		
1. POLLUTANT AND CAS NUMBER	a.	ь.	C.	a. MAXIMUM DA	ILY VALUE	b. MAXIMUM 30 [ (if availal		c. LONG TERM VALUE (if ave		1 110 05	201/2511		a, LONG T AVERAGE V		
(if available)	TESTING REQUIRED	BELIEVED PRESENT	ABSENT	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	ANALYSES	a. CONCEN- TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	b. NO. OF ANALYSES
METALS, CYANIDE	, and tot	AL PHENO	LS												
1M. Antimony, Total (7440-36-0)		X		0.0079	0.0132	N/A	N/A	0.0055	0.009	12	mg/L	lb/d			
2M. Arsenic, Total (7440-38-2)		X		0.087	0.145	N/A	N/A	0.0311	0.052	12	mg/L	1b/đ			-
3M. Beryllium, Total (7440-41-7)		X		0.004	0.007	N/A	N/A	0.00003	0.000	12	mg/L	lb/d			
4M. Cadmium, Total (7440-43-9)			X	0	0	N/A	N/A	0	0	12	mg/L	1b/d			
5M. Chromium, Total (7440-47-3)		X		0.0066	0.011	N/A	N/A	0.0007	0.001	12	mg/L	lb/d			
6M, Copper, Total (7440-50-8)		X		0.015	0.0250	N/A	N/A	0.0019	0.003	12	mg/L	lb/d			
7M. Lead, Total (7439-92-1)		X		0.0066	0.0110	N/A	N/A	0.00084	0.001	12	mg/L	lb/d			
BM. Mercury, Total (7439-97-6)			X	0	0	N/A	N/A	0	0	12	mg/L	lb/d			
9M. Nickel, Total (7440-02-0)		X		0.007	0.0117	N/A	N/A	0.0011	0.002	12	mg/L	lb/d			
10M. Selenium, Total (7782-49-2)		X		0.035	0.058	N/A	N/A	0.022	0.038	12	mg/L	lb/d			
11M. Silver, Total (7440-22-4)			X	0	0	N/A	N/A	0	0	12	mg/L	lb/d			
12M. Thallium, Total (7440-28-0)		X		0.00047	0.0008	N/A	A/N	0.00039	0.001	12	mg/L	lb/d			
13M. Zinc, Total (7440-66-6)		X		0.610	1.02	N/A	N/A	0.108	0.169	12	mg/L	lb/d		_	
14M. Cyanide, Total (57-12-5)			X	0	0	N/A	N/A	0	0	12	mg/L	lb/d			
15M. Phenols, Total		X		0.013	0.0217	N/A	N/A	0.0056	0.009	11	mg/L	lb/d			
DIOXIN															
2,3,7,8-Tetra- chlorodibenzo-P- Dioxin (1764-01-6)			X	DESCRIBE RESU	ILTS										

CONTINUED	COOLI TI	E EDONT
CONTINUED	FRUM II	

CONTINUED FROM		. MARK "X"					FFLUENT				4. UNITS		5. INTAKE (options a. LONG TERM		/)
1. POLLUTANT AND	a.	ь.	C.	a. MAXIMUM DAI	ILY VALUE	b. MAXIMUM 30 E (if availab		c, LONG TERM VALUE (if ava					a. LONG T AVERAGE V	ERM 'ALUE	]
CAS NUMBER (if available)	TESTING REQUIRED	BELIEVED PRESENT	BELIEVED ABSENT	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	d. NO. OF ANALYSES	a. CONCEN- TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	h, NO. OF ANALYSES
GC/MS FRACTION	~ VOLATIL	E COMPOL	JNDS												
1V. Accrolein (107-02-8)			X	0	0 .	N/A	N/A	0	0	11	mg/L	lb/d		_	
2V. Acrylonitrile (107-13-1)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
3V. Benzene (71-43-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
4V. Bis (Chloro- methyl) Ether (542-88-1)			$\times$	0	0	N/A	N/A	0	0	11	mg/L	1b/d			
5V. Bromoform (75-25-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
6V. Carbon Tetrachloride (56-23-5)			$\times$	О	0	N/A	N/A	0	0	11	mg/L	lb/d			
7V. Chlorobenzene (108-90-7)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
8V. Chlorodi- bromomethane (124-48-1)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
9V. Chloroethane (75-00-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
10V. 2-Chloro- ethylvinyl Ether (110-75-8)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
11V. Chloroform (67-66-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
12V. Dichloro- bromomethane (75-27-4)		X		0.00064	0.0011	N/A	N/A	0.0006	0.000	11	mg/L	lb/d			
13V. Dichloro- difluoromethane (75-71-8)			X	0	0	N/A	N/À	0	0	11	mg/L	lb/d			
14V. 1,1-Dichloro- ethane (75-34-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
15V. 1,2-Dichloro- ethane (107-06-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
16V. 1,1-Dichloro- ethylene (75-35-4)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
17V. 1,2-Dichloro- propane (78-87-5)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
18V. 1,3-Dichloro- propylene (542-75-6)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
19V. Ethylbenzeле (100-41-4)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
20V. Methyl Bromide (74-83-9)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
21V. Methyl Chloride (74-87-3)			X	0	0	n/A	N/A	0	0	11	mg/L	lb/d			

#### CONTINUED FROM PAGE V-4

CONTINOEDTRON		. MARK "X	-				FFLUENT				4. UN	ITS		KE (optiona	d)
1, POLLUTANT AND	a.	b.	c.	a, MAXIMUM DA	ILY VALUE	b. MAXIMUM 30 I (if availal		c. LONG TERM VALUE (if ava	ailable)				a, LONG T AVERAGE V		
CAS NUMBER (if available)	TESTING REQUIRED	BELIEVED PRESENT		(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	d. NO. OF ANALYSES	a. CONCEN- TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	b. NO. O
GC/MS FRACTION	- VOLATIL	E COMPO	UNDS (cont	inued)											
22V. Methylene Chloride (75-09-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
23V. 1,1,2,2- Tetrachloroethane (79-34-5)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
24V. Tetrachloro- ethylene (127-18-4)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
25V. Toluene (108-88-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
26V. 1,2-Trans- Dichlorcethylene (156-60-5)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
27V. 1,1,1-Trichloro- ethane (71-55-6)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
28V. 1,1,2-Trichloro- ethane (79-00-5)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
29V Trichloro- ethylene (79-01-6)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
30V. Trichloro- fluoromethane (75-69-4)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
31V. Vinyl Chloride (75-01-4)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
GC/MS FRACTION	- ACID CC	MPOUNDS	3					, <u> </u>							
1A. 2-Chloropheлоl (95-57-8)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
2A. 2,4-Dichloro- phenol (120-83-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
3A. 2,4-Dimethyl- phenol (105-67-9)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
4A, 4,6-Dinitro-O- Creso! (534-52-1)	-		X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
5A. 2,4-Dinitro- phenol (51-28-5)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d	· ·		
6A. 2-Nitrophenol (88-75-5)		-	X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
7A. 4-Nitrophenol (100-02-7)		_	X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
8A. P-Chloro-M- Cresol (59-50-7)	-		X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
9A. Pentachloro- phenol (87-86-5)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
10A. Phenol (108-95-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
11A. 2,4,6-Trichloro- phenol (88-05-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
EPA Form 3510-20	: (8-90)						PAGE	= V-5						ITINUE ON	20.500

#### CONTINUED FROM THE FRONT

	2	MARK "X					FFLUENT				4. UN	ITS		KE (optiona	1)
1. POLLUTANT AND	a.	b.	C.	a. MAXIMUM DA	ILY VALUE	b. MAXIMUM 30 [ (if availab		c. LONG TERM VALUE (if av					a. LONG Ti AVERAGE V		
CAS NUMBER (if available)	TESTING REQUIRED	BELIEVED PRESENT	BELIEVED ABSENT	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	d. NO. OF ANALYSES	a, CONCEN- TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	b. NO. OF ANALYSES
GC/MS FRACTION	- BASE/NE	UTRAL CO	OMPOUNDS	S			·								
1B. Acenaphthene (83-32-9)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
2B. Acenaphtylene (208-96-8)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
3B, Anthracene (120-12-7)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
4B. Benzidine (92-87-5)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
5B. Benzo (a) Anthracene (56-55-3)	_		X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
68, Benzo (a) Pyrene (50-32-8)	·		X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
7B. 3,4-Benzo- fluoranthene (205-99-2)		_	$\times$	0	0	N/A	N/A	0	o	11	mg/L	lb/d		_	
8B. Benzo (ghi) Perylene (191-24-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
9B. Benzo (k) Fluoranthene (207-08-9)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
10B. Bis (2-Chloro- ethoxy) Methane (111-91-1)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
11B. Bis (2-Chloro- ethyl) Ether (111-44-4)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
12B. Bis (2- Chloroisopropyl) Ether (102-80-1)			$\times$	0	0	N/A	N/A	0	0	11	mg/L	lb/d		·	
13B. Bis (2-Ethyl- hexyl) Phthalate (117-81-7)		X		0.0011	0.0183	N/A	N/A	0.0019	0.003	11	mg/L	lb/d			
14B. 4-Bromophenyl Phenyl Ether (101-55-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
158. Butyl Benzyl Phthalate (85-68-7)			X	0	0	N/A	N/A	0 '	0	11	mg/L	lb/d			
16B. 2-Chloro- naphthalene (91-58-7)			X	0	0	N/A	N/A	0	0	11	mg/L	1b/d			
17B, 4-Chloro- phenyl Phenyl Ether (7005-72-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
18B. Chrysene (218-01-9)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
19B, Dibenzo (a,h) Anthracene (53-70-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
208. 1,2-Dichloro- benzene (95-50-1)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/đ			
21B. 1,3-Di-chloro- benzene (541-73-1)			I X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			

#### CONTINUED FROM PAGE V-6

_	PAGE V-0	. MARK "X"		· · ·			FFLUENT				4. UN	ITS	5. INTA	KE (optiona	1/)
1. POLLUTANT AND	a.	ь.	C.	a. MAXIMUM DA	ILY VALUE	b. MAXIMUM 30 [ (if availab		c. LONG TERM VALUE (if ave					a, LONG TI AVERAGE V		
CAS NUMBÉR (if available)	TESTING REQUIRED	BÉLIEVED PRESENT		(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION		d. NO. OF ANALYSES	a. CONCEN- TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	b. NO. OF ANALYSES
GC/MS FRACTION	- BASE/N	EUTRAL CO	DMPOUND	S (continued)											
22B. 1,4-Dichloro- benzene (106-46-7)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
23B. 3,3-Dichtoro- benzidine (91-94-1)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
24B, Diethyl Phthalate (84-66-2)		X		0.00046	0.0008	N/A	N/A	0.000008	0.000	11	mg/L	lb/d			
25B. Dimethyl Phthalate (131 -11-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
26B. Di-N-Butyl Phthalate (84-74-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
27B. 2.4-Dinitro- toluene (121-14-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
28B. 2,6-Dinitro- toluene (606-20-2)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
29B. Di-N-Octyl Phthalate (117-84-0)		X		0.0047	0.0078	N/A	N/A	0.00085	0.001	11	mg/L	lb/d			
30B. 1,2-Diphenyl- hydrazine (as Azo- benzene) (122-66-7)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
31B. Fluoranthene (206-44-0)		X		0.00046	0.0008	N/A	N/A	0.00004	0.000	11	mg/L	lb/d			
32B. Fluorene (86-73-7)			$\perp$	0	0	N/A	N/A	0	0	11	mg/L	lb/d		_	
33B. Hexachloro- benzene (118-74-1)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
34B, Hexachloro- butadiene (87-68-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
35B. Hexachloro- cyclopentadiene (77-47-4)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
36B Hexachloro- ethane (67-72-1)			X	0	0	A/N	N/A	0	0	11	mg/L	lb/d			
37B. Indeno (1,2,3-cd) Pyrene (193-39-5)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
38B. Isophorone (78-59-1)		X		0.0027	0.0045	N/A	N/A	0.0002	0.000	11	mg/L	lb/d			
39B. Naphthalene (91-20-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
40B. Nitrobenzene (98-95-3)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
41B. N-Nitro- sodimethylamine (62-75-9)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
42B. N-Nitrosodi- N-Propylamine (621-64-7)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			

CONTINUED FROM THE FRONT

CONTINUED FROM		. MARK "X					FFLUENT				4. UN	ITS		KE (optiona	l)
1. POLLUTANT AND	a,	b.	c.	a. MAXIMUM DA	ILY VALUE	b. MAXIMUM 30 (if availab	DAY VALUE	c. LONG TERM VALUE (if ava	l AVRG. uilable)				a. LONG T AVERAGE V	ERM /ALUE	
CAS NUMBER (if available)	TESTING	b. BELIEVED PRESENT	BELIEVED ABSENT	(1) CONCENTRATION		(1) CONCENTRATION	(2) MASS	(1)		d. NO. OF ANALYSES	a. CONCEN- TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	b. NO. OF ANALYSES
GC/MS FRACTION	- BASE/NE	UTRAL CO													
43B. N-Nitro- sodiphenylamine (86-30-6)			X	0	0	n/A	N/A	0	0	11	mg/L	lb/d			
44B. Phenanthrene (85-01-8)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
45B. Pyrene (129-00-0)			X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
46B. 1,2,4-Tri- chlorobenzene (120-82-1)	-		X	0	0	N/A	N/A	0	0	11	mg/L	lb/d			
GC/MS FRACTION	- PESTIC	DES		,											
1P. Aldrin (309-00-2)	_		X												
2P. α-BHC (319-84-6)	_		X												
3P. β-BHC (319-85-7)			X		_										ļ
4P. γ-BHC (58-89-9)			X												
5P. δ-BHC (319-86-8)			X	_											
6P. Chlordane (57-74-9)			X												
7P. 4,4'-DDT (50-29-3)			X												
8P. 4,4'-DDE (72-55-9)			X												
9P. 4,4'-DDD (72-54-8)			X					_							
10P. Dieldrin (60-57-1)			X												
11P. α-Enosulfan (115-29-7)			X												
12P. β-Endosulfan (115-29-7)			X												
13P. Endosulfan Sulfate (1031-07-8)			X												
14P. Endrin (72-20-8)			X												
15P. Endrin Aldehyde (7421-93-4)			X												
16P. Heptachlor (76-44-8)			X												
EDA Form 3510-20	10.00						PAGE						00	ALTERUS OF	DAGE V.O

EPA I.D. NUMBER (copy from Item 1 of Form 1)

OUTFALL NUMBER

DSN002 / DSN004

CONTINUED FRO									DSN002 /	DSN00	4					
		2. MARK "X"			3. EFFLUENT					4, UN	IITS	5. INTA	KE (options	ıl)		
1. POLLUTANT AND CAS NUMBER	AND a b					ILY VALUE			VALUE (if avo	l AVRG. ailable)	4 110 05			a. LONG T AVERAGE V	ERM	
(if available)	REQUIRED	PRESENT	ABSENT	CONCEN	1) TRATION	(2) MASS	(1) CONCENTRATION	(2) MASS	(1) CONCENTRATION	(2) MASS		a. CONCEN- TRATION	b. MASS	(1) CONCENTRATION	(2) MASS	b. NO. OF ANALYSES
GC/MS FRACTION	I – PESTICI	DES (contin	ued)												(-,,	1
17P, Heptachlor Epoxide (1024-57-3)			X	<u> </u>											i	
18P. PCB-1242 (53469-21-9)			X													
19P. PCB-1254 (11097-69-1)			X	Ī												
20P. PCB-1221 (11104-28-2)			X													
21P. PCB-1232 (11141-16-5)			X													-
22P. PCB-1248 (12672-29-6)			X	•												
23P. PCB-1260 (11096-82-5)			X								<del></del>					
24P. PCB-1016 (12674-11-2)			X													
25P. Toxaphene (8001-35-2)			X													<del>                                     </del>

EPA Form 3510-2C (8-90)

PAGE V-9

Please print or type in the unshaded areas only



U.S. Environmental Protection Agency Washington, DC 20460

# Application for Permit to Discharge Storm Water Discharges Associated with Industrial Activity

#### Paperwork Reduction Act Notice

Public reporting burden for this application is estimated to average 28.6 hours per application, including time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding the burden estimate, any other aspect of this collection of information, or suggestions for improving this form, including suggestions which may increase or reduce this burden to: Chief, Information Policy Branch, PM-223, U.S. Environmental Protection Agency, 1200 Pennsylvania Avenue, NW, Washington, DC 20460, or Director, Office of Information and Regulatory Affairs, Office of Management and Budget, Washington, DC 20503.

լ. Ouπaii Location								
For each outfall, list the	ne latitude ar	nd longitude of	its location to	the nearest 1	5 seconds an	d the name	of the receiving water.	
A. Outfall Number (list)		B. Latitude		C. Longitude			D. Receiving Water (name)	
DSN001	32.00	23.00	34.01	-86.00	4.00	11.64	Unnamed Tributary to Miller Creek	
DSN004	32.00	24.00	35.21	-86.00	4.00	0.40	Tallapoosa River	
						•		
II. Improvements								

A. Are you now required by any Federal, State, or local authority to meet any implementation schedule for the construction, upgrading or operation of wastewater treatment equipment or practices or any other environmental programs which may affect the discharges described in this application? This includes, but is not limited to, permit conditions, administrative or enforcement orders, enforcement compliance schedule letters, stipulations, court orders, and grant or loan conditions.

1. Identification of Conditions,		2. Affected Outfalls		4. Final Compliance Date		
Agreements, Etc.	number	source of discharge	3. Brief Description of Project	a. req.	b. proj.	
Consent Order 19-007-CWP	001	Stormwater	Revised Stormwater Remediation Plan		10/25/19	
	004	Process and Stormwater	Wastewater Management Engineering Report	10/25/19	10/25/19	
	<del>                                     </del>	_			-	
	ļ					
	1		<del> </del>	-		
<del> </del>	<del> </del>					
	ļ					
	ļ			<b></b>		
			<del> </del>			

B: You may attach additional sheets describing any additional water pollution (or other environmental projects which may affect your discharges) you now have under way or which you plan, Indicate whether each program is now under way or planned, and indicate your actual or planned schedules for construction.


#### III. Site Drainage Map

Attach a site map showing topography (or indicating the cuttine of drainage areas served by the outfalls(s) covered in the application if a topographic map is unavailable) depicting the facility including: each of its intake and discharge structures; the drainage area of each storm water outfall; paved areas and buildings within the drainage area of each storm water outfall, each known past or present areas used for outdoor storage of disposal of significant materials, each existing structural control measure to reduce pollutants in storm water runoff, materials loading and access areas, areas where pesticides, herbicides, soil conditioners and fertilizers are applied; each of its hazardous waste treatment, storage or disposal units (including each area not required to have a RCRA permit which is used for accumulating hazardous waste under 40 CFR 262.34); each well where fluids from the facility are injected underground; springs, and other surface water bodies which received storm water discharges from the facility.

EPA Form 3510-2F (1-92)

Page 1 of 3

Continue on Page 2



Continued	from	the	Front
-----------	------	-----	-------

	om the Front				
IV. Narra	tive Description of Polluta	ant Sources			
	ch outfall, provide an estimate of the area d by the outfall.	a (include units) of imperious surface	es (including peve	d areas and building roofs) drained to the outfall, and	an estimate of the total surface area
Outrall	Area of Impervious Surface	Total Area Drained	Outfall	Area of Impervious Surface	Total Area Drained
Number DSN001	(provide units)	(provide units)	Number	(provide units)	(provide units)
DSN004	4.8 acres	10 acres			
			1		
			i i		
to stor	m water, method of treatment, stor water runoff; materials loading and	rage, or disposal; past and pre	sent materials	ee years have been treated, stored or disposee management practices employed to minimize frequency in which pesticides, herbicides, soil	contact by these materials with
Please re	efer to Form 2F Supplementa	al Information for a des	eription of	significant materials.	-
descr		ater receives, including the sch		structural control measures to reduce pollutan of maintenance for control and treatment measurement measurement measurement measurement measurement and treatment measurement measurement and treatment measurement measurement measurement measurement and treatment measurement measure	
Outfall	1			<del></del>	List Codes from
Number			reatment		Table 2F-1
DSN001 DSN004	nonstructural control me			iption of existing structural and	1-U sedimentation
		<b>,,</b>			4-A discharge to
					surface water
	1				
V. Nonst	ormwater Discharges				
				sted or evaluated for the presence of nonstorr Form 2C or From 2E application for the outfall	
Name and	Official Title (type or print)	Signature		[c	Date Signed
Tim Dermo	n, Site Leader				
				J	
B. Provid	le a description of the method used	, the date of any testing, and th	e onsite draina	ge points that were directly observed during a te	est
Wet and d	ry weather visual inspecti	ons are conducted twice	per week p	er the facility best management pra	ctices plan.
Vî. Signiî	icant Leaks or Spills				
	existing information regarding the late date and location of the spill or			or hazardous pollutants at the facility in the lased.	ast three years, including the
		of toxic or hazardous p	ollutants a	t the facility in the last three ye	ars in reportable
quantitie	Б.				

1

Continued	from	Page	2
Continueu	11 0111	I aye	_

EPA ID Number (copy from Item 1 of Form 1)

		CONTRACTOR SECTIONS
proceeding. Complete one set of tables for each or are included on separate sheets numbers VII-1 a		space provided.
r analysis – is any toxic pollutant listed in table termediate or final product or byproduct?	2F-2, 2F-3, or 2F-4, a substance or a	component of a substance which you
s below)	No (go to Section IX)	
Data Sylva Sylva 16.5 / S	40534454	
o believe that any biological test for acute or chro 3 years?	onic toxicity has been made on any of you	ir discharges or on a receiving water in
below)	No (go to Section IX)	
on   m VII performed by a contract laboratory or cons		
	ulting firm?  No (go to Section X)	D. Rollstonte Analyzed
m VII performed by a contract laboratory or cons s, and telephone number of, and pollutants		D. Pollutants Analyzed
m VII performed by a contract laboratory or cons s, and telephone number of, and pollutants th laboratory or firm below)	No (go to Section X)	D. Pollutants Analyzed  BTEX; Naphthalene; Total metals (ICPMS); Oil and Grease; Total dissolved solids; Total suspended solids; Biological oxygen demand; Total nitrogen; Total phosphorous; Phenols (total); Cyanide; Chloride; Nitrate; Total Organic Carbon Nitrogen, Kjeldahl
m VII performed by a contract laboratory or consists, and telephone number of, and pollutants the laboratory or firm below)  B. Address  3355 McLemore Drive	No (go to Section X)  C. Area Code & Phone No.	BTEX; Naphthalene; Total metals (ICCMS); Oil and Grease; Total dissolved solids; Total suspended solids; Biological oxygen demand; Chemical oxygen demand; Total nitrogen; Total phosphorous; Phenols (total); Cyanide; Chloride; Nitrate; Total Organic Carbon
m VII performed by a contract laboratory or consists, and telephone number of, and pollutants the laboratory or firm below)  B. Address  3355 McLemore Drive	C. Area Code & Phone No.  (850) 474-1001  der my direction or supervision in accordation my inquiry of the person or persons whitest of my knowledge and belief, true, ac	BTEX; Naphthalene; Total metals (ICPMS); Oil and Grease; Total dissolved solids; Total suspended solids; Biological oxygen demand; Chemical oxygen demand; Total nitrogen; Total phosphorous; Phenols (total); Cyanide; Chloride; Nitrate; Total Organic Carbon Nitrogen, Kjeldahl
m VII performed by a contract laboratory or consists, and telephone number of, and pollutants the laboratory or firm below)  B. Address  3355 McLemore Drive Pensacola, FL 32514  coument and all attachments were prepared under and evaluate the information submitted. Based of formation, the information submitted is, to the best of the property of the	C. Area Code & Phone No.  (850) 474-1001  der my direction or supervision in accordation my inquiry of the person or persons whitest of my knowledge and belief, true, ac	BTEX; Naphthalene; Total metals (ICPMS); Oil and Grease; Total dissolved solids; Total suspended solids; Biological oxygen demand; Chemical oxygen demand; Total nitrogen; Total phosphorous; Phenols (total); Cyanide; Chloride; Nitrate; Total Organic Carbon Nitrogen, Kjeldahl
m VII performed by a contract laboratory or consists, and telephone number of, and pollutants the laboratory or firm below)  B. Address  3355 McLemore Drive Pensacola, FL 32514  coument and all attachments were prepared under and evaluate the information submitted. Based of formation, the information submitted is, to the best of the property of the	C. Area Code & Phone No.  (850) 474-1001  der my direction or supervision in accordate my inquiry of the person or persons wheest of my knowledge and belief, true, acfine and imprisonment for knowing violation.	BTEX; Naphthalene; Total metals (ICPMS); Oil and Grease; Total dissolved solids; Total suspended solids; Biological oxygen demand; Chemical oxygen demand; Total nitrogen; Total phosphorous; Phenols (total); Cyanide; Chloride; Nitrate; Total Organic Carbon Nitrogen, Kjeldahl
	analysis – is any toxic pollutant listed in table termediate or final product or byproduct?  below)  Data  believe that any biological test for acute or chr 3 years?  below)  conducted on proposed Outfall 004 d	analysis – is any toxic pollutant listed in table 2F-2, 2F-3, or 2F-4, a substance or a stermediate or final product or byproduct?    Data   D

### VII. Discharge information (Continued from page 3 of Form 2F)

Part A - You must provide the results of at least one analysis for every pollutant in this table. Complete one table for each outfall. See instructions for additional details.

		um Values ide units)		erage Values aclude units)	Number	
Pollutant and CAS Number (if available)	Grab Sample Taken During First 20 Minutes	Flow-Weighted Composite	Grab Sample Taken During First 20 Minutes	Flow-Weighted Composite	of Storm Events Sampled	Sources of Pollutants
Oil and Grease	1.9 mg/L	N/A	N/A	N/A	1.00	Stormwater Runoff
Biological Oxygen Demand (BOD5)	3.3 mg/L	3.8 mg/L	N/A	N/A	1.00	Stormwater Runoff
Chemical Oxygen Demand (COD)	48 mg/L	45 mg/L	N/A	N/A	1.00	Stormwater Runoff
Total Suspended Solids (TSS)	200 mg/L	150 mg/L	N/A	N/A	1.00	Stormwater Runoff
Total Nitrogen	1.1 mg/L	2.2 mg/L	N/A	N/A	1.00	Stormwater Runoff
Total Phosphorus	0.30 mg/L	0.24 mg/L	N/A	N/A	1.00	Stormwater Runoff
pН	Minimum 8.05	Maximum 8.05	Minimum	Maximum	1.00	Stormwater Runoff

Part B – List each pollutant that is limited in an effluent guideline which the facility is subject to or any pollutant listed in the facility's NPDES permit for its process wastewater (if the facility is operating under an existing NPDES permit). Complete one table for each outfall. See the instructions for additional details and requirements.

(înclu	ım Values de units)	Aver (inc	age Values lude units)	Number	
Grab Sample Taken During First 20 Minutes	Flow-Weighted Composite	Grab Sample Taken During First 20 Minutes	Flow-Weighted Composite	of Storm Events Sampled	Sources of Pollutants
			<u> </u>		
			<u> </u>		
		<u> </u>			
		<b>_</b>		ļ	·
				1	
				++	
		<del>                                     </del>	_	<del>                                     </del>	
				-	<u> </u>
		1		<del>  </del>	
		1		<del> </del>	
		1		<del> </del>	<u> </u>
		<del> </del>		+ - +	<u> </u>
		-		<del>                                     </del>	
		1		<del>                                     </del>	
		1	<u> </u>	<del>                                     </del>	
		1		+	<del></del>
		+ +		<del></del>	
		<del>                                     </del>		<del> </del>	
		<del>                                     </del>		<del>    -</del>	
		<del>                                     </del>		<del>                                     </del>	
		<del>  -  </del>			
				<del>                                     </del>	
	<u> </u>	1			
		<del>                                     </del>		<del>                                     </del>	
-		+		1	
<del></del> -		1		+ +	
	(inclu Grab Sample Taken During First 20	Maximum Values (include units)  Grab Sample Taken During First 20 Minutes  Flow-Weighted Composite	Grab Sample Grab Sample Taken During	Grab Sample Taken During First 20 Minutes  Flow-Weighted Minutes  Grab Sample Taken During First 20 Flow-Weighted Minutes  Composite  Grab Sample Taken During First 20 Flow-Weighted Minutes  Composite	Grab Sample Taken During First 20 Minutes  Flow-Weighted Composite  First 20 Minutes  Flow-Weighted Composite  First 20 Minutes  Flow-Weighted Composite  Flow-Weighted Composite  Flow-Weighted Composite  Flow-Weighted Composite  Flow-Weighted Composite

## Form 2F Supplemental Information

# Stormwater Drainage and Management (Form 2F – Sections IV.A, B and C)

The DCA facility maintains detailed programs to manage stormwater within the developed areas of the site, including the following:

- Stormwater Best Management Practices Plan (BMPP)
- Individual operating area procedures

#### Structural Control Measures

Structural controls at the DCA facility include a stormwater retention pond, an oil/water separator for stormwater in the fuel and oil storage area, sloped containment area for loading and unloading operations that drains to the oil/water separator, and covered areas for railcar loading/unloading (Figure 2). Stormwater runoff from the facility is also controlled by curbing, graded land surfaces, culverts, and drains that direct water to the stormwater retention pond (Figure 2). The runoff system prevents significant ponding of water on site and prevents erosion of downgradient areas. As such, stormwater runoff control structures at the facility are designed and maintained to prevent or minimize the release of contaminants that may result from facility operations.

There is minimal risk of stormwater being exposed to pollutant sources because most material storage, loading, and unloading occur inside buildings or under a covered structure. Secondary containment at material storage locations includes spill containment pallets for drums and containers. The facility stores diesel outdoors in double-walled, aboveground storage tanks that also have secondary containment.

Surface cover and natural ground cover prevent soil erosion at the facility. Surface cover in the process areas of the facility consists mostly of concrete, asphalt, and gravel. Vegetative cover at the facility is well established and is routinely maintained.

#### Nonstructural Control Measures

The following best management practices (BMPs) are used to implement stormwater measures and controls:

- Good housekeeping practices
- Routine preventive maintenance
- Routine visual inspections
- Spill Prevention, Control, and Countermeasure
- Stormwater BMPP
- Employee training
- Recordkeeping and reporting

### Stormwater Drainage

The DCA facility maintains detailed programs to manage stormwater within the developed areas of the site, including:

- Stormwater BMPP
- Individual operating area procedures

The drainage network on the site consists of a system of ditches that collects surface water runoff. Runoff from the facility's manufacturing process area flows into the facility's stormwater retention pond and discharges through Outfall DSN001 (Figure 3) to an unnamed tributary of Miller Creek. A new stormwater retention / equalization basin and stormwater treatment system will be constructed to replace the existing retention basin and will discharge stormwater (up to a 25-year, 24-hour event) through Outfall DSN004 to the Tallapoosa River. Some stormwater falls on the western and northern end (non-process area) of the facility, which sheet-flows into two separate drainage ditches before leaving the facility via Outfall DSN001.

The DCA property encompasses approximately 162 acres. The facility stormwater drainage area measures approximately 42 acres, with approximately 31 of those acres having some impervious surfaces.

## Narrative Description of Pollutant Sources – Potential Exposure to Stormwater (Form 2F – Section IV.B)

DCA has implemented BMPs to prevent stormwater contamination at the Mt. Meigs facility. BMPs are presented in the facility Stormwater BMPP. Significant materials stored at the facility include new and used equipment wash solvents, new and used motor oil (tanks), diesel fuel (tanks), hydraulic fluid (drums), transmission fluid (drums), and mineral oil/Quintolubric 888-68 (drums). Wastes stored at the facility include used motor oil, used hydraulic fluid, used transmission fluid, and used mineral oil/Quintolubric 888-68, which are stored in drums. Also, a small amount universal waste, miscellaneous waste, silica fume waste, and general (household) waste are stored at the facility. Used motor oil, fluids, mineral oil, and solvents are removed by licensed waste disposal contractors. Most significant materials are stored under roof to minimize contact with stormwater. New and used oils and hydrocarbon fluids are maintained in accordance with the facility's Spill Prevention, Control, and Countermeasure plan.

Garbage dumpsters and garbage cans are located throughout the facility. The dumpsters and garbage cans may contain garbage and other refuse that produces pollutants if exposed to stormwater. Good housekeeping procedures are implemented to reduce the potential of stormwater pollution.

There are no hazardous wastes generated, stored, or disposed of at the Mt. Meigs facility.

### Herbicides and Pesticides (Form 2F – Section IV.B)

DCA contracts licensed applicators of conventional herbicides and pesticides at specific intervals for site maintenance and landscaping at the Mt. Meigs facility.

Herbicides are applied throughout site operational areas, as needed, and only in minimal amounts required to control weeds within the operational areas, roadways, and ditches. Only commercially available products are used and applied in a manner and at rates consistent with the registered usages for the specific herbicide selected, as required by the Federal Insecticide, Fungicide, and Rodenticide Act (FIFRA).

Pesticides are applied as needed for routine pest control. Only commercially available products are used and applied in a manner and at rates consistent with the registered usages for the specific pesticides selected, as required by FIFRA.

AX0601181110MGM 2



Feet

07 2019 JACOBS

IND. M'UN BRANCH

#### Jackson, Scott A

#### Subject:

RE: Updated Antidegradation Analysis for DC Alabama Permit Modification

From: Sisk, Lynn/MGM < Lynn. Sisk@jacobs.com>

Sent: Thursday, June 13, 2019 5:46 PM

To: Jackson, Scott A <scott.jackson@adem.alabama.gov>

Cc: Brockington, Shawonda (S) <SBrockington@dow.com>; Martin, J.P./MGM <J.P.Martin@jacobs.com>; Powers,

Martin/SEA < Martin.Powers@jacobs.com>

Subject: Updated Antidegradation Analysis for DC Alabama Permit Modification

#### Scott,

I have attached a revised antidegradation analysis for the DC Alabama NPDES permit modification request. Let me know if you have questions or need additional information.

Thanks.

Lynn Sisk, P.E. Jacobs Technologist | BIAF 334.215.9060 334.467.6284 mobile 334.273.7504 fax Lynn.Sisk@jacobs.com

www.jacobs.com

NOTICE - This communication may contain confidential and privileged information that is for the sole use of the intended recipient. Any viewing, copying or distribution of, or reliance on this message by unintended recipients is strictly prohibited. If you have received this message in error, please notify us immediately by replying to the message and deleting it from your computer.



### Technical Memorandum

4121Carmichael Rd, Suite 400 Montgomery, AL 36106 United States T +1.334.271.1444 F +1.334.277.5763 www.jacobs.com

Subject

Antidegradation Evaluation for DC Alabama, Inc., Mt. Meigs, Alabama

To

DC Alabama, Inc. (DC Alabama)

From

Lynn Sisk/Jacobs Engineering Group (Jacobs)

Date

June 14, 2019

Copies To

J.P. Martin/Jacobs

Martin Powers/Jacobs

Shawonda Brockington/DC Alabama

Project No:

DWMTM005

#### **Purpose**

The purpose of this Technical Memorandum (TM) is to fulfill the requirements of the Alabama Department of Environmental Management (ADEM) Administrative Code Rule 335-6-10, Water Quality Criteria, requiring the completion of an antidegradation evaluation for DC Alabama, Inc (DCA) for the modification of National Pollutant Discharge Elimination System (NPDES) Permit AL0083763. This evaluation is related to the proposed discharge of treated process wastewater and stormwater.

#### DC Alabama Facility Summary

The DCA facility is located at 1940 Ohio Ferro Road in Mt. Meigs, Montgomery County, Alabama. The facility's standard industrial classification code is 3313. The facility produces silicon metal used in chemical and aluminum products. The facility also produces silica fume, which is used as a strengthener and filler by the concrete and refractory industries. The manufacturing process includes melting raw materials (silica rock, coal, charcoal, and wood chips) in an electric arc furnace to produce molten silicon metal which is cast as ingots. The ingots are crushed before being packaged for shipping. Silica fume captured by the facility's air pollution control equipment have historically been conveyed through a recirculated water stream and placed in a silica fume slurry pond. However, DCA has modified its silica fume handling procedures so that the material is no longer being sent to the slurry pond. DCA is constructing a water treatment system to treat the water in the slurry pond and discharge it through Outfall DSN004 until the slurry pond is completely dewatered. In addition, a new stormwater sedimentation basin and treatment system is being constructed to treat stormwater runoff from the manufacturing process area of the facility. The stormwater sedimentation basin will discharge through Outfall DSN004 for 24-hour storm events with a return frequency up to 100 years. An emergency spillway in the sedimentation basin will discharge to the unnamed tributary to Miller Creek during 24-hour storm events with a return frequency of greater than 100 years. This updated antidegradation analysis reflects the new discharge of treated stormwater at Outfall DSN004 as described in the NPDES permit modification application submitted to ADEM on April 26, 2019.



#### **Economic and Social Development**

The following section responds to the question in Section 335-6-10-.12 related to economic and social development.

- 1) What environmental or public health problem will the discharger be correcting?
  - This discharge will prevent inadvertent overflow of water outside of the slurry pond and reduce the discharge of stormwater from the manufacturing area to the unnamed tributary to Miller Creek.
- 2) How much will the discharger be increasing employment (at its existing facility or as the result of locating a new facility)?
  - During the duration of the project implementation, DCA anticipates that approximately 25 contractors will be employed, depending on the phase of the project, to assist with engineering, operation, and other project work.
- 3) How much reduction in employment will the discharge be avoiding?
  - The site currently employs approximately 200 Dow and contract employees. There is no anticipated reduction in employment.
- 4) How much additional state or local taxes will the discharger be paying?
  - The new treatment process and discharge would create an estimated \$30,000 in local and state taxes.
  - There will also be an increase in local and state taxes generated from spending on machinery and equipment and construction wages.
- 5) What public service to the community will the discharger be providing?
  - DCA will continue to provide job training for employees which contributes to a skilled workforce.
  - DCA is committed to supporting the communities in which their facilities operate. DCA employees support the local community through various service activities.
- 6) What economic or social benefit will the discharger be providing to the community?
  - Though not possible to estimate at this time, there will be an economic benefit experienced through the treatment and discharge of the slurry pond water and stormwater because of spending on machinery and equipment, construction activities, and construction wages. This work will create spending in the local area and will increase tax revenue for both the local and state economy.

#### **Outfalls and Discharged Water Overview**

Proposed outfall discharges are described below:

#### DSN002/004

This is the proposed process wastewater outfall location for the discharge of treated slurry pond water
to prevent pond overflow and provide for pond dewatering during the pond closure process. The
effluent would be discharged to the Tallapoosa River or to an unnamed tributary to Miller Creek.
Outfall DSN004 will also discharge treated stormwater runoff from the facility's stormwater
sedimentation basin.

#### **Discharge Alternative Evaluation**

This discharge alternative evaluation compares the technical aspects and the costs of the potential discharge alternatives of the treated process waters from DCA's site. The same alternatives would apply whether discharge is to the Tallapoosa River or the unnamed tributary to Miller Creek. Alternates required by Chapter 335-6-10 along with potential other disposal alternatives are detailed in following sections.



#### Alternative 1: Land Application

- Land application is not technically feasible. The total potential volume of water requiring disposal
  would require an application site larger than is readily available to the facility.
- Based on soil survey reports, the soil at and near the facility location has limited water absorption
  qualities making land application infeasible
  (https://websoilsurvey.sc.egov.usda.gov/App/WebSoilSurvey.aspx).
- Review of data from other sites in proximity to the DCA property indicates groundwater is very shallow at the site (i.e., generally less than 10 feet). ADEM requirements typically prohibit land application of industrial wastewater at such sites.

#### Alternative 2: Pretreatment/Discharge to Publicly Owned Treatment Works (POTW)

- The Montgomery Water Works and Sanitary Sewer Board (MWWSSB) has a small treatment plant located near the plant site. The plant is currently very underloaded as it is in an area of the City that has not been developed. Thus, there is little sanitary treatment flow and DCA wastewater, which is very low in biochemical oxygen demand and organics, likely would not be treatable in the lightly loaded treatment plant.
- Discharging to a larger POTW, such as the MWWSSB Econchate Wastewater Treatment Facility was
  determined to be infeasible due to the cost of pumping and/or trucking the slurry pond water from the
  DCA facility to the nearest MWWSSB pump station. A more complete analysis of this alternative is
  attached.

#### Alternative 3: Relocation of Discharge

This alternative is not a relevant option as this is a new discharge.

#### Alternative 4: Reuse/Recycling

The slurry pond water does not have a purpose to be reused and therefore must be discharged to
prevent overflow of the slurry pond.

#### Alternative 5: Process/Treatment Alternatives

 DCA has determined that long-term management of silica fume will not include the use of the slurry pond for silica fume storage. As such, DCA has committed to close the slurry pond and convert a portion of the area to a constructed wetland system for long-term treatment of process stormwater. However, there is no process alternative that will allow for the complete dewatering of the pond.

#### Alternative 6: Subsurface disposal

 The groundwater table at the site is very shallow, and the slurry pond water and process stormwater contain metals concentrations which make this alternative economically and environmentally infeasible. To provide protection of the groundwater that serves multiple uses for areas surrounding DCA, an advanced water treatment system would be required to meet the water quality limits for the injection system.

#### Alternative 7: Treatment and Discharge to the Tallapoosa River or Unnamed Tributary to Miller Creek

• Treatment of the slurry pond water and process stormwater will include polymer flocculation and advanced solids capture technology to meet the surface water discharge limits. This is the most economically feasible alternative. This is also the most efficient alternative to ensure compliance with environmental regulations. This is the viable alternative available for the discharge of the treated slurry pond water and process stormwater to surface water. With proper operation of the treatment process equipment, monitoring of the outfalls, and source discharge control, water quality will be protected. Upon detailed design, should an alternative solution with a better economic and environmental profile be developed, then that option would be pursued. Upon completion of the slurry pond closure and construction of the wetlands treatment system, all discharges through Outfall DSN004 to the Tallapoosa River will be terminated.





Of the alternatives that were evaluated, a discharge to nearby surface waters is the only alternative that is technically and economically feasible.

#### **ALTERNATIVE ANALYSIS**

Applicant/Project: DC Alabama, Inc.

All new or expanded discharges (except discharges eligible for coverage under general permits) covered by the NPDES permitting program are subject to the provisions of the antidegradation policy. Applicants for such discharges to Tier 2 waters are required to demonstrate "... that the proposed discharge is necessary for important economic or social development." As a part of this demonstration, the applicant must complete an evaluation of the discharge alternatives listed below, to include calculation of total annualized project costs for each technically feasible alternative using the attached worksheets (Worksheet B for public-sector projects and Worksheet R for private-sector projects). Alternatives with total annualized project costs that are less than 110% of the total annualized project costs for the Tier 2 discharge proposal are considered viable alternatives.

Alternative	Viable	Non- Viable	Comment
1. Land Application		х	Shallow groundwater at the site and metals concentrations in the wastewater prohibit this disposal option.
2. Pretreatment/Discharge to POTW		x	Current POTW technology does not support the chemical profile of the water that needs to be treated
3. Relocation of Discharge		х	Not applicable. This is a new discharge.
4. Reuse / Recycle		x	Silica fume is no longer being sent to the slurry pond.
5. Process/Treatment Alternatives		х	Full evaporation of accumulated water is not feasible. Pond closure requires complete dewatering of the pond.
On Site/Subsurface, combination of above or other disposal alternatives.		х	Shallow groundwater at the site and metals concentrations in the wastewater prohibit this disposal option.
7. NPDES Discharge to surface water	x		This is the viable alternative to discharge the treated process wastewater. With proper operation of the treatment equipment, monitoring of the outfalls, and source discharge control, water quality will be protected.

Pursuant to ADEM A	dministrative Co	de Rule 335-6-3	.04, I certify on behalf	of the applicant t	hat I have compl	eted an evaluation of the
discharge alternatives						
		1 1				

Signature:

Professional Engineer

Date:

(Supporting documentation to be attached, referenced, or otherwise handled as appropriate.) See Attachments.

#### WORKSHEET R

## Calculation of Total Annualized Project Costs for Private-Sector Projects DCA Mt. Meigs, Alabama

Capital Cost to be Financed (Supplied by Applicant)	<u>N</u> A	(1)
Interest Rate for Financing (expressed as decimal)		
	NA	(i)
Time Period of Financing (in years)		
	<u>N</u> A	(n)
Annualization Factor = 1+ i		
$(1+i)^n-1$	<u>N</u> A	(2)
Annualized Capital Cost [Calculate: (1) x (2)]	<u>NA</u>	(3)
Annual Costs of Operation and Maintenance		
(including but not limited to: monitoring, inspection, permitting fees,		
waste disposal charges, repair, administration and replacement.)	<u>\$225,000</u>	<u>(4)</u>
Total Annual Cost of Pollution Control Project [(3) + (4)]		
	\$225,00	0 (5)

#### FOR DEPARTMENT USE ONLY

### **DOCUMENTATION OF ANTIDEGRADATION REVIEW**

Applicant/Project:			
Ala	abama's antidegradation policy is found in rule 335-6-1004 of the ADEM Administrative de, and addresses three categories of waters/uses:		
•	high quality waters that constitute an outstanding national resource (Tier 3), waters where the quality exceeds levels necessary to support propagation of fish, shellfish, and wildlife and recreation in and on the water (Tier 2), and existing instream water uses and the level of water quality necessary to protect the existing uses (Tier 1).		
per ant der	new or expanded discharges (except discharges eligible for coverage under general mits) covered by the NPDES permitting program are subject to the provisions of the didegradation policy. Applicants for such discharges to Tier 2 waters are required to monstrate " that the proposed discharge is necessary for important economic or social velopment" as a part of the permit application process.		
	nsideration of Tier 2 provisions is documented below (this completed form will be placed he permit file):		
1.	Is the application for a new or expanded discharge?YesNo (If yes, go to item 2; if no, antidegradation review is not required.)		
2.	Is the receiving stream considered to be a Tier 3 water?YesNo (If yes, refer to ONRW provisions at 335-6-1010; if no, go to item 3.)		
3.	Is the receiving stream considered to be a Tier 1 water? YesNo (If yes, refer to Tier 1 provisions at 335-6-1004(2); if no, go to item 4.)		
4.	Is the receiving stream considered to be a Tier 2 water?YesNo (If yes, go to item 5.)		
5.	Has the applicant submitted a completed <i>Alternatives Analysis</i> checklist? YesNo (If yes, go to item 6.)		
6.	Has the applicant submitted information demonstrating that the proposed discharge will accommodate important economic or social development? Yes No (If yes, all information needed for the antidegradation review is available.)		
acc An	e information submitted by the applicant demonstrating that the proposed discharge will commodate important economic or social development and the completed <i>Alternatives</i> alysis checklist will be placed in the permit file, and utilized by the Department in making a remination regarding permit issuance.		
Co	mpleted Bv: Date:		

## Supplemental Antidegradation Analysis for DC Alabama, Inc. NPDES Permit Application

Antidegradation Analysis - Discharge to the Econchate WWTP

There are two options for discharging pretreated slurry pond wastewater and process stormwater to a larger POTW within the Montgomery Waterworks and Sanitary Sewer Board's (MWWSSB) service area (Econchate WWTP). The first option will require the construction of a pump station with a maximum capacity of 500,000 gallons per day and approximately 24,000 feet (4.5 miles) of force main to reach the Econchate WWTP interceptor line near Jenkins Creek / I-85. The system will include wastewater treatment to remove solids prior to discharge to a 0.5 MGD pump station. The pump station will pump the treated wastewater through a 24,000-foot force main to the Econchate WWTP interceptor line located adjacent to Jenkins Creek on the north side of I-85. This scenario will require easements from Montgomery County and from the State of Alabama. Discharging to the MWWSSB collection system will also require permits / fees from ADEM and MWWSSB. This treatment option is not feasible because of the extensive infrastructure required and the time required to obtain easements and design / construct the wastewater treatment system, pump station, and force main.

Option #1 – Pump pretreated wastewater from DC Alabama, Inc. to Econchate WWTP Interceptor Line near I-85.

- Infrastructure / Construction Requirements:
  - Wastewater pretreatment system solids separation and handling, monitoring
  - 0.5 MGD effluent pump station to pump pretreated wastewater to Econchate WWTP interceptor line (assumes only one station will be needed)
  - Force main from pump station at DC Alabama to Econchate WWTP interceptor line
     approximately 24,000 feet
- Regulatory Requirements:
  - o Purchase right-of-way easements from Montgomery County and State of Alabama
  - o Obtain SID permit from ADEM (includes application and fee)
  - Obtain MWWSSB approval to tap into Econchate WWTP Interceptor Line at Jenkins Creek / 1-85 (includes application and fee)

The second option for discharging pretreated slurry pond wastewater and process stormwater to a larger POTW within the MWWSSB service area will require the construction of a wastewater treatment system to pretreat the wastewater to remove solids. The treated wastewater will be stored in large tanks at the DC Alabama facility until it is carried by tanker trucks to the Econchate WWTP. Tanker trucks have a capacity to carry approximately 7500 gallons. The wastewater flow rate is projected to average 200,000 gallons per day. For safety reasons, hauling of wastewater will be restricted to weekdays only between the hours of 9:00 am and 3:00 pm. This schedule results in 1,400,000 gallons per week to be hauled by truck to the Econchate WWTP. The daily volume to be hauled from Monday through Friday is 280,000 gallons. Assuming that a tanker truck will require 2.5 hours to fill the tank, drive to the Econchate WWTP from the DC Alabama facility, empty the tank at the WWTP, and return to DC Alabama for the next load, this scenario will require 16 tanker trucks per day to haul 280,000 gallons from DC Alabama to the Econchate WWTP. This scenario will also require construction of the necessary wastewater storage and pumping facilities at DC Alabama for filling the tanker trucks. This option also assumes that the MWWSSB would approve the transport of treated wastewater to the Econchate WWTP using this number of large tanker trucks over the course of a 6-hour time period each week day. This treatment option is not feasible because of the large number of tanker trucks needed to transport the pretreated wastewater safely to the Econchate WWTP.

Option #2 -- Truck pretreated wastewater from DC Alabama to Econchate WWTP

- Infrastructure / Construction Requirements:
  - Wastewater pretreatment system solids separation and handling, monitoring, holding / storage tanks
  - Tanker truck loading facility concrete pads / aprons, pumps from storage / holding tanks (750,000-gallon capacity)
  - o Stormwater / spill collection system
  - o Trucks (leased / contract) 7,500-gallon capacity each
    - To reduce potential for accidents, restrict hauling times to between 9:00 am and 3:00 pm (6 hours) on weekdays
    - 0.2 MGD x 7 days = 1,400,000 galions per week = 280,000 galions per day Monday - Friday
    - 38 truck-trips / 6 hours = 6.3 truck-trips per hour
    - Assume 2.5 hours to fill the tanker truck, drive to Econchate WWTP, empty the truck, and return to DC Alabama
    - 6.3 truck-trips per hour x 2.5 hours = 16 trucks required
- Regulatory Requirements:
  - o Obtain SID permit from ADEM (includes application and fee)
  - Obtain MWWSSB approval to empty 16 tanker trucks per day of pretreated wastewater at the headworks of the Econchate WWTP (includes application and fee)